NOAA FORM 76-35

U.S. DEPARTMENT OF COMMERCE
NATIONAL OCEANIC AND ATMOSPHERIC ADMINISTRATION
NATIONAL OCEAN SURVEY

DESCRIPTIVE REPORT

Type of Survey Shoreline
Job NoPH-6013 Map No I-12002
Classification No. Final Map Edition Nol
Ta .
LOCALITY
State Alaska Cook Inlet General Locality Kalgin Island to Anchorage Locality Susitna Flats
19 66 TO 19 74
REGISTRY IN ARCHIVES

☆ U.S. GOVERNMENT PRINTING OFFICE: 1972-761-152

NOAA FORM 76-36A (3-72)	U. S. DEPARTMENT OF COMME NATIONAL OCEANIC AND ATMOSPHERIC AD	RCE MIN.	TYPE OF SURVEY	SURVEY	(R-T-12002
		. 🛭	ORIGINAL	MAP EDITION	оn no. (¹)
DESCRIPT	TIVE REPORT - DATA RECORD		RESURVEY	MAD CLASS	Final Map
DESCRIP	TIVE REPORT - DATA RECORD				. 6013
PHOTOGRAMMETRIC O	DEFICE	 	<u> </u>		
			LAST PRECEED	ING MAP EDIT	TION
Coastal Mappin		ì	TYPE OF SURVEY	JOB E	PH
<u>Atlantic Marir</u>	ne Center, Norfolk, VA	(¤	ORIGINAL,	MAP CLASS	i
OFFICER-IN-CHARGE			RESURVEY	SURVEY D	ATES:
			REVISED	19 70 15	•
Jeffrev G. Car	rlen. Cdr.	-			
I. INSTRUCTIONS DA					
	1. OFFICE		2.	FIELD	
1	0/2////	4	ield		6/6/66 8/8/66
Aerotriangula			upplement 1		8/8/66
Compilation,	Supplement 3 4/26/	67 J	•		
Compilation, S	Supplement 4 9/11/	67			
	,, ,	·			
ļ		1			
		1			
II. DATUMS					
		ОТН	ER (Specify)		
1. HORIZONTAL:	X 1927 NORTH AMERICAN				
<u> </u>		ОТН	ER (Specify)	 -	·
	MEAN HIGH-WATER		a (apocity)		
2. VERTICAL:	MEAN LOW-WATER				
	MEAN LOWER LOW-WATER				
	MEAN SEA LEVEL				
3. MAP PROJECTION			4.	GRID(S)	
	D-3	STA	TE Aleelee	ZONE	,
]	Polyconic		Alaska	1	4
5. SCALE		5TA	TE	ZONE	
<u>[</u>	1:20,000			}	
III. HISTORY OF OFF	ICE OPERATIONS				
	OPERATIONS		NAME		DATE
1. AEROTRIANGULAT	FION	ву Р	Hawkins		Apr 1967
į.	eoplanigraph LANDMARKS AND AIDS				
2. CONTROL AND BR			Ctainhann		Feb 1968
		— 	. Steinberg . E. Serena	· · · · · · · · · · · · · · · · · · ·	Feb 1968
Man	<u> </u>				
3. STEREOSCOPIC IN				<u>. </u>	Jun 1973
COMPILATION	CHECKER				Jun 1973
1	Kelsh and Wild B-8 contours				
scale: 1:20	,000 CHECKED				
4. MANUSCRIPT DELI	NEATION PLANIMETRY	ву L	. O. Neterer,_J:	r	Jun 1973
	CHECKED	вч \overline F	. Margiotta		Jun 1973
g	CONTOURS	BY N	1		
метнор: Smoo	thdrafted contours	— 			
	HYDRO SUPPORT DATA			r .	Jun 1973
scale: 1:20	,000 CHECKED				Jun 1973
& AFFICE INCORP.	·	— -		 -	
3. OFFICE INSPECTIO	ON PRIOR TO FIELD EDIT				Jun 1973
6. APPLICATION OF	FIELD EDIT DATA	BY	. Perkinson		Jul 1975
	CHECKED	BY A	. C. Rauck, Jr.		Aug 1975
7. COMPILATION SEC	TION REVIEW	ву Д	. C. Rauck, Jr.		Aug 1975
8. FINAL REVIEW		BY J.	Byrd/C. Blood		May 1986
9. DATA FORWARDED	TO PHOTOGRAMMETRIC BRANCH	вч ј.	Byrd		Sépt 1986
10. DATA EXAMINED I	N PHOTOGRAMMETRIC BRANCH		Dempsen		Oct. 1986
11. MAP REGISTERED	- COASTAL SURVEY SECTION	BY F	L. DAVA HER-		Dac 86

NOAA FORM 76-36B (3-72)	·····		N	ATIONAL OCEA				OF COMMERC
	_	T-12	2002					OCEAN SURVE
	cc	MPILATIO	ON SOU	RCES				
1. COMPILATION PHOTOGRAPHY								
CAMERA(S)		TYPI	ES OF PH	OTOGRAPHY				
Wild RC-8"L"		_]	LEGI	END		TIME	REFERI	
TIDE STAGE REFERENCE		(c) co	LOR		ZONE			
PREDICTED TIDES		X (P) PA		ATIC		Alaska		STANDAR
REFERENCE STATION RECORDS	нү	(I) IN	FRARED		MERIC			DAYLIGH.
				00415	 -	150th	GE OF T	105
NUMBER AND TYPE	DATE	TIM	E	SCALE	 -	SIA	GE OF I	IDE
66 L 6677 - 66 L 6680	8/14/66	08:4	2	1:40,00	0 2.6	ft.a	bove 1	MLLW
							<u>.</u>	
REMARKS								
2. SOURCE OF MEAN HIGH-WATER L	INC.			· -				
graphy.								
2 SOURCE OF HEAD HAD WITE O	PHEAN LOWER	OW WATER	LINE					
3. SOURCE OF MEAN LOW-WATER O	MEAN LOWER I	LUW-WAIEK	LINE:					
The mean lower low wat	er line wa	s compil	ed fro	om the abo	ve list	ted ph	otogra	aphy.
						-	1	<u>-</u>
4. CONTEMPORARY HYDROGRAPHIC	SURVEYS (List	only those s	surveys th	at are sources fo	r photogra	mmetric s	urvey inf	ormation.)
SURVEY NUMBER DATE(S)	SURVEY Co	OPY USED	SURVE	YNUMBER	DATE(S)		SURVEY	COPY USED
5. FINAL JUNCTIONS			1.2.			T		
NORTH EA	CM-121		SOUTH			WEST		
	-12006(2) (1:10,000	1	T-12013		1	T <u>-1200</u>)1
REMARKS					•			

NOAA FORM 76-36C (3-72)	T-12002 History of Field		S AND ATMOSPHER	MENT OF COMMERCE RIC ADMINISTRATION NAL OCEAN SURVEY
I. X FIELD INSPECTION OP	ERATION FIEL	D EDIT OPERATION		
	PERATION	NA	ME	DATE
1. CHIEF OF FIELD PARTY				1.161. 216
	RECOVERED BY	A. Wardwell G. Saladin		4/61 - 7/6 4/61 - 7/6
2. HORIZONTAL CONTROL	ESTABLISHED BY	None		
	PRE-MARKED OR IDENTIFIED BY	None		
,	RECOVERED BY	NA		
3. VERTICAL CONTROL	ESTABLISHED BY	NA		
_ <u></u>	PRE-MARKED OR IDENTIFIED BY	NA		
	RECOVERED (Triangulation Stations) BY	None		_
4. LANDMARKS AND AIDS TO NAVIGATION	LOCATED (Field Methods) BY	None		
	TYPE OF INVESTIGATION	None		
	COMPLETE			
5. GEOGRAPHIC NAMES INVESTIGATION	SPECIFIC NAMES ONLY			
	NO INVESTIGATION	ĺ		
6. PHOTO INSPECTION	CLARIFICATION OF DETAILS BY	None		
7. BOUNDARIES AND LIMITS	SURVEYED OR IDENTIFIED BY	NA NA		-
II. SOURCE DATA				
I. HORIZONTAL CONTROL ID	ENTIFIED	2. VERTICAL CONT	ROL IDENTIFIED	
None		NA		<u> </u>
PHOTO NUMBER	STATION NAME	PHOTO NUMBER	STATION DI	ESIGNATION
3. PHOTO NUMBERS (Claritica) None	tion of details)			
4. LANDMARKS AND AIDS TO None	NAVIGATION IDENTIFIED			
PHOTO NUMBER	OBJECT NAME	PHOTO NUMBER	OBJEC.	TNAME
5. GEOGRAPHIC NAMES:	REPORT NONE	6. BOUNDARY AND I	IMITS: REP	ORT K NONE
7. SUPPLEMENTAL MAPS AND		10. 200.000 1 800 1		Z. K. J. ROBE
None				
	ketch books, etc. DO NOT list data submit	ted to the Geodesv Divis	sion)	
None		A THE COVERED STATE	'	

OAA FORM 76-36C -72}	T-1200 HISTORY OF FIELD		NIC AND ATMOSPHER	ENT OF COMMERCI IC ADMINISTRATION IAL OCEAN SURVEY
. 💢 FIELD INSPECTION O	PERATION Premarking TIELI	D EDIT OPERATION		<u> </u>
	OPERATION		NAME	DATE
. CHIEF OF FIELD PARTY		D M 11		30//
		R. Melby None	·	1966
. HORIZONTAL CONTROL	RECOVERED BY	R. Melby		1966
, HONIZONIAL CONTROL	PRE-MARKED OR IDENTIFIED BY	None		1900
<u> </u>	RECOVERED BY	NA		
. VERTICAL CONTROL	ESTABLISHED BY	NA		
	PRE-MARKED OR IDENTIFIED BY	NA		
	RECOVERED (Triangulation Stations) BY	None		
LANDMARKS AND	LOCATED (Field Methods) BY	None		
AIDS TO NAVIGATION	IDENTIFIED BY	None_		
	TYPE OF INVESTIGATION	1		1
GEOGRAPHIC NAMES INVESTIGATION	COMPLETE BY			
INVESTIGATION	SPECIFIC NAMES ONLY			
	NO INVESTIGATION	None		+
PHOTO INSPECTION	CLARIFICATION OF DETAILS BY	None NA		
, BOUNDARIES AND LIMIT: 1. SOURCE DATA	SURVEYED OR IDENTIFIED BY	I III		
. HORIZONTAL CONTROL	IDENTIFIED	2. VERTICAL CO	NTROL IDENTIFIED	
Non	ne		NA	
PHOTO NUMBER	STATION NAME	PHOTO NUMBER	STATION DE	SIGNATION
. PHOTO NUMBERS (Clariff	cation of details)	<u> </u>		
No	one			
4. LANDMARKS AND AIDS T	O NAVIGATION IDENTIFIED			
No	one			
PHOTO NUMBER	OBJECT NAME	PHOTO NUMBER	OBJECT	NAME
S. GEOGRAPHIC NAMES:	REPORT NONE	6. BOUNDARY AN	ID LIMITS: REPO	RT X NONE
. SUPPLEMENTAL MAPS A	ND PLANS			
No	one			
	(Sketch books, etc. DO NOT list data submit	ted to the Geodesy D	livision)	
No	one			


NOAA FORM 76-36C

(3-72)	Ψ _ 3:		NIC AND ATMO	PARTMENT OF COMMERCE DSPHERIC ADMINISTRATION NATIONAL OCEAN SURVEY
	HISTORY OF FIELD	OPERATIONS		
.I. TIELD INSPECTION	ON OPERATION TIPE	D EDIT OPERATION		
	OPERATION	N	NAME	DATE
1. CHIEF OF FIELD PA	RTY	K. W. Jef	PANG	May - Aug 1974
	RECOVERED BY	None None	1619	
2. HORIZONTAL CONT		None	,	
	PRE-MARKED OR IDENTIFIED BY	None		
	RECOVERED BY	NA		•
3. VERTICAL CONTROL	L ESTABLISHED BY	NA		
	PRE-MARKED OR IDENTIFIED BY	NA		
	RECOVERED (Triangulation Stations) BY	None		
4. LANDMARKS AND AIDS TO NAVIGATIO	LOCATED (Field Methods) BY	None		
AIDS TO ARTIS.	IDENTIFIED BY	None		
	TYPE OF INVESTIGATION			-
5. GEOGRAPHIC NAMES INVESTIGATION	BY			
*** V 1.0 * 1.0 * 1	SPECIFIC NAMES ONLY			
TO WEDECTION	Y NO INVESTIGATION	- Ct-nob1		4 107/
7 BOUNDARIES AND I		G. Strobl	<u>.e</u>	Aug 1974
7. BOUNDARIES AND L	IMITS SURVEYED OR IDENTIFIED BY	L NA	-	<u> </u>
I. HORIZONTAL CONTI	ROL IDENTIFIED	2. VERTICAL CON	TROL IDENTI	FIED
	None		NA	
PHOTO NUMBER	STATION NAME	PHOTO NUMBER		TION DESIGNATION
3. PHOTO NUMBERS (C	•			-
THE PURE AND AL	None			
4. LANDMARKS AND AL	IDS TO NAVIGATION IDENTIFIED			
	None			
РНОТО NUMBER	OBJECT NAME	PHOTO NUMBER		OBJECT NAME
	. .			
<u> </u>	·	1		
5. GEOGRAPHIC NAMES	S: REPORT MONE	6. BOUNDARY AND	D LIMITS:	REPORT X NONE
7. SUPPLEMENTAL MA	PS AND PLANS			
R. OTHER FIELD RECO	None PRDS (Sketch books, etc. DO NOT list data submi-	tted to the Geodesy Di	ivision)	
• • • • • • • • • • • • • • • • • • •	l field edit ozalid l field edit report	,	Ylajon,	

(3-72)	M 76-36D	RECOI	NATIONAL OCEANIC T-12002 RD OF SURVEY USE	U. S. DEPARTMEN AND ATMOSPHERIC	IT OF COMMERCE ADMINISTRATION
. MANUSC	RIPT COPIES				
		MPILATION STAGE	s	DATE MANUSCRI	PT FORWARDED
	DATA COMPILED	DATE	REMARKS	MARINE CHARTS	HYDRO SUPPOR
	lation complete,	6/3/73	Class III manuscript	None	6/14/73
	edit applied. Lation complete.	8/75	Class I manuscript	None	8/06/75
Final	Review	5/86	Final Map		
	ARKS AND AIDS TO NAVIGA		DATA BRANCH		
NUMBER	CHART LETTER NUMBER ASSIGNED	DATE FORWARDED		MARKS	
		!			
		1			
		 			

A.	SURCE DATA (except for Geogra CCOUNT FOR EXCEPTIONS: ATA TO FEDERAL RECORDS (II, NOAA FORM 76-	36C.
IV. SURVEY	EDITIONS (This section shell	be completed each time a new m	ap edition is i	registered)	
	SURVEY NUMBER	JOB NUMBER			SURVEY
SECOND	TP(2)	′ PH •		REVISED	RESURVEY
EDITION	DATE OF PHOTOGRAPHY	DATE OF FIELD EDIT	7	MAP	CLASS
			<u>□</u> n.	□m. □iv.	□V. □ FINAL
	SURVEY NUMBER	JOB NUMBER		TYPE OF	SURVEY
THIRD	TP(3)	PH)	REVISED	RESURVEY
EDITION	DATE OF PHOTOGRAPHY	DATE OF FIELD EDIT	7	. MAP C	CLASS
			n		□V. □FINAL
<u> </u>	SURVEY NUMBER	JOB NUMBER			SURVEY
FOURTH	TP(4)	PH	}	REVISED	RESURVEY
EDITION	DATE OF PHOTOGRAPHY	DATE OF FIELD EDIT	7	MAP	CLASS
	<u> </u>	<u> </u>] []n.	□ iii. □iv.	UV. OFINAL

1. [X] BRIDGING PHOTOGRAPHS; [X] DUPLICATE BRIDGING REPORT; [X] COMPUTER READOUTS.
2. [] CONTROL STATION IDENTIFICATION CARDS; [] FORM NOS 567 SUBMITTED BY FIELD PARTIES.



SUMMARY TO ACCOMPANY DESCRIPTIVE REPORT

T-12002

This 1:20,000 scale Final shoreline map is one of 44 maps designated as project PH-6013 Cook Inlet, Kalgin Island to Anchorage, Alaska.

The purpose of this map was to provide contemporary shoreline in support of hydrographic operations and to aid in chart revision.

Field work prior to compilation in the 1961 field season consisted of recovery of horizontal control and limited field inspection. Field work in 1966 consisted of premarking of horizontal control for aerotriangulation.

This area was photographed in August 1966 with the RC-8 "L" camera using panchromatic film at 1:40,000 scale.

Aerotriangulation was performed in the Washington office in April 1967.

This map was compiled at the Norfolk office in June 1973.

Field edit was performed for T-12002 during the 1974 field season. Field edit data was applied at AMC in August 1975.

Final review was performed at the Atlantic Marine Center in May 1986.

This Descriptive Report contains all pertinent information used to compile this Final Map. The original base manuscript and all related data were forwarded to the Washington Science Center for final registration.

FIELD INSPECTION REPORT

COOK INLET, ALASKA

PROJECT SP-1-61 1961

USC&GS Ship PATHFINDER

Arthur L. Wardwell, CAPT., Condg.

MANUSCRIPTS:-

12049, 12046, 12045, 12040, 12031, 12032, 12026, 12027, 12028, 12020, 12021, 12022, 12017, 12015, 12016, 12014, 12013, 12008, 12007, 12006, 12003, 12004, 12005, 12002, 12001, 12000, 12012, 11999, 12011, 11998, 12010, 12009, 12019, 12018, 12023, 12025, 12024, 12029, 12030, 12035, 12034, 12033, 12037, 12036

AERIAL FIELD INSPECTION:-

Areas inspected were as follows: Manuscripts No. 12049, 12046, 12045, 12040, Kenai to Boulder Point, all shoreline and alongshore features.

Balance of above listed manuscripts were used only for horizontal control identification.

The area is primarily moderately timbered with spruce, fir, alder and bear claw above the mean high water line. Shoreline varies from fine black silt at the mouth of the Kenai River mouth to large fragmented boulders at Boulder Point. Most of the beachline is sand and shingle interspersed with boulders of varying sizes. Numerous underground springs and some small creeks discharge small quantities of silt and water and are subject to constant change.

The area was inspected by cruising alongshore by launch and by walking the beach and bluff line. Foul areas now indicated on Chart No. 8553 are adequate. Two primary foul areas were noted as follows:

Kenai River Mouth

East Foreland to Moose Point

Quality of photographs was excellent. Areas of shadow were limited to the shoreline east of East Foreland and upper Knik Arm. No attempt was made to sketch in the mean high water line. Enough open areas in shadowed areas are available to adequately delineate mean high water line.

HORIZONTAL CONTROL:-

Four additional second-order triangulation stations were established between Kenai and East Foreland to supplement existing control in the area of hydrography. They were identified as follows:

AUDRY 1961 Manuscript No. 12049 Photo No. 1397
LOUISE 1961 " " 12049 " " 1402
BOO 1961 " " 12045 " " 1420
HELEN 1961 Traverse from East Foreland Light 1960.

Additional horizontal control recovery was made in upper Cook Inlet in accordance with project instructions. All stations were searched for and approximately 75 percent were recovered. Most of the stations not recovered are considered lost. It is recommended that the next vessel assigned to this project be given a Tellurometer. Simple traverse between recovered triangulation stations would adequately control presently un-controlled flight lines.

In many cases the listed triangulation station was not recovered and a U.S. Engineers' triangulation station was used as a substitute. It appears that the U.S. Engineers could not recover listed C&GS control and substituted their own stations.

Great assistance was rendered by the 5040 Air Transport Squadron at Elmendorf AFB in furnishing heliocopter service. Three days of flying enabled personnel to cover shoreline control stations over the greater part of upper Cook Inlet.

If additional control is required in the vicinity of Elmendorf AFB, use can be made of triangulation now being observed by a C&GS geodetic party. Triangulation station DORF 1961 (in the vicinity of LOOP 2) is to be set in the roof of a building on the base. By use of the description written by the observing party, an accurate office identification can be made.

Triangulation not plotted on the Photo Index was identified where it was on photographs. This control was established by G.W.M. in 1959 and H.G.C. in 1960.

VERTICAL CONTROL:-

None recovered or established.

CONTOURS AND DRAINAGE:-

No contouring was attempted.

Primary drainage features are the Kenai, Matanuska, Little Susitna, Susitna, Beluga, Kustitan, and Drift Rivers. Tidal sweep keeps some of the rivers from building up deltaic features. An extremely flat foreshore on the Matanuska, Little Susitna, Susitna and Beluga rivers give rise to wide deltas that change seasonally. Many small streams discharge around Cook Inlet but have no apparent seasonal change.

WOODLAND COVER:-

The major portion of the area is wooded and interspersed with muskeg and open grassy areas. These are easily identifiable on the photographs. In areas of increasing cultural activity, the woodland cover is being removed. No attempt was made to indicate these areas.

SHORELINE AND ALONGSHORE FEATURES:-

The mean high water line is adequately delineated on manuscripts 12049, 12046, 12045, 12040. In the area of photo hydro signals IVY and see EGG, east of East Foreland, the mean high water line is as follows:

IVY 30 meters inside MHW EGG on piles at MHW

Most of the shoreline signals are located at MHW along the beach. Many of the fishing huts set on piles at the base of the bluff were used as signals.

No attempt was made to delineate the low water line. Hydrography in the area should be satisfactory.

The foreshore area is primarily sand, small stones and boulders. The normal gradiation from stones at MHW to sand at MLW exists in all areas, except south of the Kenai River. In this area a heavy layer of silt is found in the tide zone.

OFFSHORE FEATURES:-

All offshore features are located by the hydrographer.

LANDMARKS AND AIDS:-

There are two fixed aids to navigation within the limits of the hydrographic project:

EAST FORELAND LIGHT

KENAI RIVER ENTRANCE RANGE

Both are located on Chart No. 8553.

One floating aid is also located on Chart No. 8553. Another can buoy is maintained by the oil company and is located just north of the pier.

One landmark for charts is recommended in the Descriptive Report for SP-1-61. This landmark is identified as follows:

KENAI TANK 1959, located by G.W.M. and identified on Photo No. 60w1400.

BOUNDARIES, MONUMENTS AND LINES:-

None shown.

OTHER CONTROL:-

Photo hydro signals were located in accordance with standard instructions. Signal IVY was found in error and relocated photogrammentrically, then verified by hydrographic cuts. Final location is shown on manuscript 12045.

Final location of photo hydro signals will remain in their relative position with the shoreline. Final compilation will cause a datum shift which will move both hydrography and signals the same relative amount.

DATUM DIFFERENCES:-

Radial plotting of photo identified control stations was made in the field. The following discrepancies were noted between plot positions and geographic positions.

EAST FORELAND LIGHT 1960	Lat.	-13.8 meters
•	Long.	-75.4 meters
BOULDER (USE)	Lat.	-37.0 meters
	•	-45.2 meters
KENAI CHURCH STEEPLE 1909	Lat.	-15.3 meters
	Long.	-23.6 meters

CULTURAL FEATURES:-

Numerous fishing shacks are located along high water line in the area of hydrography. These huts are subject to damage by winter storms and are in a constant state of transition. No attempt was made to locate current huts.

The Nikiski Oil Pier was under construction at the time of photography. The completed dimensions are available from a blueprint of the structure submitted with descriptive report for Project SP-1-61.

· Respectfully submitted,

Robert E. Williams, Lieut. Comdr., C&GS

Gerald C. Saladin ITJG, C&GS

Arthur J. Wardwell

Arthur L. Wardwell, Captain, C&GS

Comdg., Ship PATHFINDER

PHOTOGRAMMETRIC PLOT REPORT Job PH-6013 Cook Inlet, Alaska

April 13, 1967

21. Area Covered

The area covered by this report extends from the Redoubt Bay-East Foreland area to Anchorage, Alaska. Included in this area are T-sheets 11998 thru 12001, 12009 thru 12012, 12018, 12019; 12021, 12025 thru 12030, 12038, 12039, 12042 thru 12044, 12047, 12048 and 12987.

22. Method

Five strips were bridged on the C-8 and C-5 stereoplanigraph. Strip #1 (66-L-6602 thru 6623) was adjusted on four triangulation stations with tie points used as checks. Strip #2 (66-L-6629 thru 6634) was adjusted on two triangulation stations plus tie points from Strip #1. Strip #3 (66-L-6641 thru 6653) was adjusted on three triangulation stations plus ties. Strip #4 (66-L-6667 thru 6677) was adjusted on three triangulation stations plus 6725) was adjusted on three triangulation stations.

23. Adequacy of Control

The control, being premarked, was very good insofar as being able to see it clearly; however, in several cases, the 1:40,000 scale photography completely missed the stations. It should be noted that all strips were adjusted with minimum control, and as such, no positive proof can be provided that the adjustments are correct other than by means of tie points and residuals of adjustment. The tie points and residuals do indicate a good adjustment on all strips. Strip # had to be terminated at station SIT 1966 due to lack of control beyond this point. (Fort McKenzie could not be seen on the 1:40,000 scale photography.) Attempts were made to provide a tie point for the terminal station on the east end of this strip by bridging three models south of Anchorage, dropping points onto Strip #4. This met with complete failure. Strip #6 had to be terminated on the southern end at station GRAY CLIFF 1909 since the station at East Foreland was not covered by the 1:40,000 scale photography.

24. Supplemental Data

Local USGS quads were used to provide vertical control used in the bridging adjustment.

The coverage of 1966 photography falls short of being sufficient to show the shallow mud areas which are near lower-low water level in the area of the Susitna River Delta. To provide for the delineation of the limiting line of this feature, scale points have been selected which are common to 61M photography which does show the limiting line. Ratios of these photographs will be provided for the graphic delineation of the limiting line only. The compiler should select whatever additional points are necessary for correct delineation. A holiday exists on some of the shoreline along Strip #9. A flight of 60W photography provides coverage and three ratio photos were provided for compilation of this area.

All points on the bridged plates were drilled by PUG methods. Plate 66-L-6719 was broken after bridging. A new plate was provided but it does not contain any drilled points. It is suggested that the models on either side be compiled and pass points be dropped on this plate for compilation.

25. Photography

Photography was adequate as to definition and overlap but was not adequate as to coverage. The 1:40,000 scale photos did not cover either the shoreline or the marked control on the east end of Strip #4 or the southwest end of Strip #9. A portion of the shoreline along the part of Strip #9 which was bridged also lacks coverage.

Submitted Lawking AM

Paul Hawkins

√John D. Perrow, Jr.

<u>SUPPLEMENT</u>

PHOTOGRAMMETRIC PLOT REPORT Job PH-6013 Cook Inlet, Alaska

September 26, 1967

Strip #4 (66-L-6667 thru 6683) was readjusted using control station AUX, 1967. The results were adequate for completing T-sheets T-12002, T-12006 and T-12007.

17 77 MOON A 10						
(6~75)		DESCRIPTIV	CRIPTIVE REPORT CONTROL RECORD	NATIONAL OCEANIC AND ATMOSPHERIC ADMINISTRATION	ATMOSPHERIC ADM	INISTRATION
MAP NO.	JOB NO.		GEODETIC DATUM	ORIGINATING ACTIVITY		Cosetal Manning
T-12002	PH-6013	6	NA 1927	Division, N	್ಷ೦	ಶಿಗಾಗಿಗಳ
	SOURCE OF	AEROTRI-	COORDINATES IN FEET	POSITION		
STATION NAME	INFORMATION (Index)	POINT	STATE	φ LATITUDE λ LONGITUDE	REMARKS FORWARD	eks BACK
7700 ш10	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1		-χ	φ · 61 15 51.321	1588.6	(268.7)
700	onadjusted Field		±ħ			(334.4)
			±χ=	Ф		
			ĥ=	٧	1	
			=χ	ф		
			=ĥ	γ		
			=χ	φ		
			=h	γ		
			=χ	ф		
			=ħ	۲		
			=X	ф		
			y=	٧		•
			=X	ф		
			=ħ	У		
	i		-2χ	φ		
			<i>y</i> =	γ		
			χ=	ф		
			<i>y</i> =	γ		
			χ=	ф		
			y=	Υ.		
COMPUTED BY C. H. Bishop		DATE 4/21/67	COMPUTATION CHECKED BY		DATE	
H.H. Bishop		01/21/67	LISTING CHECKED BY		DATE	
HAND PLOTTING BY		DATE //00/67	HAND PLOTTING CHECKED BY		DATE	
		SUPERSEDES NO	SUPERSEDES NOAA FORM 76-41, 2-71 EDITION WHICH IS OBSOLETE.	H IS OBSOLETE.		

COMPILATION REPORT

T-12002

31. DELINATION:

Delineation was by the Wild B-8 and Kelsh stereoplotter, using 1:40,000 scale panchromatic photographs. Photography was adequate.

32. CONTROL:

See Photogrammetric Plot Report dated April 13, 1967.

33. SUPPLEMENTAL DATA:

None.

34. CONTOURS AND DRAINAGE:

Contours are inapplicable.

Drainage was delineated from office interpretation of the photographs.

35. SHORELINE AND ALONGSHORE DETAILS:

Alongshore details were delineated by the Wild B-8 and Kelsh stereoplotter and by offic interpretation of the photographs.

The mean high water line was delineated from the compilation photographs.

The mean lower low water line was also compiled from the $1966\ L$ photos.

36. OFFSHORE DETAILS:

None.

37. LANDMARKS AND AIDS:

No charted landmarks or aids were located during compilation.

38. CONTROL FOR FUTURE SURVEYS:

None.

39. JUNCTIONS:

See the attached Form 76-36B, Item 5 of the Descriptive Report, concerning junctions.

40. HORIZONTAL AND VERTICAL ACCURACY:

No statement.

46. COMPARISON WITH EXISTING MAPS:

A comparison has been made with the following USGS Quadrangle: TYONEK (B-1), ALASKA, 1:63,360 scale, dated 1958.

47. COMPARISON WITH NAUTICAL CHARTS:

A comparison has been made with the following National Ocean Survey Charts: 8553, scale 1:194,154, dated February 26, 1972; and 8557, scale 1:40,000, dated December 6, 1965.

ITEMS TO BE APPLIED TO NAUTICAL CHARTS IMMEDIATELY

None.

ITEMS TO BE CARRIED FORWARD

None.

Submitted by:

L. O. Neterer, Jr. Cartographic Technician

June 7, 1973

Approved:

Albert C. Rauck, Jr. / Chief, Coastal Mapping Section

GEOGRAPHIC NAMES

FINAL NAME SHEET

PH-6013 (Cook Inlet)

T-12002

Cook Inlet

Horseshoe Lake

Knik Arm

Susitna Flats

Approved by:

A. J. Wraight Chief Geographer

Prepared by:

Frank W. Pickett Cartographic Technician

 $\mathcal{C}\mathcal{R}_{\mathcal{A}}$

FIELD EDIT REPORT

OPR-469-RA-1974

UPPER COOK INLET, KNIK ARM

ALASĶA

T-12000 thru T-12008 T-12012 thru T-12016 T-12021 T-12031 TP- 00515

NOAA Ship RAINIER

CDR K. William Jeffers

Commanding

ंध

INTRODUCTION

Field edit was completed on selected "minus tide days" during the period from mid-May through the end of August. Work was carried out on shore and land.

Field edit was started in the Port of Anchorage and continued north up Knik Arm to Latitude $61^{\circ}22.0^{\circ}$, the northern limit of shoreline control. Field edit was completed on the north side of Cook Inlet westward to Longitude $150^{\circ}37.0^{\circ}$. Shoreline around Fire Island was inspected on the northwest side from North Point to West Point. Approximately 3 miles of shoreline wereinspected in the immediately vicinity of Pt. Possession.

Photographs used in the field edit are from jobs CM-7310 and PH-6013. Height data on all rocks was estimated. Times were referenced to 0° Longitude.

Adequacy of Compilation

All rocks and offshore features are labeled on the field edit ozalids, and whereever possible, verified on the field photos. Compilation of the MHWL was excellent on the manuscripts. Verification of MLLW was done by launch hydrography and is clearly deliniated on the boat-sheets.

Shoreline Summaries

T-12000, T-1200T, T-12002, T-12012, T-12013 (Northern Half), T-12014 (Northern Half)

This group of manuscripts includes the northern part of Cook Inlet fromSusitna River to Pt. Mackenzie. The area is one of extensive mud flats. One discrepancy was noted on the shoreline junction between T-12002 (1966 shoreline manuscript) and T-12006 (1973 shoreline manuscript). The 1973 shoreline manuscript extended the shoreline up to the forest edge. The MHWL is along a marsh that extends south from the forest edge. Therefore the shoreline was adjusted to follow the MHWL along the marsh.

.

T-12013 and T-12014 (southern Half)

The shoreline in this area covers Fire Island. The shoreline of Shelter Bay is muddy. The northern side of the island has a rocky beach with some detached rocks, none extending more that a quarter mile off shore. The southern andeastern side of Fire Island was not field edited, therefore, the Field Edit Ozalids should be returned to the RAINIER as soon as possible.

T-12021 and T-12031

The vicinity of Point Possession is foul with offshore rocks. The west side of Pt. Possession is very foul with rocks extending out 3/4 mile. This area was not completely field edited, therefore, the manuscripts and field edit ozalids should be returned to the RAINIER as soon as possible.

T-12006, T-12015, T-12016, TP-00515

This area includes Anchorage Harbor and the area extending westward to Pt. Mackenzie and Pt. Woronzof. The southern shore is primarily mud flats, almost entirely free of offshore rocks. The northern shore has many offshore rocks awash at MLLW. TP-00515 is a 1:5,000 scale inset of Anchorage Proper. Pier heights and additional data are recorded on the Field Edit Ozalid.

T-12007, T-12008

Lower Knik Arm-- The east and west shore are foul with many rocks: and boulders awash at MLLW.

T-12003, T-12004, T-12005

This area includes upper Knik Arm to the extent of the 1973 photo coverage. The east and west shores are mud with very few dangerous rocks.

Recommendations

Much of the area included in this survey project lacked good photo support. The 1973 photo support in Knik Arm and Anchorage Harbor was excellent, however, the 1966-1967 coverage westward into Cook Inlet was very sparse. Of special concern is the fact that the T-sheet and flight-line index showed many flight lines of photos which were never received and would have aided our field operations considerably. If these flights lines or even parts of them are not available, a complete inventory should be supplied for our records.

respectfully submitted,

(Garth Stroble LTJG, NOAA

AIDS TO NAVIGATION AND LANDMARKS FOR CHARTING

NOAA SHIP RAINIER

OPR-469-RA-1974

21 October, 1974

K. William Jeffers
Commanding

According to section 7-18 of the Hydrographic Manual, Publication 20-2, Aids to Navigation and Landmarks for Charting shall be submitted as a special report. Since all the information in this report is directly related to field edit operation, I feel this report could be incorporated in the Field Edit Report.

The chart letters and NOAA forms 76-40 included are self-explanatory and need no further explanation. The forms and letters were prepared as per sections 7.6 and 8, respectively, of the Coast Pilot Manual, Edition 3, 1969.

For further information on the locations of Aids to Navigation, refer to Geodetic Control Report, OPR-469-RA-1974.

Garth Stroble LTJG, NOAA

K. William Jeffers CDR, NOAA, Commanding

REVIEW REPORT T-12002

SHORELINE

61. GENERAL STATEMENT

See Summary included with this Descriptive Report.

62. COMPARISON WITH REGISTERED TOPOGRAPHIC SURVEYS
Not applicable.

63. COMPARISON WITH MAPS OF OTHER AGENCIES

Not applicable.

64. COMPARISON WITH CONTEMPORARY HYDROGRAPHIC SURVEYS

A comparison was made with Hydrographic Survey H-9442, scale 1:10,000, dated December 19, 1977.

There were no major conflicts.

65. COMPARISON WITH NAUTICAL CHARTS

A comparison was made with the following NOS chart: 16664, scale 1:40,000, 18th edition, January 16, 1982.

There were no major conflicts.

66. ADEQUACY OF RESULTS AND FUTURE SURVEYS

This map complies with the Project Instructions, and meets the requirements for National Standards of Map Accuracy.

Submitted by

James L. Byrd, Jr. Final Reviewer

Approved for forwarding

Billy H. Barnes

Chief, Photogrammetric Section

Approved

Chlef, Photogrammetry Production Sec.

Chief, Photogrammetry Branch

RECORD OF APPLICATION TO CHARTS

FILE WITH DESCRIPTIVE REPORT OF SURVEY NO.

INSTRUCTIONS

- A basic hydrographic or topographic survey supersedes all information of like nature on the uncorrected chart.

 1. Letter all information.

- In "Remarks" column cross out words that do not apply.
 Give reasons for deviations, if any, from recommendations made under "Comparison with Charts" in the Review.

CHART	DATE	CARTOGRAPHER	REMARKS
			Full Part Before After Verification Review Inspection Signed Via
			Drawing No.
			Full Part Before After Verification Review Inspection Signed Via
			Drawing No.
			Full D Defend the Verification Design to a single City 117
			Full Part Before After Verification Review Inspection Signed Via Drawing No.
		•	Full Part Before After Verification Review Inspection Signed Via
			Drawing No.
		-	Full Part Before After Verification Review Inspection Signed Via
			Drawing No.
		· · · · · · · · · · · · · · · · · · ·	Full Part Before After Verification Review Inspection Signed Via
			Drawing No.
			Full Part Before After Verification Review Inspection Signed Via
	-		Drawing No.
			Full Part Before After Verification Review Inspection Signed Via
			Drawing No.
			Full Part Before After Verification Review Inspection Signed Via
			Drawing No.
			Full Part Before After Verification Review Inspection Signed Via
			Drawing No.
			<u> </u>
			

FORM C&GS-8352 SUPERSEDES ALL EDITIONS OF FORM C&GS-978.

USCOMM-DC \$556-P63