

T 12527

T-12527

NOAA FORM 76-35 (6-80)	
U.S. DEPARTMENT OF COMMERCE NATIONAL OCEANIC AND ATMOSPHERIC ADMINISTRATION NATIONAL OCEAN SURVEY	
DESCRIPTIVE REPORT	
Map No. T-12527	Edition No. 1
Job No. PH-6401	
Map Classification FINAL, FIELD EDITED MAP	
Type of Survey SHORELINE	
LOCALITY	
State HAWAII	
General Locality HAWAII ISLAND, WEST COAST UPOLO POINT TO KAILUA	
Locality UMIWAI BAY	
19 ⁶³ TO 19 68	
REGISTERED IN ARCHIVES	
DATE	

NOAA FORM 76-36A (3-72) U. S. DEPARTMENT OF COMMERCE NATIONAL OCEANIC AND ATMOSPHERIC ADMIN. DESCRIPTIVE REPORT - DATA RECORD		<table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <td colspan="2" style="text-align: center;">TYPE OF SURVEY</td> <td colspan="2" style="text-align: center;">SURVEY TR. <u>12527</u></td> </tr> <tr> <td>☒ ORIGINAL</td> <td></td> <td colspan="2">MAP EDITION NO. (1)</td> </tr> <tr> <td>☐ RESURVEY</td> <td></td> <td colspan="2">MAP CLASS Final</td> </tr> <tr> <td>☐ REVISED</td> <td></td> <td colspan="2">JOB PH. <u>6401</u></td> </tr> </table>		TYPE OF SURVEY		SURVEY TR. <u>12527</u>		☒ ORIGINAL		MAP EDITION NO. (1)		☐ RESURVEY		MAP CLASS Final		☐ REVISED		JOB PH. <u>6401</u>	
TYPE OF SURVEY		SURVEY TR. <u>12527</u>																	
☒ ORIGINAL		MAP EDITION NO. (1)																	
☐ RESURVEY		MAP CLASS Final																	
☐ REVISED		JOB PH. <u>6401</u>																	
PHOTOGRAMMETRIC OFFICE Coastal Mapping Unit, Atlantic Marine Center Norfolk, Virginia OFFICER-IN-CHARGE <u>Richard Houlder</u>		<table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <td colspan="2" style="text-align: center;">LAST PRECEDING MAP EDITION</td> </tr> <tr> <td colspan="2" style="text-align: center;">TYPE OF SURVEY</td> </tr> <tr> <td>☐ ORIGINAL</td> <td>JOB PH. _____</td> </tr> <tr> <td>☐ RESURVEY</td> <td>MAP CLASS _____</td> </tr> <tr> <td>☐ REVISED</td> <td>SURVEY DATES: 19__ TO 19__</td> </tr> </table>		LAST PRECEDING MAP EDITION		TYPE OF SURVEY		☐ ORIGINAL	JOB PH. _____	☐ RESURVEY	MAP CLASS _____	☐ REVISED	SURVEY DATES: 19__ TO 19__						
LAST PRECEDING MAP EDITION																			
TYPE OF SURVEY																			
☐ ORIGINAL	JOB PH. _____																		
☐ RESURVEY	MAP CLASS _____																		
☐ REVISED	SURVEY DATES: 19__ TO 19__																		
I. INSTRUCTIONS DATED																			
1. OFFICE		2. FIELD																	
Compilation September 12, 1968 Supplement No. 1 February 11, 1969 Compilation March 11, 1969 Supplement No. 2 December 11, 1969		Control/Field Inspection April 29, 1964																	
II. DATUMS																			
1. HORIZONTAL: ☐ 1927 NORTH-AMERICAN		OTHER (Specify) Old Hawaiian Datum																	
2. VERTICAL: ☒ MEAN HIGH-WATER ☐ MEAN LOW-WATER ☐ MEAN LOWER LOW-WATER ☐ MEAN SEA LEVEL		OTHER (Specify)																	
3. MAP PROJECTION Polyconic		4. GRID(S) <table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <td style="width: 50%;">STATE Hawaii</td> <td style="width: 50%;">ZONE 1</td> </tr> </table>		STATE Hawaii	ZONE 1														
STATE Hawaii	ZONE 1																		
5. SCALE 1:10,000		STATE _____ ZONE _____																	
III. HISTORY OF OFFICE OPERATIONS																			
OPERATIONS		NAME	DATE																
1. AEROTRIANGULATION BY P. Hawkins Jun 1966 METHOD: Stereoplanigraph LANDMARKS AND AIDS BY J. Perrow Jun 1966																			
2. CONTROL AND BRIDGE POINTS PLOTTED BY P. Hawkins Jun 1966 METHOD: Coradomat CHECKED BY J. Perrow Jun 1968																			
3. STEREOSCOPIC INSTRUMENT PLANIMETRY BY E. Margiotta Sept 1968 COMPILATION CHECKED BY C. Bishop Sept 1968 INSTRUMENT: Wild B-8 CONTOURS BY N.A. SCALE: 1:10,000 CHECKED BY N.A.																			
4. MANUSCRIPT DELINEATION PLANIMETRY BY E. Margiotta Sept 1968 CHECKED BY C. Bishop Oct 1968 METHOD: Smooth drafted CONTOURS BY N.A. SCALE: 1:10,000 CHECKED BY N.A. HYDRO SUPPORT DATA BY A. Shands Sept 1968 CHECKED BY C. Bishop Oct 1968																			
5. OFFICE INSPECTION PRIOR TO FIELD EDIT BY C. Bishop Oct 1968																			
6. APPLICATION OF FIELD EDIT DATA BY A. Shands Aug 1969 CHECKED BY R. Smith Dec 1969																			
7. COMPILATION SECTION REVIEW BY R. Smith Dec 1969																			
8. FINAL REVIEW BY J. Hancock Oct 1986																			
9. DATA FORWARDED TO PHOTOGRAMMETRIC BRANCH BY J. Hancock Mar 1987																			
10. DATA EXAMINED IN PHOTOGRAMMETRIC BRANCH BY P. Dempsey May 1987																			
11. MAP REGISTERED - COASTAL SURVEY SECTION BY E. L. DAUGHERTY MAY 1987																			

TP-12527
COMPILATION SOURCES

1. COMPILATION PHOTOGRAPHY

CAMERA(S) Wild RC-8"S", S=152.29 mm		TYPES OF PHOTOGRAPHY LEGEND (C) COLOR (P) PANCHROMATIC (I) INFRARED		TIME REFERENCE	
TIDE STAGE REFERENCE ☒ PREDICTED TIDES ☐ REFERENCE STATION RECORDS ☐ TIDE CONTROLLED PHOTOGRAPHY				ZONE Yukon MERIDIAN 135th	☒ STANDARD ☐ DAYLIGHT
NUMBER AND TYPE	DATE	TIME	SCALE	STAGE OF TIDE	
63S(C) 7754-7756**	Aug. 27, 1963	09:51	1:20,000	1.8 ft. above MLLW	
63S(P) 7798-7799**	Aug. 27, 1963	10:52	1:30,000	1.8 ft. above MLLW	
				Mean Tide Range=1.4 ft.	

REMARKS

*Bridging Photographs, **Compilation photographs

2. SOURCE OF MEAN HIGH-WATER LINE:

The mean high water line was compiled from office interpretation of the compilation photographs using stereo instrument methods.

3. SOURCE OF MEAN LOW-WATER LINE OR MEAN LOWER LOW-WATER LINE:

No mean lower low water line was compiled.

4. CONTEMPORARY HYDROGRAPHIC SURVEYS (List only those surveys that are sources for photogrammetric survey information.)

SURVEY NUMBER	DATE(S)	SURVEY COPY USED	SURVEY NUMBER	DATE(S)	SURVEY COPY USED
H-9019	Surveyed 1968	Registered	H-9975	Surveyed 1981	Registered

5. FINAL JUNCTIONS

NORTH	EAST	SOUTH	WEST
No Survey	T-12528	T-12529	No Survey

REMARKS

T-12527

HISTORY OF FIELD OPERATIONS

I. ☒ FIELD INSPECTION OPERATION☐ FIELD EDIT OPERATION

OPERATION	NAME	DATE
1. CHIEF OF FIELD PARTY	R. Newsom	May 1964
2. HORIZONTAL CONTROL	RECOVERED BY E. Cline	May 1964
	ESTABLISHED BY E. Cline	May 1964
	PRE-MARKED OR IDENTIFIED BY E. Cline	May 1964
3. VERTICAL CONTROL	RECOVERED BY None	
	ESTABLISHED BY None	
	PRE-MARKED OR IDENTIFIED BY None	
4. LANDMARKS AND AIDS TO NAVIGATION	RECOVERED (Triangulation Stations) BY None	
	LOCATED (Field Methods) BY E. Cline	July 1964
	IDENTIFIED BY None	
5. GEOGRAPHIC NAMES INVESTIGATION	TYPE OF INVESTIGATION ☐ COMPLETE ☐ SPECIFIC NAMES ONLY BY ☒ NO INVESTIGATION	
6. PHOTO INSPECTION	CLARIFICATION OF DETAILS BY E. Cline	May 1964
7. BOUNDARIES AND LIMITS	SURVEYED OR IDENTIFIED BY None	

II. SOURCE DATA

1. HORIZONTAL CONTROL IDENTIFIED		2. VERTICAL CONTROL IDENTIFIED	
PHOTO NUMBER	STATION NAME	PHOTO NUMBER	STATION DESIGNATION
63(S)7799*	LORAN TOWER, 1948 (Sub Pts 1 & 2 identified) *Section of ratio photo submitted.		

3. PHOTO NUMBERS (Clarification of details)

63(S)7799 (Matte Contact).

4. LANDMARKS AND AIDS TO NAVIGATION IDENTIFIED

None

PHOTO NUMBER	OBJECT NAME	PHOTO NUMBER	OBJECT NAME

5. GEOGRAPHIC NAMES: ☐ REPORT ☒ NONE6. BOUNDARY AND LIMITS: ☐ REPORT ☒ NONE

7. SUPPLEMENTAL MAPS AND PLANS

None

8. OTHER FIELD RECORDS (Sketch books, etc. DO NOT list data submitted to the Geodesy Division)

2 Forms 152 (CSI)

HISTORY OF FIELD OPERATIONS

I. ☐ FIELD INSPECTION OPERATION☒ FIELD EDIT OPERATION

OPERATION	NAME	DATE
1. CHIEF OF FIELD PARTY	(USC&GS Ship McARTHUR) R. Newsom, CDR	Oct 1968
2. HORIZONTAL CONTROL	RECOVERED BY ESTABLISHED BY PRE-MARKED OR IDENTIFIED BY	R. Newsom, CDR None None
3. VERTICAL CONTROL	RECOVERED BY ESTABLISHED BY PRE-MARKED OR IDENTIFIED BY	None None None
4. LANDMARKS AND AIDS TO NAVIGATION	RECOVERED (Triangulation Stations) BY LOCATED (Field Methods) BY IDENTIFIED BY	R. Newsom, CDR None None
5. GEOGRAPHIC NAMES INVESTIGATION	TYPE OF INVESTIGATION ☐ COMPLETE ☐ SPECIFIC NAMES ONLY ☒ NO INVESTIGATION	
6. PHOTO INSPECTION	CLARIFICATION OF DETAILS BY	None
7. BOUNDARIES AND LIMITS	SURVEYED OR IDENTIFIED BY	None

II. SOURCE DATA

1. HORIZONTAL CONTROL IDENTIFIED

None

2. VERTICAL CONTROL IDENTIFIED

None

PHOTO NUMBER	STATION NAME	PHOTO NUMBER	STATION DESIGNATION

3. PHOTO NUMBERS (Clarification of details)

None

4. LANDMARKS AND AIDS TO NAVIGATION IDENTIFIED

None

PHOTO NUMBER	OBJECT NAME	PHOTO NUMBER	OBJECT NAME

5. GEOGRAPHIC NAMES: ☐ REPORT ☒ NONE6. BOUNDARY AND LIMITS: ☐ REPORT ☒ NONE

7. SUPPLEMENTAL MAPS AND PLANS

None

8. OTHER FIELD RECORDS (Sketch books, etc. DO NOT list data submitted to the Geodesy Division)

1 Field Edit Paper Print

RECORD OF SURVEY USE

I. MANUSCRIPT COPIES

COMPILATION STAGES			DATE MANUSCRIPT FORWARDED	
DATA COMPILED	DATE	REMARKS	MARINE CHARTS	HYDRO SUPPORT
Compilation complete, pending field edit.	Oct. 1968	Class III Manuscript (Includes Field Inspection)	Oct. 1968	Oct. 1968 Dec. 1969
Field edit applied compilation complete.	Dec 1969	Class I Manuscript		Nov. 1973
Final Review	Oct 1986	Final Map	mar 1987	mar 1987

II. LANDMARKS AND AIDS TO NAVIGATION

1. REPORTS TO MARINE CHART DIVISION, NAUTICAL DATA BRANCH

NUMBER (pages)	CHART LETTER NUMBER ASSIGNED	DATE FORWARDED	REMARKS
2		Jan 1970	2 C&GS Forms 567

2. ☒ REPORT TO MARINE CHART DIVISION, COAST PILOT BRANCH. DATE FORWARDED: Jan 21, 19703. ☐ REPORT TO AERONAUTICAL CHART DIVISION, AERONAUTICAL DATA SECTION. DATE FORWARDED: _____

III. FEDERAL RECORDS CENTER DATA

1. ☒ BRIDGING PHOTOGRAPHS; ☒ DUPLICATE BRIDGING REPORT; ☒ COMPUTER READOUTS.
2. ☒ CONTROL STATION IDENTIFICATION CARDS; ☐ FORM NOS 567 SUBMITTED BY FIELD PARTIES.
3. ☐ SOURCE DATA (except for Geographic Names Report) AS LISTED IN SECTION II, NOAA FORM 76-36C.
ACCOUNT FOR EXCEPTIONS:

4. ☐ DATA TO FEDERAL RECORDS CENTER. DATE FORWARDED: _____

IV. SURVEY EDITIONS (This section shall be completed each time a new map edition is registered)

SECOND EDITION	SURVEY NUMBER TP - _____ (2)	JOB NUMBER PH - _____	TYPE OF SURVEY ☐ REVISED ☐ RESURVEY MAP CLASS ☐ II. ☐ III. ☐ IV. ☐ V. ☐ FINAL
	DATE OF PHOTOGRAPHY	DATE OF FIELD EDIT	
THIRD EDITION	SURVEY NUMBER TP - _____ (3)	JOB NUMBER PH - _____	TYPE OF SURVEY ☐ REVISED ☐ RESURVEY MAP CLASS ☐ II. ☐ III. ☐ IV. ☐ V. ☐ FINAL
	DATE OF PHOTOGRAPHY	DATE OF FIELD EDIT	
FOURTH EDITION	SURVEY NUMBER TP - _____ (4)	JOB NUMBER PH - _____	TYPE OF SURVEY ☐ REVISED ☐ RESURVEY MAP CLASS ☐ II. ☐ III. ☐ IV. ☐ V. ☐ FINAL
	DATE OF PHOTOGRAPHY	DATE OF FIELD EDIT	

Official Mileage
For
Cost Accounts

Sheet No.

Area
Sq. Mi.


T-12527	1
T-12528	3
T-12529	3
T-12530	3
T-12531	2
T-12532	2
T-12533	3
T-12534	2
T-12535	2
T-12536	3
T-12537	4
T-12538	2
T-12539	4
T-12540	4
T-12541	4
T-12542	2
T-12543	3
T-12544	2
T-12545	3
T-12635	2
T-13131	2
T-13132	2
T-13154	2
T-13382	1
Total	61

JOB PH-6401

SHORELINE MAPPING

HAWAII IS. WEST COAST
UPOLO POINT TO KAILUA

SCALE 1:5,000 & 1:10,000



Kailua Ranch
Islet Camp
W. S. YOUNG CAMP

SUMMARY TO ACCOMPANY
DESCRIPTIVE REPORT

T-12527

This 1:10,000 scale final shoreline map is one of twenty-three maps that comprise PH-6401, Hawaii Island, Hawaii, West Coast, Upolo Point to Kailua. The project consists of seventeen 1:10,000 scale maps (T-12527 thru T-12541, T-12543, T-12545) and six 1:5,000 scale inset maps (T-12542, T-12544, T-12635, T-13131, T-13132, T-13382).

The purpose of this map was to furnish data in support of hydrographic operations and to provide current shoreline data for marine charts.

This map portrays a portion of shoreline along the northwest coast of Hawaii Island from Lat. 20° 15.0' to Lat. 20° 16.0'.

Photo coverage for the project was adequately provided in August/September 1963 using the Wild RC-8 "S" camera. Photography consisted of 1:30,000 scale panchromatic photographs used for field inspection and aerotriangulation. The 1:20,000 and 1:15,000 scale color photographs were used for compilation and hydro support. The 1:20,000 scale photo coverage was obtained for the 1:10,000 scale maps and the 1:15,000 scale photographs provided coverage of the 1:5,000 scale inset maps. Additional color photographs at 1:15,000 scale were obtained in February 1969 with the Wild RC-8"E" camera. These photographs were bridged and a supplemental plot report was prepared in order to compile three 1:5,000 scale inset maps (T-13131, T-13132 and T-12635). The stage of tide for all project photographs was based upon predicted tide data. No infrared photographs were provided.

Field work prior to aerotriangulation consisted of the recovery and establishment of horizontal control by photoidentification methods. In addition, a field inspection was performed for the project area utilizing the 1:30,000 scale photographs. This activity was conducted in May/June 1964.

Analytic aerotriangulation was adequately provided by the Washington Science Center in three phases. Initial bridging activity was accomplished for seven of the northern project maps in June 1966. The second phase was conducted for the remaining project maps in February 1969. A final bridge was provided in October 1971 for the 1969 photo coverage of three 1:5,000 scale inset maps. Aerotriangulation activity included ruling the base manuscripts and also provided ratio photographs for the compilation and hydrographic/field edit operations.

Compilation for this map was performed at the Coastal Mapping Section, Atlantic Marine Center in October 1968. Copies of the manuscript and hydrographic support data were forwarded to the hydrographer for field edit. A copy of the manuscript was also submitted to the Marine Charts Section.

T-12527

Field edit for this map was conducted in conjunction with hydrographic survey H-9019 by USC&GS Ship McARTHUR personnel in October 1968.

Application of field edit data was accomplished at the Atlantic Marine Center in December 1969 and the manuscript was advanced to Class I. A copy of the Class I manuscript was forwarded to the Hydrographic Surveys Branch.

Final review was performed at the Atlantic Marine Center in October 1986. A comparison was made with the common nautical chart(s) and hydrographic survey(s). The original base manuscript and related data along with a final Chart Maintenance Print and a Hydrographic Print were forwarded to the Washington Science Center for registration and distribution.

FIELD INSPECTION
T-12527

Field activity prior to compilation included a field inspection of the shoreline and the recovery/photoidentification of horizontal control necessary for project aerotriangulation. Results of the 1964 field inspection were submitted on the 1:30,000 scale contact photographs.

PHOTOGRAMMETRIC BRIDGE REPORT
Hawaii Island, Hawaii
Job PH-6401

June, 1966

21. Area Covered

This report covers only Strip #1 and Strip #2 which fall along the northwestern tip of Hawaii Island. T-sheets in this area are numbered 12527 through T-12533.

22. Method

Both strips were bridged on the stereoplanigraph and were adjusted by IBM 1620 methods. Strip #1 was adjusted on five control stations with four additional stations as checks. Strip #2 was adjusted on four control stations with two additional stations as checks. All tie points between strips were averaged.

23. Adequacy of Control

The control provided by the field was adequate but did not comply with project instructions in that many stations were identified directly with no substation. The following stations could not be held in the bridging adjustments.

1. KAWAIHAE LIGHT 1948. The field misidentified this station by some 1,500 feet. The description places this station to the southeast of where it was pricked.
2. KEPUHI 2, 1948, SS #1. The substation was misidentified during bridging operations; however, the home station held in the bridge.
- 3 & 4. MAHUKONA HARBOR SOUTH DAY BEACON 1910 and MAHUKONA NORTH DAY BEACON 1910. These two stations were identified directly. No Form 152's were provided by the field. The identification seems to fit the descriptions; however, the two stations could not be held in either bridge by same amounts (30' to 35'). In view of the bridging results, using the other control stations, and the good junction between strips, the two stations were disregarded. It is recommended that a field check of these stations be made during hydro operations.

24. Supplemental Data

Local Geological Survey Quads of the area were used to establish rough elevations for bridging.

25. Photography

Photography was adequate as to coverage, overlap, definition and quality of diapositives.

Submitted by:


Paul Hawkins

Paul Hawkins

Approved by:

John D. Perrow, Jr.

John D. Perrow, Jr.



COMPILATION REPORT
T-12527

31 - DELINEATION

Delineation was by instrument methods using the Wild B-8 stereoplotter and 1:20,000 scale color photographs. The 1:30,000 scale panchromatic field inspection photographs were used during compilation; however, many of the field identified rocks were not discernible when viewing the 1:20,000 scale color compilation photographs. Rocks that were not clearly identifiable were not compiled.

Compilation ratio photographs were processed for hydro support and were used graphically to assist in delineation of minor details. Photo coverage and quality were adequate.

32 - CONTROL

Refer to the Photogrammetric Plot Report, dated June 1966.

33 - SUPPLEMENTAL DATA

None.

34 - CONTOURS AND DRAINAGE

Contours are inapplicable. Drainage was delineated from the compilation photographs.

35 - SHORELINE AND ALONGSHORE DETAILS

The shoreline was delineated from office interpretation of the mapping photographs and from the annotated photographs resulting from the precompilation field inspection. Because of the small tide range, no mean lower low water line was compiled.

36 - OFFSHORE DETAILS

There were no significant offshore details.

37 - LANDMARKS AND AIDS

Two landmarks were determined during the field inspection activity.

38 - CONTROL FOR FUTURE SURVEYS

None.

39 - JUNCTIONS

Refer to the Data Record Form 76-36B, Item 5.

T-12527

40 - HORIZONTAL AND VERTICAL ACCURACY

Refer to the Photogrammetric Plot Report dated June 1966.

46 - COMPARISON WITH EXISTING MAPS

A comparison was made with U.S.G.S Quadrangle, Mahukona, Hawaii, dated 1957, scale 1:24,000.

47 - COMPARISON WITH NAUTICAL CHARTS

A comparison was made with USC&GS Chart 4140, scale 1:80,000, 3rd edition, dated Jan. 24, 1966.

ITEMS TO BE APPLIED TO NAUTICAL CHARTS IMMEDIATELY

None.

ITEMS TO BE CARRIED FORWARD

None.

Submitted by

F. P. Margiotta

for F. P. Margiotta
Cartographic Aid
September 1968

Approved

Albert C. Rauck, Jr.

for Albert C. Rauck, Jr.
Chief, Coastal Mapping Section

ADDENDUM TO THE COMPILATION REPORT

T-12527

Field edit was performed concurrent with hydrographic survey H-9019. The field editor indicated that surf conditions prohibited him from verifying most of the alongshore rocks and limit lines. The only field data submitted was a paper field edit print. Adequate information was furnished in order to advance the manuscript to Class I status.

August 20, 1968¹³

GEOGRAPHIC NAMES

FINAL NAME SHEET

PH-6401 (Hawaii, West Coast I. of Hawaii)

T-12527

Alenuihaha Channel

Limukoko Point

Mookini Heiau

Pacific Ocean

Umiwai Bay

Approved by:

A. J. Wright

A. Joseph Wright
Chief Geographer

Prepared by:

Frank W. Pickett

Frank W. Pickett
Cartographic Technician

REVIEW REPORT
T-12527

SHORELINE

61 - GENERAL STATEMENT

Final review for this final field edited map was accomplished at the Atlantic Marine Center in October 1986. For a schedule of the office and field operations, refer to the Summary included with this Descriptive Report.

62 - COMPARISON WITH REGISTERED TOPOGRAPHIC SURVEYS

Not applicable.

63 - COMPARISON WITH MAPS OF OTHER AGENCIES

A comparison was made with U.S.G.S quadrangle Mahukona, Hawaii, dated 1957, scale 1:24,000.

64 - COMPARISON WITH CONTEMPORARY HYDROGRAPHIC SURVEYS

A portion of hydrographic survey H-9019 and H-9975 are common to this final shoreline map. A comparison was made with a registered copy of H-9019, AR-10-8-68, 1:10,000 scale, field surveyed 1968 and H-9975, RA-20-5-81, 1:20,000 scale, field surveyed 1981. Field edit for this final map was performed in conjunction with hydro survey H-9019. Because the hydro surveys junction within the limits of this shoreline map (Lat. 20° 15.5') coastal detail was applied to H-9975 even though it was field surveyed in 1981.

65 - COMPARISON WITH NAUTICAL CHARTS

A comparison was made with NOS chart 19327, scale 1:80,000, 8th edition, Sept. 5, 1981.

66 - ADEQUACY OF RESULTS AND FUTURE SURVEYS

This map complies with the Project Instructions, and meets the requirements for National Standards of Map Accuracy.

T-12527

Submitted by

*Jerry L. Hancock*Jerry L. Hancock
Final Reviewer

Approved for forwarding

*Billy H. Barnes*Billy H. Barnes
Chief, Photogrammetric Section, AMC

Approved

Jerry O. Robson

Chief, Photogrammetric Production Sec.

G. Y. Bryson

Chief, Photogrammetry Branch

TO BE CHARTED

STRIKE OUT TWO

62-11761-10A

ONLY CATING AIDS OR LANDMARKS FOR CHARTS

Atlantic Marine Center

Dec. 30 1969

I recommend that the following objects which have ~~(three-not)~~ been inspected from seaward to determine their value as landmarks be charted on ~~(sketched from)~~ the charts indicated.

The positions given have been checked after listing by

A. L. Shands

T-12527

Allen L. Powell, Director, AMC

Chief of Party.

[illegible]

This form shall be prepared in accordance with Hydrographic Manual, Publication 20.2, Sec. 1-55, 2-39, 6-36, 7-18 to 22 inclusive, and Fig. 79. Positions of charted landmarks and *nonfloating aids* to navigation, if redetermined, shall be reported on this form. Revisions shall show both the old and new positions. The data should be considered for the charts of the area and not by individual field survey sheets. Information under each column heading should be given.

* TABULATE SECONDS AND METERS

004-20905 36-WINDSTN

