

# 8644

Diag'd on Diag. Ch. No. 1201

Form 504

## U. S. COAST AND GEODETIC SURVEY

DEPARTMENT OF COMMERCE

### DESCRIPTIVE REPORT

Type of Survey Topographic

Field No. CS-272-E Office No. T-8644

#### LOCALITY

State Maine

General locality Eastern Maine

Locality Narraguagus Bay and Pleasant River

1944-48

CHIEF OF PARTY

Dale E. Sturmer

LIBRARY & ARCHIVES

DATE May 24 - 1949

# 8644

## DATA RECORD

T- 8664

Quadrangle (II): Harrington, Maine

Project No. (II): CS-272-F

Field Office: Millbridge, Me.

Chief of Party: Dale E. Sturmen

Compilation Office:  
Baltimore, Md.Chief of Party:  
Lieut. Comdr. Thos. B. ReedDiv. of Photogrammetry,  
Office FilesInstructions dated (II III):  
June 19, 1945  
Sept. 18, 1946Copy filed in Descriptive  
Report No. T— (VI)

Completed survey received in office: 12-9-48

Reported to Nautical Chart Section:

Reviewed: 3-15-49

Applied to chart No.

Date:

Redrafting Completed:

Registered: 4-21-49

Published:

Compilation Scale: 1:10,000 (Multiplex)  
scale 1:8500)Published Scale: 1:24,000  
1:25,000

Scale Factor (III): 1.00

Geographic Datum (III): N. A. 1927

Datum Plane (III): Mean Sea Level

Reference Station (III): Foster, 1861

Lat.: 44° 31' 36.843"

Long.: 67° 50' 0.782"

Adjusted  
~~Unadjusted~~

State Plane Coordinates (VI):

X =

Y =

Military Grid Zone (VI)



1945-1946 21944  
-2-  
PHOTOGRAPHS (III)  
E.S.T.

Number	Date	Time	Scale	Stage of Tide
588-591	5-30-46	0905	1:20,000	MHW of 11.1 plus 0.3'
781-788	5-9-44	1130	"	" " 11.3 less 0.0
796-804	5-16-44	0930	"	" " 11.3 " 8.7'
1130-1134	5-19-44	1100	"	" " 11.3 " 5.5'
1142-1150	5-19-44	1115	"	" " 11.3 " 6.6'
1161-1166	5-19-44	1130	"	" " 11.3 " 6.8'
1738-1744	6-5-44	1030	"	" " 11.3 " 1.5'

Millbridge, Narraguagus Bay; Gibbs Island, Pleasant River,  
Tide from (III): Trafton Island, Narraguagus Bay.

Mean Range: 11.2' Spring Range: 12.7'

Camera: (Kind or source) U.S.C. & G.S. Type "C", 6" Metrogon Lens

Field Inspection by: 1:20,000 photos: -B.L., D.E.S. date: Summer and  
1:10,000 photos: - M.G.M. Fall of 1945,  
1:8500 photos: - I.I. Saperstein Summer 1946  
Field Edit by: G. Varnadoc date: July 1948

Date of Mean High-Water Line Location (III): Aug. & Sept. 1945 for waters west  
of Pleasant River. June, 1946 for Pleasant River.

Projection and Grids ruled by (III) 1:10,000 - S. Rose date: May 1945,  
1:8500: - T.L.J., S. Rose June & July 1946  
" " " checked by: date:  
Control plotted by: R.J.F., N.S.S. date: Aug. 1946  
1:8500: - Albert K. Heywood  
Control checked by: 1:8500 - Stanley W. Trow date: 1:8500 - Sept. 1946  
1:10,000 - N.S.S., C. L. 1:10,000 - Spring 1946  
Bernice Wilson, Henry P. Eichert  
Radial Plot by: (not used) date:

Detailed by: Multiplex: - Albert K. Heywood and date: Spring & Fall,  
Albert C. Rauck, 1947  
1:10,000 Tracing & shoreline by: Bernice Wilson, N S  
Reviewed in compilation office by: Mildred Trautman Z date: Nov. & Dec. 1947  
Henry P. Eichert,

manuscript  
Elevations on ~~photocopy~~ ~~photocopy~~  
checked by: H.P. Eichert

date: Nov. 1947

100

STATISTICS (III)

Land Area (Sq. Statute Miles): 36

Shoreline (More than 200 meters to opposite shore): 73 statute miles

Shoreline (Less than 200 meters to opposite shore): 18.5 statute miles

Number of Recoverable Topographic Stations established: 39

Number of Temporary Hydrographic Stations located by ~~radio~~ multiplex:  
~~radio~~ 584

Leveling (to control contours) - miles: 166 (from field report)

Roman numerals indicate whether the item is to be entered by, (II) Field Party, (III) Compilation Party, or, (VI) the Washington Office.

When entering names of personnel on this record give the surname and initials (not initials only).

Remarks:



MAP T-8644

PROJECT NO. CS 272 J

SCALE OF MAP 1:10,000

SCALE FACTOR 1.00

STATION	SOURCE OF INFORMATION (INDEX)	DATUM	LATITUDE OR $\phi$ -COORDINATE LONGITUDE OR $\lambda$ -COORDINATE		DISTANCE FROM GRID IN FEET, OR PROJECTION LINE IN METERS		DATUM CORRECTION	N.A. 1927 - DATUM DISTANCE FROM GRID OR PROJECTION LINE IN METERS		FACTOR DISTANCE FROM GRID OR PROJECTION LINE IN METERS	
CON, 1913	USCGS GP List	NAD 27	44 35	13.177				406.7	1445.3		
			67 45	08.505				187.6	1136.0		
Sub. Pt. CON, 1913		"	44 35					394.1	1457.9		
			67 45					173.2	1150.4		
WASS, 1862	"	"	44 35	37.365				1153.2	698.8		
			67 45	26.581				586.3	737.3		
Sub. Pt. WASS, 1862	"	"	44 35					1137.1	714.9		
			67 45					556.0	767.6		
ADDISON, WHITE CHURCH BELFERY, 1934	"	"	44 36	58.882				1817.4	34.6		
			67 45	19.314				425.8	897.5		
WARD, 1881	"	"	44 33	00.766				23.8	1828.2		
			67 46	29.462				650.3	674.1		
Sub. Pt. WARD, 1881	"	"	44 33					27.9	1824.1		
			67 46					660.4	664.0		
FORT, 1861	"	"	44 32	34.055				1051.2	800.8		
			67 50	43.493				960.2	364.6		
Sub. Pt. FORT 1861	"	"	44 32					1065.4	786.6		
			67 50					952.7	372.1		
FOSTER, 1861	"	"	44 31	36.843				1137.2	714.8		
			67 50	01.782				39.4	1285.8		
Sub. Pt. FOSTER, 1861	"	"	44 31					1134.1	717.9		
			67 50					41.2	1284.0		
TURNER, 1861	"	"	44 30	10.205				315.0	1537.0		
			67 51	47.136				1041.3	284.2		

1 FT. = 3048006 METERS  
COMPUTED BY: A.K. Heywood.

DATE 1946.

CHECKED BY: S.W. TROW, 1946.

COPY CHECKED  
DATE  
M. 2308-12

MAP T-8644

PROJECT NO. CS 272 F

SCALE OF MAP 1:10,000

SCALE FACTOR 1.00

STATION	SOURCE OF INFORMATION (INDEX)	DATUM	LATITUDE OR $\phi$ -COORDINATE LONGITUDE OR $\lambda$ -COORDINATE O ° ' "		DISTANCE FROM GRID IN FEET, OR PROJECTION LINE IN METERS FORWARD (BACK)		DATUM CORRECTION	N.A. 1927 - DATUM DISTANCE FROM GRID OR PROJECTION LINE IN METERS FORWARD (BACK)		FACTOR DISTANCE FROM GRID OR PROJECTION LINE IN METERS FORWARD (BACK)
Sub. Pt. TURNER, 1861	USC&GS	N.A.	44	30				328.3	1523.7	
RIPIEY 2, 1881	G.P. LIST	1927	67	51				1029.7	295.8	
	"	"	44	31	19.150			591.1	1860.9	
	"	"	67	46	59.820			1321.1	4.1	
Sub. Pt. RIPIEY 2, 1881	"	"	44	31				592.8	1259.2	
LILY, 1934	"	"	67	47				1.6	1323.6	
	"	"	44	35	24.767			764.5	1087.5	
	"	"	67	48	20.784			458.5	865.1	
Sub. Pt. LILY, 1934	"	"	44	35				762.1	1089.9	
	"	"	67	48				479.6	844.0	
MILL RIVER, CHURCH, 1934			44	35	51.915			1602.5	249.5	
LOG, 1861			67	50	43.421			957.7	365.9	
	"	"	44	30	04.547			140.4	1711.6	
	"	"	67	48	26.772			591.4	734.1	
Sub. Pt. LOG, 1861	"	"	44	30				124.7	1727.3	
	"	"	67	48				589.4	736.1	
WALLACE, 1861	"	"	44	34	02.437 (Use with caution).			75.2	1776.8	
	"	"	67	52	09.536			210.4	1113.6	
Sub. Pt. WALLACE, 1861	"	"	44	34				86.9	1765.1	
	"	"	67	52				214.6	1109.4	
HARRINGTON, WHITE	"	"	44	37	09.184			283.5	1568.5	
CHURCH SPIRE, 1934	"	"	67	48	46.447			1024.0	298.9	
NARRAGUAGUS RIVER HALF-TIDE LEDGE IN 1913	"	"	44	31	50.151			1548.0	304.0	
	"	"	67	51	54.022			15192.9	132.0	

COMPUTED BY: A.K. HEYWOOD

DATE 1946

CHECKED BY: S.W. TROY

DATE 1946

M. 2308-12

FIELD REPORT

TOPOGRAPHIC MANUSCRIPT, SURVEY NO. T-8644

The area of this topographic survey is covered by a Descriptive and Seasons Report, Air Photographic Survey, Project CS-272-F, State of Maine, Prospect Harbor to Jonesport, by Fred. L. Peacock, Chief of Party, dated 26 December 1945. Filed in Div. of Photogrammetry - General Files

For field data covering Survey T-8644 refer to the above mentioned report.



## COMPILATION REPORT

TOPOGRAPHIC MANUSCRIPT - SURVEY NO. T-8644

### 26. CONTROL

Horizontal Control: Refer to "Compilation Report" for Project CS-272-F for a detailed report on horizontal control. Filed in Div. of Photogrammetry - General Files

There are three (3) triangulation points on the manuscript which were not used as control for the following reasons:

NARRAGUAGUS RIVER HALF-TIDE LEDGE BN. 1913, was recovered but not picked and no image could be discerned on the photographs.

CHANNEL ROCK BN., 1913, and COFFIN ROCK BN., 1913, were reported lost in 1945, but were apparently rebuilt later and sextant fixes taken by the field party in 1946. Positions for both beacons have been plotted from these fixes. Their scaled positions have been reported on both forms 567 and 524. Note

Vertical Control: Refer to "Compilation Report for Project CS-272-F for a detailed discussion of vertical control.

Vertical Point PM-21 in model 796-797 could not be held with water surface and other control points in the model. The elevation of PM-21 as determined in the field was 79' but as read after model was levelled was 103'. PM-21 is located off the west limit of the quadrangle. See Field Edit Report for T 8643

In order to level model 1141-1142 it was found necessary to make use of pass points from Model 1140-1141. It is felt that as such the levelling solution is weak and therefore the contours shown be regarded as form lines. For this reason they have been shown broken. Verification should be done during the field edit. The area in question is the northern portion of Dyer Island. See Field Edit Report for T 8648

### 27. RADIAL PLOT

As discussed in the "Compilation Report" for Project CS-272-F, a radial plot covering the area of this quadrangle was not used.

Because of insufficient overlap along line of flight, photographs 1130 through 1133 were not used for multiplex plotting. Instead, a flight farther to the east (photos 1740 - 1742) was used. As now, there ~~was~~ was not sufficient side lap between this flight and the adjoining flight to the west (photos 1147-1149), there was a gap in the work from Oliver Lord Point to the north limit of the quadrangle. The omitted details were delineated from the office photographs, using radial intersections and matching adjoining detail already plotted.

The contours in this area, of course, remain to be done in the field. Contoured by Field Edit Party. Contours added to map manuscript in Baltimore Office



28. DETAILING

Detailing was accomplished in accordance with project instructions dated September 18, 1946, and supplementary instructions issued by the Chief, Division of Photogrammetry.

Roads, buildings, woods lines, and drainage were detailed with the multiplex plotting instrument. Shoreline was detailed from the photographs holding to multiplex detail points.

29. SUPPLEMENTAL DATA

None

30. MEAN HIGH WATER LINE

The mean high water line was delineated from the field inspection photographs. From stereoscopic examination of the photographs, the mean high water line as picked by the field inspection party seemed reasonably accurate. In a few places there was slight disagreement but this is considered of minor importance and therefore a special note of each case is not considered necessary.

31. LOW WATER AND SHOAL LINES

Low-water and shoal lines have been shown both from data furnished on the field inspection photographs and from office interpretation. It is felt that these data are in need of completion and verification by the hydrographic party. See Review Report for T 8647

32. DETAILS OFFSHORE FROM THE HIGH WATER LINE

All instances of offshore rocks and ledge which were discovered and in need of verification and location by the hydrographic party have been noted on the discrepancy overlay. Several fish traps have also been noted on the overlay.

33. WHARVES AND SHORELINE STRUCTURES

There are very few wharves and shoreline structures on this quadrangle. It is believed that all in the area have been shown.

34. LANDMARKS AND AIDS TO NAVIGATION

There are three non-floating aids to navigation shown on the map manuscript, namely, CHANNEL ROCK DAYBEACON, COFFINS ROCK DAYBEACON, and HALFTIDE ROCK DAYBEACON. HALFTIDE ROCK DAYBEACON is a triangulation station. The positions of the two aforementioned beacons have been determined from sextant fixes. See paragraph 26.

See Review Report.

106

34. LANDMARKS AND AIDS TO NAVIGATION (Continued)

There are no old landmarks on this quadrangle. One new landmark has been recommended, namely, STACK. Its position is being submitted on forms 524 and 567. Chart Letter 68 (48)

35. HYDROGRAPHIC CONTROL

The positions on the map of all photo-hydro points are believed to be within the limits of accuracy required for charting. Refer to "Compilation Report" for details of plotting.

Several photo-hydro points have been omitted from the map for the following reasons:

Nos. 2812, 2814, 2816, 2822, and 3315 were in areas that apparently have been cut over subsequent to the time these stations were chosen. The diapositives used were made from a reflight taken after the time of the field inspection. The photographs used in the reflight were 588 to 591 taken May 30, 1946.

No. 3151 was not plotted, as its accuracy to within the required limits was very improbable.

An obvious error was found, in the field book, in the compass directions for stations Nos. 3289 through 3304. Changes were indicated in red pencil. During the editing of the descriptions, in all cases where there was doubt, that part of the description that appeared doubtful was omitted.

36. LANDING FIELDS AND AERONAUTICAL AIDS

None

37. GEOGRAPHIC NAMES 814 Approved list filed in Geographic Names Section

No special survey has been made of geographic names. All names appearing on the map have been taken from U.S.C. & G.S. Chart No. 305, published March 1931 (4th edition), scale 1:40,000. A list of these names has been prepared and accompanies this report.

38. JUNCTIONS

Junctions have been made as follows:

To the east with T-8645  
To the south with T-8648  
To the west with T-8643

The junction to the north with the Cherryfield, Me. quadrangle, U.S.G.S., 1:62,500, is not satisfactory. The details at the junction, have been enlarged to scale of 1:10,000 and shown on the discrepancy overlay.

See Review Report Item 48.



### 39. BOUNDARIES

There was no special report for Boundaries which covered this quadrangle. Those boundaries shown were obtained from data furnished on the field inspection photographs. As the information concerning boundaries is incomplete, township lines have been taken from the U.S.G.S. quadrangle, Cherryfield, Me., and shown on the discrepancy overlay for further investigation. See Field Edit and Review Report

### 40. MILITARY GRID

The military grid, as required in the instructions, does not appear on the map. The grid had been requested by the compilation office but was not furnished by the Washington Office. Not required.

### 44. COMPARISON WITH EXISTING TOPOGRAPHIC QUADRANGLES

Comparison was made with the Cherryfield, Me. quadrangle, U.S.G.S. edition of 1904, scale 1:62,500. The planimetry was in good agreement except, of course, that fewer details are shown on the U.S.G.S. quadrangle. The contours were only in fair agreement.

There are several churches shown on the U.S.G.S. quadrangle which had not been identified by the field inspection party. These have been noted on the discrepancy overlay for further investigation.

There are also four churches shown on the U.S.G.S. quadrangle which our field inspection party has identified as schools. These have also been indicated on the discrepancy overlay.

All discrepancies checked by Field Editor.

### 45. COMPARISON WITH NAUTICAL CHARTS

The quadrangle was compared with Chart No. 305, U.S.G.S. dated March 1931 (4th Edition). The details were in good agreement, especially shoreline details. There were, nevertheless, a few places in the shoreline where agreement was poor. Several offshore rocks and ledges shown on the chart do not appear on map manuscript. These have been noted on the discrepancy overlay for further investigation.

A cut-out portion of Chart 305, on which all important discrepancies between the chart and the map have been noted, has been submitted with the "Notes to the Hydrographer".

~~After the completion of the field edit and hydrographic surveys, it is believed that this compilation should supersede all previous charted information.~~

Respectfully submitted  
23 December 1947

Henry P. Eichman  
Photogrammetrist  
Descriptive Report and Review

Melvin M. Lautman  
Photogrammetric Aid  
Compilation


Stanley W. Trout  
Supervisor

Barnice Wilson  
Engineering Aid (Cartog.)  
Compilation

Approved and forwarded

7 January 1948

Thos. B. Rind  
Officer in Charge  
Baltimore Photogrammetric Office





NOTES  
FOR  
HYDROGRAPHIC PARTIES  
EASTERN MAINE

TOPOGRAPHIC MANUSCRIPT, SURVEY NO. T-8644

PROJECT NO. CS-272-F

Attached is a descriptive list of photo hydro stations to be used as hydrographic signal sites.

Attached also is a cut-out section of U.S.C. & G.S. Chart No. 305, scale 1:40,000. Circled in red ink are rocks, ledges, small islands, which have not been located on the new map manuscript.

Respectfully submitted  
30 December 1947

  
Photogrammetrist

Approved and forwarded

  
Thos. B. Reed  
Officer in Charge  
Baltimore Photogrammetric Office

COAST OF MAINE  
HARRINGTON QUADRANGLE  
PROJECT CS-272-F  
SURVEY NO. T - 8644

DESCRIPTIONS OF PHOTO-HYDRO STATIONS TO BE USED AS HYDROGRAPHIC  
SIGNAL SITES

Described by: Field Inspection Party

Edited by: Melvin M. Treatman  
Photogrammetric Aid

Bernice Wilson  
Engineering Aid (Cartog.)

Reviewed by Harry P. Eichen  
Photogrammetrist

No. of Station	Description	Photo. No.
1382	18' spruce tree at the NW end of a group of deciduous trees on SW end of a dirt bluff. Station is the only spruce tree in the vicinity. 5' above MHW.	798
1383	30' juniper tree on the NW end of woods. There is a 20' bushy deciduous tree $1\frac{1}{2}$ m. NW of the spruce. Station is about 25 m. NE of edge of marsh. 4' above MHW.	798
✓ 1384	Red brick chimney on a $1\frac{1}{2}$ story gray shingled house. Chimney is in center of ridge of main section of house. There is a one story addition to the north. 35' above MHW.	798
1385	30' spruce tree on the west end of sand beach. There is another double spruce tree just north of station. Spruce is on edge of 8' bank. 10' above MHW.	798
1392	Most northeasterly of a line of spruce trees along 10' grass bank on west side of small cove about 40 meters SW of point of land and about 10 meters SW of double 30' juniper tree. 11' above MHW.	798
1393	20' spruce tree at the base of a 15' grass bank. Tree leans to the west and is most easterly of group on west edge of marshline. 4' above MHW.	798
2501	Center of 5' brown boulder about 12 meters north of MHWL. Boulder is the largest in the area and is about 75 meters NE of marsh. 2' above MHW.	798
2502	20' unblazed spruce on the woods line on small point of top of very large gray ledge boulder on the SE side of small cove. Base pricked. Station is about 3 meters west of MHWL. There is a spruce of equal size about 1 meter west of the station. 9' above MHW.	798
2503	7' gray boulder about 7 meters SE of MHWL. It is split on west and north sides. Boulder is largest in the vicinity. Station has been pricked on the NE side of boulder which is highest point of rock 4' above MHW.	798



No. of Station	Description	Photo.No.
✓ <u>2504</u>	Station is the north gable of main section of two story house. Main ridge has two chimneys. North and west sides of house are painted orange. There is a one story addition on the northeast side and three outbuildings about 4 meters to the northeast. There are 4 fruit trees in yard to the east. Recoverable photo topographic station. 40' above MHW.	797
G 2505	Station is the northeast gable of one room frame cottage. Roof is red tar paper and sides painted white. There is a one story addition on SW side. Station is about 20 meters west of MHWL. There is another cottage, white with green trim, about 20 meters south of the station 30' above MHW.	798
2506	Station is a 45' spruce tree at base of 6' bank. There is a clearing just south of station. On the south side of clearing there is another tall spruce tree which leans north. 3' above MHW.	797
2507	Station is the center point on brown ledge rock boulder, 10' in diameter, just south of small cove about 8 meters east of tree line. Top side of west end of rock flush with ground while east side is about 4' above the ground. There is a 4' gray boulder about 4 meters west of station; a triple trunk birch tree directly inshore; and another boulder about 22 meters offshore to the east which is covered 3' at MHW. 2' above MHW.	797
2508	Station is a multi-trunked deciduous tree at the southwest end of a red-brown and dark strip of ledge about 10' wide between woods and shore. Tree leans to the east and sits on the woods line. There is a small 15' birch about 2 meters west of station. Base of the tree is about 5 meters west of MHWL. There is a large birch tree about 22 meters north of station. This 30' birch sits on the southwest end of dark ledge rock strip slightly thinner but otherwise similar to the one mentioned before. Trunks of station tree are intertwined. Another similar dark strip of ledge rock ends on woods line about 45 meters southwest. 4' above MHW.	797
+ 2509	Station is the point on base of church steeple which is about 35' high. Steeple on northeast end of 1½ story building. The first story is painted white and the upper half story is painted green. Roof is unpainted shingle. Front entrance of church is in base of steeple. Double shutter windows in upper part of two sides of steeple. There is a one story building about 10 meters east of station with unpainted shingle roof. 70' above MHW.	797

No. of Station	Description	Photo. No.
<u>2510</u>	Station is a 60' twenty-five year old red brick chimney on west side of concrete stone and brick ruins about 15 meters west of MHWL and about 60 meters south of mouth of small creek. Large concrete platform beginning about 10 meters east of chimney. A 1x3 opening 13' high on side of chimney. Base is pricked. Recoverable photo topographic station. Also landmark. 5' above MHW.	797
2511	Station is the gray boulder on the south end of large rock ledge. There is a large dark strip of ledge 3 meters southeast of the boulder. Boulder is just inside MHWL. 4' above MHW.	797
✓2512	Station is a red brick chimney midway between main gables and offset to southeast of ridge about 1'. Chimney is on two story house. The first story is painted white and the second story green. There are a double window and a door on the first story of northeast side and two windows on the second story. 45' above MHW.	796
2513	Station is the 15' double birch tree on the east side of large cove about 5 meters off MHWL. 4' above MHW.	796
✓2513A.	Station is the north tip of wreck on east side of cove. There is a ruin of a boat bottom just to the southeast on shore. It is east of a small ledge rock island. One double and one single birch tree 1 or 2 meters south on grass line. Four trunked birch about 15 meters east of station also on grass line. 6' above MHWL.	796
2514	Station is the 5' light gray boulder 3 meters west of MHWL. Three meters east of brush line. Just south of gravel beach. A boulder beach lies just south of station. 5' above MHW. Station inshore from point of ledge.	796
2515	Station is the 15' unblazed spruce about 9 meters west of MHWL. Station is 6 meters south of 18' triple birch tree; 3 meters north of 12' triple birch tree; about 8 meters north of large spruce stump which is on slight point of land. It is about 70 meters north of small sand beach in cove.	796
2516	Station is the southeasterly of two 35' unblazed spruces about 12 meters northwest of MHWL on grass line. There is a large clearing to the southwest about 18 meters west of north end of black strip of ledge rock. 5' above MHW. Photo 796.	
2527	Station is the 25' unblazed spruce tree on grass and brush covered bank about 10' above brushline. Station is about	

No. of Station	Description	Photo. No.
2527 (cont'd.)	9 meters north of MHWL and 10 meters east of MHWL, about 5 meters west of 30' spruce, and about 8 meters northeast of wall of ledge rock on large point of land. 15' above MHW.	798
x2528	Station is the red brick chimney in the center of ridge of west section of unpainted 2½ story frame house. Another chimney on smaller of two sections of house offset about 5' to north of center between south gable and where ridge joins roof of main section. Barn in need of repair in yard to southeast. Full length front porch on west side of main section. 45' above MHW.	798
2529	Station is the 30' unblazed spruce tree about 3 meters east of MHWL. Tree is most northern spruce in group on east side of cove. There is a small channel about 10 meters long running northwest to southeast. Has its SE end three meters west of station. 6' above MHW.	798
2530	Station is the 30' unblazed double spruce tree about 11 meters southeast of MHWL and about 3 meters south-east of brush line which is on top of 9' dirt bluff. Spruce is largest in vicinity and about 15 meters east of north tip of ruins of old wharf. 12' above MHW.	798
2531	Station is the 20' unblazed double spruce about 10 meters east of MHWL, 5 meters east of grass line, and about 15 meters northeast of 12' multi-trunk deciduous tree which is about 3 meters east of point of grass line which is on top of boulder bluff about 10' high off MHWL.	798
2532	Station is the 35' unblazed spruce about 20 meters north of MHWL. Spruce is the southernmost of a line of spruce leading out from grove. There are large clearings to the east and west and it is about 12 meters to grass line on which are scattered small trees and bushes. 11' above MHW.	798
2533	Station is the 30' double spruce about 22 meters north of MHWL about 15 meters north of grass line in middle of the north end of cove; about 13 meters west of westernmost spruce in grove of evergreens. 11' above MHW.	798
2534	Station is a leaning 35' spruce at head of small cove	

No. of Station	Description	Photo. No.
2534 (cont'd.)	on edge of grass line. There is a 2' gray boulder 10 meters southeast of the base of the tree. 3' above MHW.	798
2535	Station is the most southerly of two spruces on the south side of small cove on side of 8' grass bank. They are the only spruces in the vicinity. 4' above MHW.	798
2536	Station is a 30' spruce tree on northeast of small cove. There are birch trees on east side of it. There is a small pile of rocks at base of tree. 3' above MHW.	798
2537	Station is a 25' spruce tree on point on edge of tree line on south side of small cove area. There is white ledge directly in front of signal. 4' above MHW.	798
2538	Station is the most southerly tip of grass on rock island. There are two spruce trees just in shore from signal. There is a small pile of rock on south tip. 8' above MHW.	798
2539	Station is the 25' spruce on point of land. There is a 15' spruce 2 meters southeast and a tree stump 2 meters south on edge of tree line. 3' above MHW.	798
2540	Station is a 25' spruce 32 meters south of small creek, 8 meters inside of brush and tree line. Tree leans slightly to the north and is marked with a stick and blazed. 8' above MHW.	798
2541	Station is the most northerly spruce in group of 3 in center of clearing of earth bank. There is a leaning spruce 28 meters to the southwest. Tree lays on southeast side and is blazed on the southeast side. 3' above MHW.	798
2542	Station is a 25' spruce tree on point. There is a large 6' boulder one (1) meter to the south. Spruce is on edge of tree line on south side of small creek. It is blazed on the east side. 2' above MHW.	798
<u>2543</u>	Station is a red brick chimney on a 1½ story yellow frame house with green trim. Chimney is midway between gables offset about 1' from ridge. There is a full length porch and a dormer on the east side. Recoverable photo topo station. 30' above MHW.	798

No. of Station	Description	Photo. No.
<u>2544</u>	Station is a prominent large boulder which is most easterly large boulder in mud flats. Boulder is 80 meters northeast of two large rocks in mud flats and 75 meters southwest of large pointed rock. It is 63 meters southeast of tree line and 75 meters north of small island. No topo disk required because of station's prominence. Recoverable photo topo station. 3' above MHW.	798
2545	Station is the 40' unblazed spruce on the northwest side on cove about 8 meters northwest of MHWL; about 45 meters southwest of made over 2½ story red with yellow trim barn, (door on the southeast side) and about 4 meters northwest of grass line. Tree becomes double at height of about 29'. 8' above MHW.	798
2546	Station is the 35' spruce tree which is northeasterly of small group of spruce and tallest of group. There is a lone 13' spruce about 6 meters northeast. Station is about 3 meters northwest of brush line. Tree is blazed on the east side. 8' above MHW.	1144
2547	Station is the 3' brown gray boulder about 6' long north to south and 5' wide. Station is about 4 meters southeast of MHWL and appears to be isolated at MHW. There is a 5' white gray boulder with black moss on north side about 2 meters to the west. 1' above MHW.	1144
2548	Station is the most northerly of two large spruces leaning to the east. Station is double spruce about 40' tall about 3 meters west of MHWL. Station is about 35 meters south of point of land. There is a 25' dead spruce on MHWL with length north to south. 6' above MHW.	1144.
2549	Station is the 17' spruce tree about 6 meters southwest of MHWL on northeast corner of woods about 8 meters northwest of southernmost tip of marsh. Spruce has flat top and is blazed on northeast side. 3' above MHW.	1144
2550	Station is the 40' spruce about 10 meters inshore from brush line; on south side of break in marsh. There is a 25' birch tree 10 meters northeast of spruce on edge of brush line and a dead spruce 10 meters southeast of spruce. 7' above MHW.	1144
2551	Station is a 35' spruce in northern corner of grove blazed on the northwest side of edge of marsh line 50 meters southeast of old pier. 2' above MHW.	799

No. of Station	Description	Photo No.
2552	Station is large 40' leaning spruce on top of 4' bank on south side of small clearing. There is a dead birch in clearing 8 meters to the N. There is a dead birch 5 meters from spruce with no branches. The spruce is blazed on the E. side. 5' above MHW.	799
2553	The most westerly tree on point of land on back limits of marsh on edge of tree line. Tree is blazed on NW side. There is a small birch 15 meters SE of spruce. 3' above MHW.	799
<u>2554</u>	"AGAR, 1945" - 4' round flat boulder, bares 1' at MHW, 10 m. offshore from group of spruces, largest boulder in vicinity, 3 m. W. of limits of marsh as seen by navigator. There is a 20' leaning spruce 12 m. to the SW on side of earth bank 8 m. N. of break in marsh. Marked "AGAR, 1945". 1' above MHW	1145
2555	15' spruce tree at edge of dirt bank. There are no branches on lower half of trunk. There is a 20' birch tree 12 meters to the NE. There is a 25' overhanging maple about 15 meters NE of spruce. The maple almost leans horizontally from bank. 7' above MHW.	1145
2556	Station is 30' spruce on the point of land 6 meters E. of dead spruce tree on edge of tree line. There is a leaning maple about 12 meters E. of the spruce. 3' above MHW.	1145
2557	15' spruce tree on south side of large marsh area. Tree is most NE'ly of group of spruces. There are dead birch tree trunks 5 meters N. and S. of spruce tree. On woods line there are two 6' poplar trees 1 meter from spruce on edge of line 2' above MHW	1145
2558	20' leaning spruce tree on the S. side of small clearing on edge of 4' bank. There is a dead leaning spruce 2 meters to the E. and a flat top 10' double spruce 7 meters N. in clearing. Tree blazed on SE. 4' above MHW	1145
2559	Station is 15' spruce on point of land just N. of a long ledge. There is a dead double trunk birch tree 6 meters to the S. at a base of ledge. Tree blazed on the SE side. 4' above MHW.	1145
2560	25' spruce on point of land at inshore end of ledge. There is a dead spruce 1 meter to the N. on the edge of tree line. Tree is blazed on one side. The base is pricked. 2' above MHW	1145
2561	30' spruce on the point of the NE side of a large cove. There is a 15' spruce to the E. and a dead spruce 3 meters to the NW. Tree is blazed on the E. side. The base is pricked. 7' above MHW.	1145



No. of station	Description	Photo. No.
2562	Station is the 35' spruce most southerly of 2 spruces. There is a lone 10' spruce in clearing 8 meters to the south. Station is on side of 4' earth bank. Tree is blazed on the east side. The base is pricked. 5' above MHW.	1145
2563	Station is the 40' leaning spruce tree on the southern end of island. There is a double spruce 20 meters to the west and a dead spruce at the base of station. The top is pricked. 2' above MHW.	1145
2564	Station is a 15' spruce tree at point of land directly north of small island, west of small creek at edge of tree line. The tree is blazed on the south side. 1' above MHW.	1145
2565	Station is an 8' spruce tree in clearing on the northeast side of small creek. No other spruces near by. 3' above MHW.	1145
2566	Station is the 35' spruce on northern end of island on edge of brush line. Tree is the most northerly spruce on island. The base is pricked. 3' above MHW.	1145
2567	Station is the 20' spruce tree on edge of 5' earth bank. There is a lone birch tree 12 meters west of spruce on bank in clearing. There is a group of spruce trees to the east. 5' above MHW.	1145
2568	Station is the 16' spruce on tree line. There is another 12' spruce 1 meter to the south on the edge of a 3' earth bank. There are two birch trees just to the north. Station is a double spruce. There is a strip of ledge just offshore. 3' above MHW.	1145
2569	Station is the west gable of unpainted one story vacation cottage. The roof is red shingle; the middle section and east section are green tarpaper shingle and the west addition is unpainted wood shingle. There is a red brick chimney 1' west of east end of middle section and 4 windows and a door on the west side. There is a 25' flagpole with sunken base attached to the north side. Station is 13 meters east of MHWL. 16' above MHWL.	1144
2570	Station is the 13' unblazed spruce about 6 meters north of MHWL on top of 5' dirt and grass bank, about 9 meters east from point of land. There is an octagon shaped pavillion about 5 meters west. 6' above MHW.	1144
2571	Station is the 35' unblazed spruce on top of 6' grass bank about 8 meters north of MHWL and about 20 meters west of dirt bank on curved point of land. 6' above MHW.	1144

No. of Station	Description	Photo. No.
2572	Station is the red brick chimney about 3' east of midpoint between gables on 1 story white frame house with green trim. Chimney sits on south side of ridge. Two double windows and front door are on south side. There is a screened porch on the east side. A 25' flagpole stands in yard about 9 meters southwest. (Recoverable photo topo station). 30' above MHW.	1144
2573	Station is the 35' unblazed spruce about 9 meters east of MHWL. Green branches start at height of 15'. Station is about 7 meters east of brushline. 13' above MHW.	1144
2574	Station is the 27' unblazed spruce tree about 2 meters southeast of MHWL. The base of another spruce tree is 1' east of station. A very prominent 6' gray boulder rests at station on the southwest side. 5' above MHW.	1144
2575	Station is a 4' gray boulder about 6' long (east to west) and 5' wide, about 4 meters west of MHWL at back center of cove. There is another smaller boulder about 20 meters north. 2' above MHW.	1144
2576	Station is the 25' spruce tree. Tree is on steep ledge rock rise about 6 meters southeast of north tip of sharp cut in shoreline. Tree is most southwesterly of a line of spruces. 5 meters north there is a 25' birch tree. 8' above MHW.	1144
2577	Station is the most southerly spruce on small island 12 meters north of brush line. 8' above MHW.	1144
2578	Station is the 3' boulder on the west side of small cove. There is another large boulder on the southeast side of cove. Boulder is gray color on top and is located 18 meters south of grass line. 3' above MHW.	1144
2579	Station is a round gray boulder on the southeast side of small cove at the end of ledge point directly across the river from hydro. signal 2578. 3' above MHW.	1144
2580	Station is the 35' double bushy spruce tree on point of land 8 meters inshore from brush line and directly inshore from ledge point. 5' above MHW.	1144
2581	Station is the 30' broad spruce tree on edge of 3' bank on south side of cove. There is a pointed spruce 12 meters to the south. 3' above MHW.	1144
2582	Station is the most easterly of two red brick chimneys on house with four sections. Chimney is on second section from west, and three feet west of east gable of section. 30' above MHW.	1144

(21)

No. of station	Description	Photo.No.
2583	Station is the 35' bushy spruce tree on the west side of a gravel beach. There is a pointed gray boulder 18 meters to the southwest. On the edge of tree line, there is a group of spruce trees to the northeast and a 30' spruce on top of bank 12 meters to the southwest. 3' above MHW.	1144
2584	Station is the center of a 5' flattop light gray rock on the east end of a gravel and boulder beach and 18 meters southwest of boulder studded point of land. Another rock is 1 meter southeast of station. 3' above MHW.	1144
2585	Station is the 35' double spruce tree on the edge of tree-line. Tree is most northerly of a group of 3 spruces. There is a black boulder 12 meters to the south; a dead birch tree 4 meters to the north and another dead birch 6 meters to the southwest. 2' above MHW.	1144
2586	Station is the 35' spruce most northerly in a line of spruces on edge of tree line 20 meters south of point of land. There are two dead 6' tree trunks on either side of spruce tree. 2' above MHW.	1144
2587	Station is the 35' pointed spruce tree on inshore end of ledge point 4 meters north of a 40' double spruce. There is a dead birch trunk 3 meters east of spruce. There is a fallen scrub pine lying on dead birch tree trunk. 4' above MHW.	1144
2588	Station is a 3' gray boulder on the north side of cove 8 meters southeast of tree line. It is largest gray boulder in the vicinity. 3' above MHW.	1144
2589	Station is the <del>20'</del> 20' double spruce tree on point of land 8 meters west of grass line. There is a group of three dying birch trees just east of spruce. A dead tree trunk is lying against spruce on the west side. There are also two 3' tree stumps on either side of spruce. 4' above MHW.	1144
2590	Station is the white boulder with black spots located on the southeast side of small cove north of a group of birches in the center of which there is an 8' narrow spruce. There is a round, white boulder to the northwest. Directly behind is a brown boulder. 2' above MHW.	1144
<u>2591</u>	Station is the most northerly of four large boulders. The rock has a flat gray top and is the largest in the vicinity. It is marked with a standard topographic disc in the southwest corner of the rock. Marked "ABUT 1945". 3' above MHW. Recoverable photo topo station.	1144

122

No. of Station	Description	Photo. No.
2592	20' spruce tree on the SE corner of woods. There is 10' birch tree 8 meters NE of spruce and a dying deciduous tree 8 meters to the south. There is a group of birches directly inshore from spruce. 5' above MHW.	1144
2593	4' light gray prominent boulder (largest in vicinity). Boulder is on top of a brown ledge. 4' above MHW.	1144
2594	35' unblazed spruce tree. Tree is tallest on woods line on point of land and leans slightly to east. It is about 2 meters south of MHW and about 3 meters west of MHW. 1' above MHW.	1144
2595	2' gray boulder 7' long (east to west) directly on MHWL about 5 meters east of woods line. Trees hang within 2 meters of station. A brown ledge 30' north to south and 13' wide begins about 9 meters north and leads to woods line. 2' above MHW.	1144
2596	35' unblazed spruce directly on MHWL on top of edge of 7' rock bluff at foot of dirt portion of steep bank. Base is pricked. 4' above MHW.	1144
2597	5' gray boulder 8' long (southwest to northeast) and 6' wide. It is the most prominent boulder in vicinity and is on brown ledge about 3 meters east of MHWL. There is black moss on top. 4' above MHW.	1144
2598	Top of 25' unblazed spruce tree curved upward at top. Bottom of tree leans at 45° angle. The tree grows out sideways at foot of bank. It is on tip of land on woods line and is directly over MHWL. 18' above MHW.	1145
2599	25' unblazed spruce on the south side of tip of land about 6 meters north and 5 meters west of MHWL. Tree leans slightly to the east. It is 12 meters SW of 5' high 18' long (north to south) and 15' wide boulder almost split equally in two. 3' above MHW.	1145
2600	12' unblazed spruce on brush line, on the north side of tip of land about 5 meters west and 6 meters south of MHWL, - about 5 meters NW of 13' double spruce and about 10 meters west of MHWL; on tip of land on ledge rock. 4' above MHW.	1145
2601	36' unblazed white pine about 10 meters south of MHWL. Tree is comparatively bare up to height of 15' or 20'. Winds have bent the upper branches to the SE. It is 8 m. south of brush line. 9' above MHW.	1145
2602	30' unblazed spruce on MHWL, at the SW tip of large 5' gray boulder, about 11' wide (SE to NW); about 18 m. S. of S. end of 12' smooth ledge bluff, just N. of rock-pebble beach.	1144

No. of Station	Description	Photo. No.
2603	22' unblazed spruce on small point of land on woods line in grove of birch about one meter NE of MHWL. Tree grows out over water from top of ledge line on N. end of small cove. Top is pricked. 2' above MHW.	1145
2604	35' unblazed juniper about 18 m. S. of MHWL, about 15 m. NW of wooden fence. Tree becomes double at height of about 20'. There is a 22' juniper about 2 m. NE. 3' above MHW.	1145
2605	Prominent 50' spruce, most S'ly. in a group of four spruces in a large clearing. Tree is 67 m. NE of road. 15' above MHW.	1145
2606	Station is 20' bushy spruce on the side of 18' earth bank. There is a pointed leaning spruce about 15 m. to the SE and another 5' leaning spruce at base of earth bluff 8 m. NE. Tree is bushiest spruce in vicinity. 10' above MHW.	1145
<u>2607</u>	Prominent gray-black-spotted boulder just E. of a gravel pit, and just offshore from a small gravel and boulder beach. Disk is on the E. side of boulder. There is a 10' spruce tree directly inshore from boulder at edge of gravel pit. Recoverable photo topo station. 3' above MHW. Marked "AXIS 1945"	1145
2608	Top of 10' leaning spruce which is most E'ly. spruce on point of land. Tree has a branch running parallel to the trunk about halfway up. There is a 20' birch tree 1' inshore and a dead 8' spruce tree 2 m. to the W. 3' above MHW.	1145
2609	35' spruce tree leaning towards the SE. There is another large spruce 8 meters to the SE and also leaning in a S'ly. direction. There is 15' spruce growing out of one of the roots of the station on point of land in center of cove. Top is pricked.	1145
2610	Top of 30' spruce leaning E. at edge of brush line, 10 m. SE. of an earth bank. There is a 10' dead trunk 8 m. inshore. 2' above MHW.	1145
2611	30' spruce on NE point. It is the tallest spruce on point. There is a dead tree inshore from station, a dead birch 10 m. NW of station, and 3 smaller spruces N. of station. 3' above MHW.	1145
2612	20' spruce, most NW'ly on point. There is a dead birch 2 m. W. and a 4' gray boulder 6 m. W. of station. 3' above MHW. Tree is blazed on north side.	1145
2613	45' pine on E. side of small cove, largest tree in cove. There is a dead spruce 1 m. to the W. 5' above MHW.	1145
2614	30' triple-trunk spruce, most N'ly in the line of spruces on W. side of small cove and 12 m. NW of 4' gray boulder. 2' above MHW.	1145
2615	6' round boulder, largest in vicinity, midway between ledge island and woods line. 5' above MHW.	1145

124

No. of Station	Description	Photo. No.
2616	45' spruce at head of bight in ledge. There is a 3' brown rock at head of bight and a birch 1 m. N. of spruce on the W. side of bight. 6' above MHW. Tree is blazed on SE side.	1145
2617	25' spruce, most N'y. tree on point. In a clearing there is a shack 5 m. SW of station and behind shack is a birch. 2' above MHW.	1145
2618	25' spruce on point on E. side of marsh on edge of ledge bank 8 m. E. of dying 5' spruce. Blazed on N. side. 3' above MHW.	1145
<u>2619</u>	Red brick chimney in middle of ridge and gables of W. section of 2-story frame house on N. end of open grass field. Only house near point of peninsula. Another red brick chimney on section of house to E. Garage stands off to NE. Full length front porch on S. side of main section. 50' above MHW. Recoverable photo. topographic station.	1146
2620	4' round boulder about 3 m. S. of MHW. and about 5 m. S. of brushline at foot of 6' bank at point of land. About 15 m. E. of prominent 6' brown boulder. 3' above MHW.	1145
2621	4' gray boulder about 6' long E. to W. and 4' wide. About 35 m. N. of small cove. About 32 m. S. of center of white ledge. About 7 m. E. of woods line and 7 m. W. of marsh line. 1' above MHW.	1145
2622	5' gray boulder about 7' long E. to W. and 7' wide. About 2 m. E. of woods line. Station is directly on MHW. About 25 m. S. of point. Most prominent boulder near point. About 8 meters N. of S. end of dark ledge. Black moss all over top. 5' above MHW.	1145
2623	Center and high point of 7' gray and brown boulder about 12' long N. to S. and 6' wide. Boulder has pointed ridge along length of top. About 3 m. E. of MHW. and about 6 m. E. of woods line. There is a marble-like black and white 4' boulder about 1 m. N. 4' above MHW.	1146
2624	E. gable of 20' unpainted barn. Northernmost of 3 building. Unpainted shed about 25 m. SW and 1½ story white cottage with green trim is about 55 m. SSW. Barn has rolling doors on S. side.	1146
2625	30' spruce on MHW and on woods line about 30 m. N. of seven-trunked 30' birch leaning over from top of bank at 30-degree angle. Station tree is double from 15' up. On south side of point. 0' above MHW.	1146
2626	25' flat-top spruce, leaning slightly to E. It is SE. of edge of woods, about 4 m. W. of MHW. on top of 8' grass and earth bank. There is a 22' double spruce 2 m. E. 8' above MHW.	1146

No. of station	Description	Photo.No.
<u>2627</u>	"ANUS", 1945" - 10' brown rock, diamond-shaped, long N. to S. There is another large brown boulder 19 m. to the NE of station and E. of a point of land. Marked "ANUS, 1945". Disk is in center of rock 3' above MHW. Recoverable photo. topo. station.	1146
2628	5' gray boulder about 30 m. NE of ledge point of land. There is a 3' brown boulder in shore. Station is NE about 8 m. from a line of 3 boulders. 3' above MHW.	1146
2629	Most SW'ly of two 25' junipers, about 38 m. NW of point and about 33 m. N. of an 8' earth bank. 12' above MHW.	1146
2630	25' lone spruce on N. side of creek, in a group of deciduous trees, 10 m. N. of tree line, and about 50 m. inshore of a small cove in creek. 5' above MHW.	1146
2631	12' unblazed blue double spruce about 5 meters NE of MHWL on grass line about 3 meters SW of nearest spruce. 4' above MHW.	1143
2632	25' unblazed double spruce on NE side of cove about 3 m. NE of MHWL on top of 7' dirt bank with brush on top. There is a small clearing to the NE. 7' above MHW.	1143
2633	25' blazed spruce about 4 m. east of MHWL on the SW corner of cove about 7 meters south of 4' white boulder. Tree is blazed on the west side. 6' above MHW.	1143
2634	30' unblazed spruce tree about 4 m. east of MHWL. There is a dead stump about 4 m. N. and a 4' round boulder about 2 m. SW. The boulder is white. 4' above MHW.	1143
2635	10' blazed spruce about 12 m. N. of MHWL. Most SW'ly tree on point. It is blazed on the SW side. There is a clearing on brush line about 4 m. S. of nearest spruce, 5' above MHW.	1143
2636	30' unblazed spruce about 19 meters NE of MHWL. It is 9 m. NE of grass line. There is another blue spruce slightly shorter about 11 m. NW. 6' above MHW.	1143
2637	15' unblazed double spruce about 15 m. N. of MHWL about 10 m. N. of grass line. It is the tallest tree in group of 3 trees and is NW'ly in group. There is a 9' double spruce about 2 m. N. and a 13' spruce 3 m. E. 7' above MHW.	1143
2638	10' lone spruce about 7 m. W. of MHWL. Tree is double and stands in open field about 2 m. W. of grass line. 8' above MHW.	1143

No. of Station	Description	Photo. No.
2639	30' blazed spruce which is most SE'ly. of group of three spruces. Double spruce stands 1 meter to the N. of station. There is a 4' spruce 3 m. SE. Station is directly inshore from rocky ledge. It is blazed on the E. side. 2' above MHW.	1143
2640	Station is the 30' unblazed spruce tree about 3 meters W. of MHWL, about 25 m. S. of tip of ledge rock on point. It is the largest tree near point on the SE side of cove. 3' above MHW.	1143
2641	12' unblazed spruce directly at center of back of cove about 2 meters W. of MHWL. There is a small clearing to the W. A 3' stump stands at base of tree on the S. side. 1' above MHW.	1143
2642	40' unblazed spruce tree in center of small cove on the N. side of larger cove. There are no green branches below height of 12'. It is the largest tree in cove about 2 meters N. of MHWL. 1' above MHW.	1143
2643	30' unblazed spruce N.E'ly. of line of three spruces. The other two are double 30' spruces. Station is about 1 m. S. of MHWL, and about 5 m. W. of MHWL. 1' above MHW.	1143
2644	28' unblazed spruce tree about 4 m. NW of MHWL on grass line about 30 meters SW of W end of small fishing pier. 4' above MHW.	1143
2645	4' white boulder on the MHWL on the W. side of point of land about 15 m. SW of point of land at MHW about 3 m. NE of grass line. 4' about MHW.	1143.
<u>2646</u>	4' white boulder on the SE side of island about 4 m. N. of MHWL and about 11 m. E. of MHWL. It is the most prominent single boulder on beach. Station is at the center; highest point of the boulder. It is marked "EDDY, 1945". Recoverable photo topo station. 2' above MHW.	1143
2647	Station is the 25' unblazed spruce about 30 meters north of small cove. Tree is on MHWL and overhangs the water. It grows on top of rock bluff. Tree is made double by a very small trunk up to a height of about 10'. At MHW.	1143
2648	35' unblazed spruce about 4 meters north of MHWL and brush line. Another flat top 30' spruce is about 2 meters SE. Station is on the W. side of clearing and is tallest tree in group. 10' above MHW.	1143



No. of Station	Description	Photo. No.
2649	35' unblazed spruce on small point of land on woods line growing on top of ledge bluff. There is a 10' spruce about 1 m. S. 2' above MHW.	1143
2650	20' unblazed double spruce. Tree is the most SW'ly on point of W. side of point. It is about 35 m. N. of MHWL, about 30 m. W. of MHWL and about 3 meters E. of MHWL. 8' above MHW.	1143
2651	30' unblazed shaggy spruce on S. side of cove. Station is the tallest tree on the S. side of cove and is about 3 m. W. of MHWL. 3' above MHW.	1143
2652	5' brown boulder about 40 meters SE of small cove and about 3 meters E. of MHWL. Station is about 7 m. E. of 2.5' boulder. 2' above MHW.	1143
2653	2.5' white round boulder about 1 m. S. of MHWL, 3 m. N. of MHWL, 3 m. W. of MHWL, 3 m. E. of grass line, 8 m. E. of woods line, and about 4 m. SW of highest point of ledge rock on small point. 3' above MHW.	1143
2654	5' spruce on the S. side of sandy beach cove about 10 m. NW of overhanging spruce. Tree is most easterly of group of small spruces on edge of bank. There is a group of rocks and a pole at base of tree. 7' above MHW.	1143
2655	20' unblazed spruce tree about 7 m. N. of MHWL. Tree grows on top of 8' dirt bank and leans about 45° to the E. There is a 2.5' white rock about 5 meters north. 10' above MHW.	1143
2656	13' unblazed spruce growing on top of 15' sand bluff. It is about 5 meters W. of MHWL. A 15' spruce grows about 2 m. SW. An 18' birch grows about 5 m. SW. 16' above MHW.	1143
2657	35' double spruce on the tree and marsh lines about 40 meters NW of points of land, about 3 m. NE of a 40' juniper and about 6 m. NW of a 35' juniper. 2' above MHW.	1143
2658	30' umbrella-like unblazed spruce about 4 m. W. of MHWL. Tree is double up to height of about 15'. There is an odd shaped 30' spruce which grows out horizontally and curves up and over water 2 m. NE. 3' above MHW.	1143
2659	30' spruce about 15 m. W. of ledge point of land on woods line with many base roots exposed. It is about 7 meters W. and 5 m. E. of fine sand beach. Tree is blazed on the N. side. 2' above MHW.	1143

No. of Station	Description	Photo. No.
2660	40' spruce tree about 25 m. SE of point of land about 6 m. N. of MHWL and about 13 m. SE of dead 35' birch tree. Station tree grows about 1 m. north of top of 6' dirt bank. 8' above MHW.	1143
2661	20' bushy spruce most NW'ly on island. There is a dead 5' spruce about 8 m. to the SE. 6' above MHW.	1143
2662	20' double bushy spruce on edge of grass line. There is a group of small spruces just to the E. and a 4' spruce 10 m. to the S. 3' above MHW.	1143
<u>2663</u>	On top center of boulder just E. of high point of 5' pointed gray permanent boulder (the largest in the vicinity). Boulder has a crack about halfway from its base on the south side. Boulder is on MHWL. It is 7 meters NW of a 7' double spruce, and about 13 m. S. of a group of spruces which are on the S. side of a clearing. There is a 12' leaning spruce about 10 m. to the NE. Marked "CAFE 1945". Recoverable photo topo station. 4' above MHW.	1142
2664	Double 18' spruce tree. It is the most easterly in a group of three spruces. Only the bottom half of the tree to the west remains. 2' above MHW.	1142
2665	4' brown boulder which is the largest in the cove. It lies about 5 m. SW of MHW. There is a line of small spruce trees to the north. 2' above MHW.	1142
2666	18' spruce tree most westerly on point of land. It is about 40 m. E. of MHWL. There are some small spruce trees just in rear of signal tree. It is blazed on the W. side. 4' above MHW.	1142
2667	18' bushy double spruce tree on point of land in small cove. There is a rock ledge in front of tree. Just NE of signal there are three large spruces. 5' above MHW.	1142
2668	30' double spruce at head of small creek on N. side. There is a small clearing to the NW and there are a group of spruces in clearing 10 m. to the NW. Station is on edge of 4' bank. 3' above MHW.	1142
2669	30' dying spruce tree on the W. side of small cove. Tree leans toward the east. There is a small rock just in front of the station. There is a 25' birch growing beside the station. 2' above MHW.	1142

No. of Station	Description	Photo. No.
2670	30' pointed spruce tree at the extreme southern end of cove. There is a dead birch about 10 m. to the NE. Tree is about 8 m. S. of MHWL. 4' above MHWL.	1142
2671	25' spruce most westerly in a group of three spruces just west of a small cove. There is a rock ledge just in front of station. 2' above MHW.	1142
2672	10' double spruce on edge of ledge bank just inside of MHWL. It is on the SW side of large cove and is most NW'ly spruce on the S. side of cove. It is just north of brush line about 25 m. NE of group of small birches. 2' above MHW.	1142
2673	25' spruce which is most westerly of the spruces about 10 m. SW of a dead birch. There are dead tree stumps about 15 m. W. of spruce on edge of bank. Spruce just east of station is more bushy. 10' above MHW.	1142
2674	20' spruce tree on edge of rock cliff. There is a rock ledge directly in front of station. There is a dead stump about 20 meters north of tree. It is about 8 m. east of MHWL. 3' above MHW.	1141
2745	Station is the tip of grass on the NE corner of island. There is a 3' bush just inshore from grass point. 4' above MHW.	1145
2746	30' and most E'ly. of a few of spruces on a rounding point. There is a dead birch 4 m. to the W. and a small clearing to the E. that has small spruces in it. 2' above MHW.	1145
2747	20' spruce on rounding point. There is a group of 8' spruces to the S. and another group of 6' spruces about 10 m. to the N. Blazed on W. side. 3' above MHW.	1145
2748	Leaning 40' pine on the N. side of a small cove. It is the largest pine in the cove. 2' above MHW.	1145
2749	40' spruce, most westerly on E. side of cove. Station tree has few branches on lower half. There is a group of spruces to the E.	1145
2750	25' dying fir, most northeasterly on point. There is another dying fir 1m. to the W. Blazed on east side. 3' above MHW.	1145
2751	20' double spruce, most southeasterly on point. There is a group of dead trunks SW of station. 2' above MHW.	1145

No. of Station	Description	Photo. No.
2752	35' spruce in center of brushy clearing which has junipers on both sides. There is a 25' spruce 4 m. E. of station. 5' above MHW.	1145
2753	30' spruce on E. side of stream, largest spruce on point. There are two 6' spruces to the SE. 2' above MHW.	1145
2754	35' bushy spruce, largest & most northerly spruce on S. side of stream. 4' above MHW.	801
2755	Lone 35' double spruce on N. side of stream, on edge of brush line. 2' above MHW.	801
2756	40' pine, largest in area, at head of stream. 5' above MHW. <del>5' above MHW.</del>	801
2757	Lone 25' spruce on W. side of stream, on brush line. Dead trees on both sides of station. 2' above MHW.	801.
2758	North gable of most westerly section of 2 story house. There is a large deciduous tree to the W. 40' above MHW.	801
2759	20' double spruce at edge of 10' bank on point. 5m. NW of station. There is an 8' spruce at base of bank. 10' above MHW.	1146
2760	40' pointed spruce at head of cove. Tallest tree in head of cove. 2' above MHW.	1146
2761	25' bushy spruce, 25 m. south of point. There is a 7' spruce 6 m. to the N. and a group of birch trees on both sides of station. 2' above MHW.	1146
<u>2762</u>	"AREA, 1945" - NE corner of 5' gray boulder on brown ledge, 4 m. W. of tree line and S. of a small cove. There is a 3' brown boulder 1 m. to N. of station, a group of 3 spruces to NE of station on bank, and a 45' spruce about 18 m. to S. of station. 6' above MHW. Recoverable photo. topo. station.	1146
2763	40' spruce, blazed on E. side. There is a prominent white birch about 12 m. to S. and a very large boulder about 20 m. to S. of station. 2' above MHW.	1146
2764	40' spruce. There is a dead Y-shaped birch 4 m. to SW. 6' above MHW.	1145
2765	25' leaning spruce, blazed on E. side, about 20 m. NE of point. There is another 25' leaning spruce 8 m. to the NE. 2' above MHW.	1145

No. of Station	Description	Photo. No.
2765A	Top of 35' leaning spruce, top third of which is vertical. There is a flat-topped 20' spruce 6 m. to the N. from base of station and a group of gravel and rock boulders just off-shore from base of station tree. 4' above MHW.	1145
2766	3' gray boulder off point of land, and 8 m. SW of earth bank. There is another large boulder 5 m. to the E. 3' above MHW.	1145
2767	15' spruce, most southwesterly, There is a group of birch trees to the NW. Station is in a brush area. 8' above MHW.	1145.
2768	12' spruce on the NE corner of island. There is a 3' double spruce 4 m. north of spruce. Spruce has a double trunk on top and is blazed on the NE side. 6' above MHW.	1144
2769	Most SW spruce on island. It is 12' high. There are two other attached spruces to the north. 4' above MHW.	1144.
2770	40' double spruce just southwest of a small clearing. Clearing has a group of dead stumps in it. Tree is blazed on the northwest side.	1144
2771	30' bushy spruce. There is another similar tree 10 m. to the west. There is a small clearing just to the NE. 4' above MHW.	1144.
2772	The largest boulder on island. The boulder is grey. It is 8 m. northeast of grassline and on northeast side of island. 5' above MHW.	1144
2773	25' spruce which is most northeasterly on island just inside brush line. There is a group of birches to the west. 3' above MHW.	1144
2774	20' leaning spruce just north of rounding point. There is a 2' grey boulder 20 meters to the north. There are two dead birches on each side. 1' above MHW.	1144
2775	20' leaning spruce tree most southerly on island. There is a dead birch tree 1 m. to the north. 2' above MHW.	1144
2776	40' prominent pine at head of small cove. It is the largest tree in cove. 2' above MHW.	1144.
2777	20' spruce most westerly on point of land about 4 m. east of grassy point. There is a 4' spruce at its base. 5' above MHW.	1143
2778	30' leaning spruce on the east side of small cove. Spruce leans southwest. There is a birch tree 4 meters to the NW. 3' above MHW.	1143

No. of Station	Description	Photo. No.
2779	Top of leaning spruce at head of cove. The top third of tree is vertical and the trunk is crooked. The tree is blazed on the west side. 2' above MHW.	1143.
2780	25' leaning spruce on point. There is a small clearing just inshore. Tree is most westerly tree on point. There is a 1' spruce inshore 2 m. 3' above MHW.	1143
2781	15' spruce on point of land. There is a 12' spruce 2 m. south and a dead birch tree 4 m. to the west lying on edge of grass line. 3' above MHW.	1143
2782	20' double spruce on point. There is a bushy 25' spruce 25 m. to the southeast. Station is the most southwestern tree on point.	1143.
2783	40' spruce about 25 m. south of a small cove. There is a dead birch 8 meters to the north and another 6 meters to the south. Tree is blazed on the west side. 3' above MHW.	1143
2784	30' double spruce on the southwest side of a small clearing. There are two spruces directly inshore. It has 3 trunks at base. 3' above MHW.	1143
<u>2785</u>	Station is the 8' pointed light gray boulder with black spots on top. It is on north side of small cove. It is the largest boulder in the vicinity. Recoverable photo topo station. Stamped "DAMP 1945". 8' above MHW.	1143
2786	15' bushy spruce on southwest side of island. There is a 3' spruce 6 m. to the southwest on edge of 10' bank. Spruce has a flat top.	1144
2787	18' spruce in center of small clearing. There is a 6' spruce 1 meter to the south. 7' above MHW.	1144
2788	20' spruce 5 meters southeast of a dead spruce. There is a group of spruces to the south in line with station. It is blazed on the north side. 2' above MHW.	1144
2789	Dark 4' boulder 40 meters south of rounding point. It is the largest boulder on the east side of cove. It is on a brown ledge 4' above MHW.	1144
2790	10' spruce just south of an earth bank clearing that has 3' spruce in center of it. Spruce is in center of ledge. There is a dead birch 2 m. to the north and a small dead birch in center of clearing. 1' above MHW.	1144

No. of Station	Description	Photo. No.
<u>2791</u>	Prominent ledge like rock that is brown colored with green spots on top. There is a ledge bank to the north that runs from station to point of land. There is a large flat rock ledge to the south. A dead 7' double spruce lies 1 m. inshore. The south side of station (rock) is almost square and vertical. Rock was once part of rock ledge. There is a space of about 2' between ledge and bank. There is a pointed rock 2' from north-east corner. Station is on the south end of rock. Marked "BARK, 1945". Recoverable photo topo station. 6' above MHW.	1144
2792	Station is the 25' spruce on northern end of island. There are no branches on the lower half of tree. There is a 20' spruce 4 meters to the east which has a clump of branches at the top. There is a group of three spruces to the south-east and a small birch 6 meters to the southeast. 8' above MHW.	1144
2793	Top of 35' leaning spruce which leans to the southeast. There is another leaning spruce to the north. There is a 4' brown boulder 10 meters to the NE. 4' above MHW.	1144
2794	25' spruce on the west side of brush clearing. There are a 15' spruce 1 meter to the west and a birch with four trunks 8 meters to the west. 1' above MHW.	1144
2795	NE gable of 1 story tarpaper shack. A door and two windows are on the SE side. 15' above MHW.	1144
2796	6' grey-topped boulder just offshore from a leaning juniper. There is a small group of rocks around a large rock. There is another prominent boulder 70 meters SW and another smaller boulder is 38 m. SE. 4' above MHW.	1144
2797	4' brown boulder 20 m. SW of a small cove. Boulder is on black ledge. There is a 7' double spruce 14 m. to the NE. 3' above MHW.	1144
2798	30' spruce on point on east side of cove. There is a 3' grey boulder 3 m. to the South. There is a 2' light grey boulder 6 m. to the SW. 3' above MHW.	1144
2799	18' spruce on top of ledge bank in clearing. It is on NE side of cove. There is an 8' bank to the NW. A juniper is 8 m. to the N. 7' above MHW.	1144
2800	8' spruce on point in cove just inshore from a gravel and rock beach. Spruce is on edge of 8' bank and there is some brush on side of bank 4 m. to the NE. 8' above MHW.	1144
2801	25' spruce on the west side of cove on edge of bank. There is a 7' birch 4 m. north and a many trunked birch 15 m. to the N. There is a large ledge 3 m. to the S. and a brown boulder 3 m. to the E. and on the N. side of bank. 5' above MHW.	1144

134

No. of Station	Description	Photo. No.
2802	25' spruce on the SE side of gravel and boulder beach. Tree is most NW'ly on the southeast side of beach about 100 m. SE of small cove. 4' above MHW.	1142
<u>2803</u>	SW gable of 2½ story yellow-shingled brown-trimmed house. There are three chimneys on the house. 50' above MHW. Recoverable photo topo station.	1142
2804	40' double spruce on SE side of small clearing. There is 2-story house in back end of clearing. There is a 50' spruce directly inshore. 8' above MHW.	1142
2805	NW corner of rock cribbing. There are three more cribbings from station to shore. 50' above MHW.	1143
2806	25' spruce tree on the north side of a small opening in ledge. There is a birch at back end of opening. There is a one foot grey rock at base of station. 5' above MHW.	1143
2807	25' spruce on south side of a small cove. There is a group of birches just to the north. There is a 25' pointed spruce 2 m. to the north. 4' above MHW.	1143
2808	20' spruce at head of small cove. There are birches to the east and a whitewood tree to the northwest 10 meters. There is a spruce at the base of bank 1 meter from ledge. 2' above MHW.	1143
2809	15' spruce on rounding point. It is the most westerly spruce on point. It is just inshore from black ledges. 4' above MHW.	1143
2810	15' bushy cedar tree at back limits of rock ledge. There is a large group of dead brich behind cedar. 2' above MHW.	1143
2811	20' spruce on north side of cove. There is a group of tall spruces directly behind station and there are gray boulders at the base. There is a dead birch 7 meters to the northwest. Tree is blazed on the south side. 4' above MHW.	1143
2813	18' spruce just north of point at base of 15' bank. 2' above MHW.	1144
2815	45' pine on point on north side of small cove at edge of 5' bank. 5' above MHW.	1144
2817	Chimney on the east gable of one-story shack on island. There are no other shacks on the island. 20' above MHW.	1144



No. of Station	Description	Photo. No.
2818	30' spruce on north side of island just east of small clearing. There is a 40' spruce 8 meters to the south. There is a group of small spruces 2 meters to the west. The tree is blazed on the north side. 6' above MHW.	1144
2819	South gable of dilapidated shack with the door on the south side. There is another shack just inshore. 12' above MHW.	1144
2820	40' double spruce on rounding point. There is a small clearing just inshore. Station is on side of 5' bank and there is a 1' tree stump 2 meters to the east. 3' above MHW.	1144
2821	3' brown boulder on ledge. There is a 25' birch 5 meters to the east. There is a 2' grey boulder 6 meters northeast. 4' above MHW.	1144
2823	40' pointed spruce at head of cove. There is a dead birch 1 m. to the west. It is on the west side of small clearing. There are a few branches on the bottom half.	1144
2824	4' grey boulder. It is the largest boulder offshore from the point. There are smaller boulders nearby. 3' above MHW.	1144
2825	25' spruce on the southeast side of cove. The lower half of tree is bare of branches. Tree leans to the north. Blazed on the north side. 1' above MHW.	1144
<u>2826</u>	6' brown boulder on point 10 meters north of leaning spruce. 15 meters to the west is a dying, leaning pine. Disk is in side of rock to south. Marked "BABE 1945". 3' above MHW. Recoverable photo topo station.	1144
2828	12' spruce most NW'ly on island just north of brush line. Tree is blazed on the north side. 3' above MHW.	1142
2829	10' spruce on the east side of point most NE'ly on island. Tree is blazed on the east side. 5' above MHW.	1142
2830	Lone 20' spruce on the SE side of gravel beach. There is a tree stump 7 meters to the NW. 1' above MHW.	1142
2831	25' spruce 10 meters south of clearing and 60 m. SW of rounding point. 10' above MHW. east	1142
2832	30' spruce on the <u>side</u> of cove. There are four smaller spruces to the south. Station is blazed on the west side. 6' above MHW.	1142
2833	18' spruce which is most Northerly on point of land. There is a group of 3 spruces on the SW. Tree is blazed on the north side. 6' above MHW.	1142

No. of Station	Description	Photo. No.
2834	Lone 25 spruce on the north side of small creek. There is a small pear tree 20 meters southwest. 2' above MHW.	798
2835	30' pine tree at the SW end of small creek on the west side. There is a leaning pine 30 meters to the north and a dead tree 2 meters north of leaning pine. At MHW.	798
2836	One 30' spruce on the south side of stream. There is a group of dead birches 10 meters to the north. 3' above MHW.	798
2837	25' pointed spruce just back of rounding point of marsh on west side of entrance to small stream. 3' above MHW.	798
2838	45' pine on the north side of stream. The lower half is bare of branches. 2' above MHW.	798
2839	Top of leaning spruce on north side of stream. There is a 12' spruce at its base. 1' above MHW.	798
2840	50' pine on the south side of stream. There are no branches on the lower half. 6' above MHW.	798
2841	25' spruce on the southeast point of land. Spruce is about 12 meters SE of woods line. There is another spruce 12 meters to the north. 2' above MHW.	799
2842	30' dying spruce (most northern on point of land). There is another spruce 3 meters to the SE. 3' above MHW.	799
2843	30' bushy spruce on the east side of stream. There is a bushy double spruce 10 meters to the southeast. Tree is 10 meters SW of a group of spruce and deciduous trees. 2' above MHW.	799
2844	30' double spruce which is most northerly and tallest in a group of spruces. 2' above MHW.	799
<u>2845</u>	Red brick chimney on the northeast side of house 1 meter south of north edge of roof and 1 meter east of ridge. House is a 2 story grey-shingled cottage. The porch is on the south side. There is another chimney on the south side of the house. 50' above MHW. Recoverable photo top station.	799
2846	35' double spruce on the south side of stream on the east side of small clearing on edge of tree line. 4' above MHW.	799
2847	NE point of fast land. A board with a nail in it is in a tree stump nearby. There is another stump 3 meters northwest. A 4' bush also grows on the point of land. 2' above MHW.	799

No. of Station	Description	Photo. No.
2848	35' double spruce on west side of earth dike. It is the most southerly and largest of a group of spruces. 2' above MHW.	799
2849	35' spruce on point of fast land. Tree has 2 trunks on upper third and a few branches on the lower half. Station is on the SE side of small clearing. There is a 35' spruce 1 m. to the east. 1' above MHW.	799
2850	35' pointed spruce (most SE'ly and tallest in group) on east side of small stream, just NW of a small clearing. There are two 20' spruces 3 m. to the SE. There is a 25' spruce 12 m. to the SE. 2' above MHW.	799
2851	40' spruce 10 m. NW of brush point. Station is the tallest and most SE'ly on point. There is a dead tree stump 1 m. to the south. Tree is blazed on the south side. 3' above MHW.	799
2973	20' spruce just north of a group of dead spruces. There is a leaning spruce 1 m. to the east. There is a group of birches to the E. There is a large dead birch 20 m. to the north. Station is blazed on the south side. 1' above MHW.	799
2975	40' pointed spruce on SW corner of woods. There is a 30' pointed spruce 1 m. to S. 1' above MHW.	799
2976	35' pine on point on W. side of stream. 3' above MHW.	799
2977	30' spruce surrounded by small spruces, on top of small hill at head of creek. 20' above MHW.	799
2978	35' spruce at head of stream on NE side of point. Most S'ly and tallest spruce on point. There is a large group of trees on point. 4' above MHW.	799
2979	25' pointed spruce on N. end of a line of trees. There is a 3' post 6 m. to E. Post is in marsh. 2' above MHW.	799
<u>2980</u>	Chimney in center of 2 story house (shingled). It is the only lone house in the group. The ridge of house runs north and south. There are two windows in the south side of second story and 2 windows in east side of first story. Recoverable photo topo station. 45' above MHW.	799
2981	35' spruce at base of 3' bank. There is a juniper 7 meters to the south. There is a 10' spruce 8 meters to the north. 1' above MHW.	799
2982	20' spruce most southerly in group of three spruces at edge of woods line. 3' above MHW.	799

No of Station	Description	Photo. No.
2983	15' dark spruce at edge of woods line. Spruce is at west end of line of stakes. There is a line of junipers to the northwest. 1' above MHW.	799
2984	25' spruce about 40 meters SW of grass and water area in center of stream. Spruce is at edge of tree line. 2' above MHW.	799
2985	Top of overhanging spruce 6 meters south of dead birch tree; 18 meters south of a small marsh area. The top is pricked. 2' above MHW.	799
2986	15' spruce on east side of creek on point of land. There is a group of smaller spruces to the east. 3' above MHW.	799
2987	30' spruce on the northeast side of small marsh cove. It is the most NE'ly spruce on north side of cove. 1' above MHW.	799
2988	Most easterly of two 35' spruces in line with a group of other spruces. 2' above MHW.	799
2989	12' double, lone, spruce on W. side of small cove. 6' above MHW.	1145
2990	15' spruce, most W'ly of two. There is a rock 12 m. to SW. 3' above MHW.	1147
<u>2991</u>	Chimney on E. gable of 2-story shingled house. Chimney is 1' S. of the gable. There is a wider chimney on the W. gable. Enclosed porch on S. side of house and 4 windows on E. side, one of which is a double window. 50' above MHW. Recoverable photo. topo. station.	1147
2992	18' double, lone, very bushy spruce on W. side of stream. 2' above MHW.	1147
2993	8' spruce, most southerly of two, 10 m. S. of woods line, in grassy clearing. 3' above MHW.	1146
2994	45' pine, most northerly of three (at back limits of marsh point). There is a double pine 10m. to SW. 4' above MHW.	1146
2995	45' pine, most northerly of two. There is a group of overhanging spruces 15 m. to NW. 4' above MHW.	1146
2996	35' spruce, with few branches on lower half, at back limits of marsh. 2' above MHW.	1146
2997	18' pointed spruce on point. There is a 15' spruce 1 m. to E. and a dead trunk 2 m. to S. 5' above MHW.	1146
2998	25' spruce, most NW'ly in group.	1146.

No. of Station	Description	Photo. No.
2999	30' spruce, most NW'ly of two at base of 10' earth bank. There is a similar group of spruces 10 m. to NW, and a dead tree on bank 10 m. to E. Station tree is leaning to SW at a 45 degree angle. 3' above MHW.	1146
3000	50' pointed spruce. There is a group of smaller spruces to the N. 3' above MHW.	1146
3001	25' spruce on E. side of stream, 10 m. W. of tree line. There is a dead birch 8 m. to E. and a 10' spruce 8 m. to S. with no branches on lower half. 2' above MHW.	1146
3002	Lone 15' spruce on top of hill at head of stream. Group of taller spruces on either side. 30' above MHW.	1146
3003	25' spruce at SW corner of woods line, tallest and most southerly on points. 2' above MHW.	1146
3004	30' spruce about 30 m. SE of marsh point, most easterly spruce on W. back limits of marsh cove. 4' above MHW.	1146
3005	30' spruce inshore from 3 birches. There is a group of dead spruces 4 m. to SW. 3' above MHW.	1146
3006	15' spruce, most northwesterly tree on rounding point. 2' above MHW.	1146
3007	15' dark spruce on point. There is a dead tree 1 m. to South. Gravel and boulders offshore. 4' above MHW.	1146
3008	20' dark bushy spruce, about 10 m. S. of bank. There is an overhanging spruce lying at its base. There are overhanging spruces to N. but none to S. 4' above MHW.	1146
<u>3009</u>	SE gable of 2 story large white house. There is a chimney on center section, another on SE section, a dormer on center section, and a shingled-roof porch on S. side. 45' above MHW. Recoverable photo topo station.	1146
3010	35' pine with few branches on middle half, on edge of woods line. There is another 35' pine about 80 m. to South. 2' above MHW.	1146
3011	30' pine, about 10 m. SW of 1½ story, unpainted, house, and 20 m. SE of barn, 25' above MHW.	1146
3012	12' spruce, partly hidden in deciduous trees, on E. side of entrance to stream, on edge of woods line. There is a 35' pine about 10 m. to the E. and a 20' spruce 10 m. to the NE. 1' above MHW.	801



No. of Station	Description	Photo. No.
3013	Lone 30' pine. There is a 20' spruce to the S. 2' above MHW.	801
3014	30' bushy spruce on point. There is another 30' spruce to the SE. In between them there is a double juniper. 3' above MHW.	801
3015	7' spruce on point, about 13 m. W. of tree line. 2' above MHW.	801
3016	Lone 40' spruce. There is a dead trunk 3 m. to the N. 1' above MHW.	801
3017	15' spruce on edge of earth bank. There is a dead birch and spruce along side. At MHW.	801
3018	Long 10' spruce in center of clearing. There is a lone dead 30' tree 2 m. inshore. 1' above MHW.	801
3019	4' spruce on N. side of small clearing on point. There is a 25' juniper 5 m. to NW. 1' above MHW.	801
3020	15' lone, bushy, spruce, about 10 m. W. of MHW. There is a group of dead birch trees on MHW. 4' above	801
3021	35' spruce on point. There is a 25' spruce 10 m. to SW. 3' above MHW.	801
3022	20' pine on N. side of large group of birch trees. A dead tree is 12 m. to S. on edge of bank. 1' above MHW.	801
3023	40' spruce on edge of wooded section between two marsh-lined stream entrances. (North of 3022, about 1/2 mile.) 1' above MHW.	801.
3024	40' double spruce, 25 m. NW of highway bridge. Group of small pines surrounding station. 3' above MHW.	801
3025	40' spruce tree, most northerly of two. 3' above MHW.	801
3026	Lone 30' spruce on fence line in clearing. 6' above MHW.	801
<u>3027</u>	Chimney in center of 2 story frame house, white with green roof. There are 3 windows on SE side and a door and window on NE side. Ridge of roof runs NW & SE. 50' above MHW. Recoverable photo. topo. station.	801
3028	30' spruce with few branches on upper half. A group of birch trees to NE. 2' above MHW.	801
3029	40' pine, about 12 m. W. of point of fast land, and inshore from a double 25' spruce. 4' above MHW.	801

No. of Station	Description	Photo. No.
3030	35' pine on the NW corner of woods. There is a small leaning spruce at its base. Station is on east side of river. 3' above MHW.	801
3031	30' lone spruce on edge of mostly deciduous woods, and on point of fast land on back limit of marsh. There is a 50' pine tree about 20 m. to the W. of station. 3' above MHW.	801
3032	10' lone bushy spruce on back edge of marsh. There is a 6' spruce to the North. Station is about 1/2 mile south of 3031. 3' above MHW.	801
3033	30' pointed spruce tree on back edge of ledge. There is a birch tree 3 meters to the southeast. There is a spruce tree (double) 5 meters to the SE. 7' above MHW.	1141
3034	25' spruce tree on the north end of gravel beach. There is a double birch tree 20 meters to the north. 4' above MHW.	1141
3040	Most southerly of two 20' spruce trees. There is a dead 4' tree between the two spruces. Station is two meters inshore. 5' above MHW.	1142
3041	50' pointed spruce tree about 10 meters southwest of small gravel beach. It is tallest spruce at back end of beach. There is a group of smaller spruces at offshore side. Station is 7 meters from MHWL. 4' above MHW.	1142
3042	35' spruce tree about 12 meters east of northeast corner of island. Tree is blazed on the north side. 4' above MHW.	1142
3043	8' spruce tree growing out of rock ledge bluff. There is a 1' spruce tree 4 meters to the south. There is a brush clearing to the northeast. 6' above MHW.	1142
3044	7' flat topped spruce tree on the southwest side of cove on the back edge of ledge. 4' above MHW.	1142
3045	25' spruce with a birch lying 1 m. to NE. of its base. Station is at edge of wooded point on W. side of Five Is. Cove. 2' above MHW.	1145
3046	25' pointed spruce. There are two dead birch trunks, one 6 m. to west and the other 1' to east. 5' above MHW.	1145
3047	35' spruce, leaning slightly to the NE. There is a dead birch at its base, 3 thin birch trees to the S, and a 45' double spruce 5 m. to SW. 4' above MHW.	1145
3048	12' spruce, 1 m. S. of a dead birch. Station is the tallest spruce S. of the sandy point. 4' above MHW.	1146

No. of Station	Description	Photo. No.
3049	40' spruce, blazed on N. side, at head of cove, and on W. side of fast land point. 2' above MHW.	1146
3050	15' double spruce in center of small clearing at head of inlet. Station is also on edge of road. 2' above MHW.	1146.
3051	25' spruce, most southeasterly on point. There is a 15' spruce 1 m. to W. 5' above MHW.	1146
3052	2' gray boulder, about 10 m. E. of 10' earth bank, NE. of a rounding point. It is largest boulder on the beach. 1' above MHW.	1146
3053	30' lone, broad spruce, SW of 8' earth bluff. 7' above MHW.	1146
3054	18' juniper about 14 m. NW of point and at end of brush line, and on N. side of inlet. 3' above MHW.	1146
<u>3055</u>	"ZUNI, 1945" - Station is two inch white rock imbedded approximately in top center of 10' boulder which is 8 m. E. of MHW in the middle of a cove, the largest boulder in the vicinity, and of gray-green color, spotted black on top. 4' above MHW. Recoverable photo. topo. station.	1146
3056.	2½' light gray boulder. There is a leaning deciduous tree at woods line inshore about 8 m. to the N. 2' above MHW.	1146
3057	30' lone spruce at edge of woods line. There is a small birch 1 m. inshore. 2' above MHW.	1146
3058	20' spruce on edge of woods line, S. of clearing. There is a 15' spruce 3 m. to SW. 3' above MHW.	1146
3059	30' spruce, most southerly on island. About 1½ miles south of 3058. 3' above MHW.	1146
3060	12' poplar in center of small island. About 2 miles south of 3059. 3' above MHW.	1145
3061	3' clump of brush on extreme N. end of island. 3' above MHW.	1145
<u>3084</u>	NW corner of one story white frame bungalow having stairway on the west side. There is a red brick chimney on sloping roof which is not visible from shore. There is an extension to house on the northeast side. 40' above MHW. Recoverable photo topo station.	1144
3100	Stone chimney on south part of 2 story shingle house. There is an outbuilding 10 meters north of main house. The house is on the west side of island. It is the only house on the island. 40' above MHW.	1136

No. of Station	Description	Photo. No.
3101	25' spruce tree which is the most easterly of a group of three 25' spruce trees on point of land about 6 meters north of edge of woods line. 12' above MHW.	1136
3102	30' lone spruce tree on the NE part of small cove on the NW side of island at edge of grass line. It is about 20 meters NE of protruding rock ledge. 5' above MHW.	1136
3103	15' spruce on the NW side of small gravel beach in small inlet. There is an overturned spruce trunk 2 m. SE of station. Station is at edge of grass line. 5' above MHW.	1136
3104	4' bushy spruce tree 5 meters SE of 1½ story cottage on N. side of walk leading to cottage. 6 m. to the NE there is a very large spruce at edge of grass line. 5' above MHW.	1136
3105	Lone 32' spruce tree on small point. 20 m. to the NW is a grey shingled 1-story cottage. There is a large 10' timber 4 meters from the tree on the north side. 4' above MHW.	1136
3106	Lone 20' spruce on the NW side of cove on the north edge of group of alders. 10 meters to the NW there is a dark green 25' spruce. Station is 6 meters from MHWL. 4' above MHW.	1136
3107	SE gable of 1½ story light grey shingled house. There is a small porch on the NE. There are two small windows directly under the gable. There is a stone seawall in front of house. 25' above MHW.	1136
<u>3108</u>	Red brick chimney on the east side of 1½ story grey shingled house. The chimney runs from ground to 5' above roof. There are 2 more chimneys on the west side of house. There is a grey garage 12 meters to the northeast of house. There is a 30' spruce 4 meters from west end of house. There is a small porch on the south side of house and a small balcony on the west side of house. House has cement posts for foundation. Station is 20 m. NW of MHWL. Recoverable photo topo station. 30' above MHW.	1136
3109	Large 3' white boulder 5 meters from MHWL at head of cove. It is the largest boulder in the vicinity and there is a smaller white boulder 9 meters to the west. 1½' above MHW.	1136
3110	Large white 3' boulder 4 meters from MHWL, 11 meters west of rock bluff. There is a flat white 1' rock on west side of station directly beside it. 1' above MHW.	1136
3111	15' spruce on small point. There are 2 dead tree trunks 1 meter and 10 meters to the west of station. Tree is blazed. It is 12 meters from the MHWL. 9' above MHW.	1136
3112	8' spruce tree on rock point 12 meters from MHWL. Tree is blazed. 4 meters to the NW is a 15' bushy spruce. 6' above MHW.	1136

144

No. of Station	Description	Photo. No.
3113.	22' lone spruce tree on very edge of 8' rock bank. There are a number of large boulders on shore in front of station. Station is 8 meters from MHWL. 13' above MHW.	1136
3114	13' spruce on extreme north end of island. It is 6 meters from MHWL. There are some smaller scattered spruces in back of station. 6' above MHW.	1136
3115	14' spruce tree blazed on the south side of 13' bluff which is shaped like a small point. Tree has no branches on the lower half. 11' above MHW.	1136
3116	3' white boulder. 5 meters to the W. on grass line is a dead birch tree. Station is 2 meters from MHWL. At MHW.	1136
3117	23' spruce on the SW side of very small point. It is on the north end of gravel and boulder beach. Station is 4 meters from MHWL and is blazed on the east side. 4' above MHW.	1135.
<u>3118</u>	Very large 8' grey boulder almost in the center of gravel beach. West end is on grass line and the east end is 5½ m. from MHWL. There is a 40' spruce tree 4 m. to the S. and a 16' spruce 1 m. to the north with some of its branches hitting on and over the rock. Marked "BUNK 1945". Recoverable photo top station. 10' above MHW.	1135
3119	23' spruce tree 1 meter in back of edge of grass line and 8 meters west of MHWL. There is a dead birch tree 1 meter to the east. Station is blazed on the east side. 2' above MHW.	1135
3120	3' white boulder 4 m. north of grass line. It is the only white boulder in the vicinity. There is a group of dead birches inshore from boulder. Station is 2 meters from MHWL. 1/2' above MHW.	1134
3121	30' spruce tree on edge of grass line and 6 m. south of MHWL. There is a group of birches to the east and west. Station tree is blazed on the north side. 5' above MHW.	1134
3122	Red brick chimney in center of 2 story grey-shingled house. House has porch on the north side and 2 windows on the second story on the north side. 48' above MHW.	1134
3123	8' spruce tree on the end of point most northwesterly on point and smallest on point. There is a 20' spruce 4 meters to the south. Tree is blazed on the west side. 4' above MHW.	1134
3124	45' leaning spruce tree. The largest in the vicinity. There is a 3' white boulder 4 meters to the west. The tree is blazed on the north side. 4' above MHW.	1134

No. of Station	Description	Photo. No.
3125	20' spruce tree at bottom of 10' earth bank. 1' to NE is a dead birch tree. Station is 8 meters NW of MHWL. Tree is blazed on the NW side. 3' above MHW.	1134
3126	3' brown boulder 6 m. on the west side of MHWL and 12 m. W. of brush line. 4 m. to the south is large flat black ledge. Station is on north side of very small point. 2' above MHW.	1134
3127	30' double spruce tree at very edge of grass line on top of large black, flat ledge with white strips on it. Both trunks are blazed on the north side. 3' above MHW.	1134
3128	45 large brown boulder 8 m. west of MHWL, and 18 meters west of brush line. It is the largest boulder in the vicinity. Inshore to the NE is a group of large oak trees. 3' above MHW.	1134
3129	Large brown and white 5' boulder on the south side of point. It is the largest boulder in the vicinity and a very prominent boulder. It is on MHWL and 12 meters to the SW of the brush line. 3' above MHW.	1134
3130	20' spruce tree on the edge of grass line. There is a dead tree trunk 1' to the south. To the southwest is a white rock. Tree is blazed on the west side. 3' above MHW.	1134
3131	18' spruce on small rounding point of land on the west side of group of birches, and dead trees. Spruce is on edge of brush line.	1134
3132 ✓	Red brick chimney 2' west of east gable of 1½ story grey-shingled house. There are 2 windows on the west side and 3 windows and a door on the south side. 30' above MHW.	1134
3133 ✓	Ball on top of flagstaff which is on the west gable of a grey shingled pavillion (open). 30' above MHW.	1134
3134	13' spruce on top of rock bank on edge of grass line. 10 meters to south are two cedar trees. Tree is blazed on the west side. 5' above MHW.	1134
3135	6' brown boulder, largest in vicinity. There is a large, bushy spruce 20 m. inshore. 2' above MHW.	1134
<u>3136</u>	"SINK, 1945" - 4' white boulder, largest in vicinity, and located on south end of a 6' rock cliff. There is a smaller white rock 1 m. to S. on very edge of grass line. 6' above MHW. Recoverable photo topo station.	1134.

No. of Station	Description	Photo. No.
3137	Lone 15' spruce, blazed on W. side, on S. side of small point, on edge of grass line, and 8 m. E. of MHW. 4' above MHW.	1133
3138	12' spruce with no branches on lower half, blazed on N. side, in head of small cove. 4' above MHW.	1133
3139	18' spruce, blazed on W. side, at edge of grass line, and 4 m. E. of MHW. There is a line of birch trees along shore to N. 6' above MHW.	1133
3140	7' spruce, blazed on W. side, at head of cove, on edge of grass line, 7 m. E. of MHW, and surrounded by birch trees, and dead birch trunks. 4' above MHW.	1133
3141	30' juniper, blazed on NW side, 6 m. E. of grassline and 11 m. E. of MHW. There is a 15' juniper 2 m. to NW. 3' above MHW.	1133
3142	9' spruce blazed on N. side, 4 m. SE of MHW, on N. side of point, on edge of grass line. 6' above MHW.	1133
3143	Lone 35' double spruce in clearing, and on N. side of small gully running east from the shore. 10' above MHW.	1133
3144	18' spruce, blazed on NW side, on point, at edge of grass line. 4m. E. of MHW. 1' above MHW.	1133
3145	File of rocks, 3' high, containing a 6' pole, on point of land, and 2 m. S. of MHW. 1' above MHW.	1133
3146	Lone 13' bushy spruce, on edge of 5' earth bank, 1 m. S. of grass line, and 6 m. S. of MHW. 5' above MHW.	1133
<u>3147</u>	"BOIL", 1945" Station is on a sharp point of white ledge. Station is 3 m. NW of grass line, and one to three m. inshore from the MHW. The point is on the south side of entrance to Timber Cove. Station marker is covered by a small flat rock. 2' above MHW. Recoverable photo topo station.	1133
3148	20' spruce on edge of grass line. Three meters to the S. is a dead spruce trunk. 5 meters to the north is a leaning 23' birch tree. Station tree is blazed on the east side. 5' above MHW.	1135
3149	35' spruce 5 meters south of grass line and 12 meters south of MHWL. It is the largest spruce in near vicinity. It is blazed on the north side. 8' above MHW.	1135
3150	12' spruce 2 meters SW of bottom of 25' sand bank. It is 8 m. SW of MHWL in center of bank. Tree is blazed on the NE side. 5' above MHW.	1135



No. of Station	Description	Photo. No.
3152	28' spruce on very edge of grass line. It is the most S'y tree on the SW end of land. 6' above MHW.	1135
3153	32' spruce on the NW end of land. There is a dead birch 6 meters to the NE. The station tree is blazed on the NW side. 5' above MHW.	1135
3154	Center of large brown 4' boulder. It is the largest in vicinity. Boulder is 20 meters north of MHWL. 1' above MHW.	1135
3155	30' spruce on very edge of grass line. Station is 1 meter from MHWL. Tree is blazed on the north side. 1' above MHW.	1135
3156	3' white boulder 5 meters north of grass line and MHWL. It is the only boulder in the vicinity. 2' above MHW.	1135
3157	Very large 45' double spruce on edge of grass line & MHWL. Tree is blazed on the north side. 3' above MHW.	1135
3158	NE gable of 1½ story grey shingled house. There are two small and one large window on the east side of the house. There is a barn on the North and South side of house. 35' above MHW.	1134
3159	20' spruce 2 meters north of brush line and 8 meters north of MHWL. There is a birch 1 meter to the west. Station is blazed on the south side. 4' above MHW.	1134
<u>3160</u> x	Red brick chimney in center of 2 story red shingled house. On east side of the roof, there are 2 dormer windows. On first floor on east side there are 4 windows and a door. On the north side there is a one-story, grey shingled addition. 6 meters to the NE, there is a garage with green doors. There is a line of spruces in front of house on the edge of shore. Station is 72 meters north of MHWL. 30' above MHW. Recoverable photo topo station.	1134
3161 x	Red brick chimney on the south side of roof of 2 story grey shingled, green-trimmed house. The house has porch on the south side. 32' above MHW.	1134
3162	10' spruce with no branches on the lower half of edge of grass line. It is 5 m. NW of MHWL. Tree is blazed on the SE side. 2' above MHW.	1134

148

No. of	Station Description	Photo. No.
3163	24' spruce on edge of grass line on small point. Tree has no branches on north side. Tree is blazed on the south side. 5' above MHW.	1134
3164	18' spruce on point on edge of grass line and 4 meters north of MHWL. Tree is blazed on the south side. 4' above MHW.	1134
3165	13' spruce in small cove 8 meters north of grass line and 12 meters north of MHWL. Tree is blazed on the south side. It is the most westerly of a group of trees on the south side of road. 4' above MHW.	1134
3166	Station is the east gable of 1½ story green and white, shingled house. There are three windows on the east side. There is a porch on the south side. There is a dormer with 2 windows on the south side. 25' above MHW.	1134
3167	West gable of 1 story brown, shingled cottage. There is one window on the west side and a porch on the south side. 21' above MHW.	1134
3168	12' fir tree on the east side of point. It is the most NE'ly tree of a group on the point. The station tree is blazed on the east side. 5' above MHW.	1134
3169	35' spruce in clearing 15 meters south of small camp. The tree is 7 meters N. of grass line and 16 meters N. of MHWL. 6' above MHW.	1134
3170	26' bushy spruce on small point 5 meters west of grass line and 10 meters west of MHWL. Station is blazed on the east side. 4' above MHW.	1134
3171	West gable of 1½ story brown log cabin with red shutters. There is a brown, tile chimney on the west side. Station is 15 meters north of grass line. 22' above MHW.	1134
3172	23' spruce on edge of grass line and on MHWL. Tree is blazed on the west side. Station is on edge of 14' rock bluff. 4' above MHW.	1134
3173	12' spruce on side of 6' grass bank. It is 3 meters north of grass line and 6 meters north of MHWL. There is a dead tree 8 meters to the NW. 4' above MHW.	1134
3174	Red brick chimney on the east end of white frame 1½ story house. There are four windows and a door on the south side. 32' above MHW.	1134
3175	12' spruce on edge of grass line and 2 m. W. of MHWL. Tree is most northerly of a group of spruces. It is blazed on the east side. 4' above MHW.	1134

149

No. of Station	Description	Photo. No.
3176	22' spruce 3 meters west of grass line and 8 meters west of MHWL. There is a smaller spruce 1' to the south and 1 meter to the north. Tree is blazed on the east side. 7' above MHW.	1134
3177	4' white boulder which is the only white boulder in the vicinity. It is 8 meters east of grass line and 4 meters east of MHWL. 2' above MHW.	1134
3178	18' spruce on edge of brush line and 3 meters NW of MHWL. It is on north end of sand and gravel beach. Tree is blazed on the east side. 3' above MHW.	1134
3179	Lone 30' bushy spruce on point in small cove. There are some dead birches to the SE. 4' above MHW.	1134
3180	20' spruce on the NE side of cove 5 meters NE of brush line and 9 meters NE of MHWL. There is a 25' bushy spruce 2 m. to the NW. 8' above MHW.	1134
3181	30' bushy spruce on the NE side of cove. It is on edge of brush line and 4 meters east of MHWL. 22 meters to the S. is a line of large spruces. 4' above MHW.	1134
3182	20' spruce on edge of grass line and MHWL. It is at top of 8' rock bluff and is blazed on the east side. 6' above MHW.	1134
3183	3' white boulder in center of small cove. It is the largest in cove and is 2 m. east of grass line and on MHWL. 3' above MHW.	1134
3184	22' spruce on small point of land 2 meters west of grass line and 3 meters west of MHWL. There is a smaller spruce 2 m. to the west. 5' above MHW.	1134
3185	White cement chimney on the west side of roof next to ridge pole. House is white framed with black tar paper roof. House has four windows on the south side. 40' above MHW.	1134
3186	Lone 20' spruce on edge of brush line on rock ledge and 4 m. E. of MHWL. Tree is blazed on the W. side. 5' above MHW.	1134
3187	28' bushy spruce with double top on NW end of island. It is the largest tree on island. 5' above MHW.	1134
3188	Lone 17' bushy spruce on the E. side of island. It is on edge of grass line. Tree has no branches in the middle third. 3' above MHW.	1134

No. of Station	Description	Photo. No.
3189	Lone 12' spruce in head of cove in center of 12' grass bank 6 m. N. of MHWL. It is 4 meters north of grass line. 5' above MHW.	1134
<u>3190</u>	Center of 5' white boulder 5 meters south of grass line. It is 20 m. NW of point of land on rock ledge. It is the only large white boulder in the vicinity. It is on the MHWL. Marked "CARE 1945". Recoverable photo topo station. 6' above MHW.	1134
3191	20' spruce tree on the SW part of cove. There are 3 other spruces southeast of station. Station is on edge of grass line. It is blazed on the SE side. 4' above MHW.	1134
3192	Lone 20' spruce on the NE part of cove on edge of grass line. There is rock ledge at base of tree. 4' above MHW.	1134
3193	Lone 20' double spruce tree on edge of grass line. It is about 50 meters north of point of land. 2' above MHW.	1134
3194	Lone 22 spruce, 2 m. W. of grass line, and 4 m. W. of MHW. Station is blazed on E. side. 8' above MHW.	1134
3195	20' spruce, on top of 8' bank. Station is most easterly of a line of spruce trees, and the third tree from north end of line of spruces. 8' above MHW.	1134
3196	Brown 6' boulder, largest in vicinity, 19 m. E. of brush line, and 16 m. E. of MHW. There is a 3' white boulder 14 m. to NW. 3' above MHW.	1133
3197	17' spruce on top of 12' bank. It is most southeasterly of a group of spruces. 11' above MHW.	1133
3198	17' spruce, blazed on N. side, on edge of grass line. There is a small boulder 1' to W. and a line of spruce trees 10 m. to SW. 2' above MHW.	1133
3199	15' spruce, blazed on N. side, on edge of grass line, and most northwesterly tree on small point. 4' above MHW.	1133
3200	Lone 20' spruce on east side of cove. There is a small gully 6 m. to N. 4' above MHW.	1133
3201	22' spruce, blazed on N. side at edge of grass line, and most NE'ly tree on point. 5' above MHW.	1133
3202	Lone 18' fir tree, blazed on W. side, on edge of grass line, and on east side of cove. 3' above MHW.	1133

No. of Station	Description	Photo. No.
3203	Lone 20' spruce, blazed on E. side, 2 m. W. of MHW, on point on west side of cove, and on edge of grass line. 1' above MHW.	1133
3204	Dying 25' spruce, blazed on E. side, on very edge of grass line, 2 m. W. of MHW, and on S. side of small rounding cove. 1' above MHW.	1133
3205	25' spruce, blazed on east side, largest spruce of edge of grass line. 3' above MHW.	1133
3206	4' spruce, most southeasterly on small ledge point in middle of larger cove. 4' above MHW.	1133
3207	18' spruce, blazed on SW side, most southwesterly on point. There is a 10' spruce 1 m. to SW. 5' above MHW.	1133
<u>3208</u>	East gable of 2-story frame house, white with brown trim. Station is on wing to SE of main section of house and there is also a wing to NW of main section. House has 3 red brick chimneys; and there are 2 windows and a door on south side. 18 m. to W. is a large 2-story, grey shingled barn with a bell cupola; 20 m. to NE is a long low chicken house, and 16 m. to south is a 40' deciduous tree. Station is 26 m. NW of MHW. 50' above MHW.	1133
3209	Black 5' boulder, with brown spike in top, largest boulder in vicinity, 10 m. E. of brush line, and 6 m. E. of MHW. 1½' above MHW.	1133
3210	18' fir, blazed on E. side, on edge of brush line, and 4 m. W. of MHW. Station is at bottom of 15' bank that has leaning and fallen trees on it. 2' above MHW.	1133
3211	Large, brown 4' boulder, only boulder on beach, 16 m. N. of brush line, and 10 m. N. of MHW. 1' above MHW.	1133
3212	10' spruce, in center of 16' bank, most northeasterly of a group of spruce trees. 8' above MHW.	1133
3213	4' green and black boulder, largest in vicinity, 8 m. E. of brush line, and 2m. E. of MHW. 3' above MHW.	1133
3214	Lone 12' spruce, on top of 15' bank, and with few branches on lower half. 16' above MHW.	1133
3215	4' white and green boulder, largest in vicinity, 3 m. E. of brush line. NE end is on MHW. 4' above MHW.	1133

No. of Station	Description	Photo. No.
3216 ✓	S. gable of abandoned grey barn. House has no roof. 40' above MHW.	1133
3217	Lone 25' bushy, triple, spruce, 5 m. N. of edge of brush line. 5' above MHW.	1133
3218	Bushy 28' spruce, on edge of brush line, on N. side of inlet. There is a 30' pine directly across inlet to S. 4' above MHW.	1133
3219	18' fir, blazed on S. side, most easterly on end of point. There is a small juniper 3 m. to SE. 5' above MHW.	1133
3220 ✓	SW gable of 1½ story boat house that is on sand beach. Boat house has white doors. The rest of the boat house is gray shingle. 15' above MHW.	1136
3221 ✓	West gable of one-story grey shingled shack 10 m. east of grass line. There is a large group of spruces to the west. 20' above MHW.	1136
3222	18' spruce tree which is the largest of two spruces on small grassy island. 8' above MHW.	1136
3223	6' spruce on top of ledge 2 meters east of grass line on 7' ledge bank. It is 5 meters west of MHWL. 7' above MHW.	1136
3224	Most easterly of 4 spruces at edge of grass line at back of sand beach. Tree is 8' spruce. 3' above MHW.	1136
3225	20' spruce at edge of grass line on top of 7' rock bluff. 12' to the north is a 25' spruce and 3 m. to the north of that is a 23' double spruce. 6' above MHW.	1136
3226	Lone 5' spruce tree, most easterly on point and on island. 10 m. west of station is a small boulder-filled cove. 10' above MHW.	1136
3227	15' spruce on north side of small rock point. About 50 m. NE is a 50' rock bluff. 5 m. to the south are two spruces, 15' and 22'. 6' above MHW.	1136
3228 ✓	Station is the south gable of 1½ story grey shingled, white-trimmed cottage. There are three chimneys on cottage. There is a porch half the length of the house on the south side. It is built into the house. There is a small open porch on the E. side and a picket fence on the west side around yard. It is the only large building on island. Cottage has cement posts for foundation. It is 50 meters NW of MHWL. 45' above MHW. Recoverable photo. topo station.	1136

No. of Station	Description	Photo. No.
<u>3243</u>	Standard bronze disk in the northern part of white boulder slightly covered with moss. There is a 15' birch tree growing over south part of boulder 1 meter from station. There is a 20' spruce tree 2 m. south of station. Station is 1 meter south of MHWL. 4' above MHW. Recoverable photo topo station. Marked "Bell, 1945".	1135
3244	15' spruce on the NE side of island on edge of grass line. 4 meters to the SW is a dead tree trunk. 3' above MHW.	1135
3245	Lone stunted 10' spruce tree on the west end of small cove. Tree is protruding 2 meters from bank in shape of "L". 2' above MHW.	1135
3246	4' white boulder, only white boulder on the SW end of island. Boulder is 2 meters NE of grass line. 10' above MHW.	1135
3247	14' spruce 6 m. NE of grass line. It is the most SW'ly spruce on island. 6' above MHW.	1135
3248	16' spruce 4 meters W. of brush line. 22 m. SE of station is a large white boulder. Station is the most easterly tree on the island. 5' above MHW.	1135
3249	14' spruce 5 m. east of brush line and most NW'ly tree on island. 25 m. S. of station is small indentation in the land. 5' above MHW.	1135
3250	35' spruce. It is the only spruce on point of island and the most southerly spruce on island. 5' above MHW.	1135
3251	20' bushy spruce, most northwesterly on west end of island, 8 meters east of grass line. 8' above MHW.	1135
3252	NW gable of 1 story board shack which is only shack on island. It is in a grove of birches. 18' above MHW.	1135
3253	18' spruce on the dge of grass line. It is the most easterly spruce on the island. 10 m. to the SW is a 30' spruce with a double top. 1' above MHW.	1135
3254	4' red boulder on edge of grass line on the SW tip of island. It is the only red boulder in the vicinity. 3' above MHW.	1135.
3255	East gable of 2 story grey shingled house which is the only house on the island. 20' above MHW.	1135
3256	14' spruce 4 m. north of grass line on south end of island. It is the largest spruce on island.	1135

No. of Station	Description	Photo. No.
3229	Lone 5' bushy spruce on top of grey ledge. About 10 meters east is a 15' spruce on edge of grass line. Station is SW of small clearing. 15' above MHW.	1136
3230	Lone 16' double spruce most easterly on island. 6' above MHW.	1136
3231	Lone 10' bushy spruce most westerly on island 4 meters east of grass line. 10' above MHW.	1136
3232	3' spruce on end of point. It is smallest and most southerly on point. 6' above MHW.	1135
3233	7' brown boulder 2 m. west of MHWL. It is the largest and only brown boulder in the vicinity. 2' above MHW.	1135
3234	20' double spruce on edge of grass line. It is the most northerly of a group of 4 or 5 spruces on point of black ledge. 3' above MHW.	1135
3235	30' spruce on the west side of small clearing on bank. 2 m. to the SE a $1\frac{1}{2}$ story cottage is under const uction. (This is not on photo) 6' above MHW.	1135
3236	30' spruce on edge of grass line at back end of small boulder beach. It is the most southeasterly of a small clump of spruces. 5' above MHW.	1135
3237	3' white boulder 1 meter south of grass line. It is the only white boulder in the vicinity. 6' above MHW.	1135
3238	38' spruce on edge of grass line. It is the largest tree on the east end of island. There is a fallen dead spruce at its base. 4' above MHW.	1135
3239	South gable of $1\frac{1}{2}$ story grey, shingled shack 12 meters north of grass line. There is an old grey bait shed on shore to the SW. 16' above MHW.	1135
3240	10' spruce at edge of brush line. 8 meters to the NW is a small light in the land. 1 meter to the east is a ledge of red rock. 5' above MHW.	1135
3241	15' spruce tree which is the most northwesterly of two 15' spruces on the SW part of island on edge of grassline. Tree is blazed on the SW side. 4' above MHW.	1135
3242	Slim 26' spruce on ledge in center of small rock beach. There is a 16' spruce 2 meters to the west on edge of grass line. 5' above MHW.	1135

154



No. of Station	Description	Photo. No.
3257	25' spruce on east side of island. It is the largest spruce on the east side of north end of island. 4' above MHW.	1135
3258	18' spruce on the south side of very small cove on edge of grass line and 4 meters east of MHWL. Tree is blazed on the west side. 4' above MHW.	1135
3259	12' spruce on edge of grass line 6 meters west of MHWL which is the most southerly of a small group of spruces. 4 meters to the north is a dead tree trunk. 4' above MHW.	1135
3260	Large 4' black boulder, largest on point, and leaning on a small white boulder. South side of Timber Cove. At MHW.	1133
3261	Lone 12' spruce, at edge of brush line, 3 m. W. of MHW and most easterly of a group. 2' above MHW.	1133
3262	N. gable of 2 story grey, shingled, run-down house. Largest in vicinity. Three windows and a door on N. side. 20' above MHW.	1133
3263	10' spruce, 5 m. E. of MHW. and 2 m. W. of brush line. There is a large pine 40 m. to south. 3' above MHW.	1133
3264	40' double spruce at edge of brush line, and on side of small cove. 3' above MHW.	1133
3265	28' spruce, at edge of brush line. There are 5 birch trees 4 m. to N. 1' above MHW.	1133
3266	18' leaning spruce on MHW, and most southwesterly spruce on W. side of point. At MHW.	1133
3267	35' spruce on edge of brush line 2 m. east of MHW. There is a 20' spruce 2 m. to the north. 2' above MHW.	1133
3268	35' spruce, on edge of brush, 3 m. E. of MHW, and most westerly of 3 prominent spruce trees. 3' above MHW.	1133
3269	Very prominent, 4' white, boulder, largest white boulder in vicinity. 3' above MHW.	1133
3270	Station is small white and green cupola on a large, 2 story white barn, beside a 2½ story white house with green trim. 35' above MHW.	1132
3271	NW gable of 2 story boat house, cream colored with green trim. Boat house is at bottom of 16' bank on the MHWL. 16' above MHW.	1132

No. of Station	Description	Photo. No.
3272 ✓	SE abutment of fixed, steel bridge. 4' above MHW.	1132
3273	24' spruce, 2 m. N. of brush line, most easterly of 2 spruce trees, set off from brush line. 1' above MHW.	1132
3274	30' lone, dying spruce, 10 m. from MHW. on point in Mill Creek.	1132
3275	Lone 25' spruce, 6 m. N. of grass line, and 10 m. N. of brush line. 5' above MHW.	1132
3276	Most northerly of two 26' spruce trees that are 4' apart, very prominent, and the most westerly on point. 4' above MHW.	1132
3277	22' juniper, on edge of grass line, only tree on end of point. 1' above MHW.	1132
<u>3278</u>	"DART, 1945"-Station is 5' white boulder on N. side of point, 1 m. N. of MHW, 3 m. N. of brush line. There is an east-west line of spruce trees, the nearest of which is 6 m. to the SE. Station is the only large white boulder in the vicinity. 3' above MHW. Recoverable photo. topo. station.	1132
3279	Lone 12' spruce on N. side of creek, 12 m. S. of brush line. There is a 6' spruce 14 m. to W. 3' above MHW.	1132
3280	Bushy 25' spruce, most northwesterly of a group of 4 bushy 25' spruces. To the NW there is a group of alders. 5' above MHW.	1132
3281	Double 25' spruce, on N. side of creek, only spruce in a clump of poplars. 3' above MHW.	1132
3282 ✓	Red brick chimney in center of the north-south gable of a 2-story, gray, shingled house. There is a smaller and lower section of the house to the south with a chimney on the south end. There is also a wing to the east which is longer and more conspicuous on the photo but probably not visible from the water. 30' above MHW.	1132
3283	Lone 25' bushy spruce on N. side of head of creek. There is a large group of dying birches and poplars to the W. 4' above MHW.	1132
3284	Lone 25' spruce on point in center of a grove of birches. 6' above MHW.	1132
3285	Lone 30' bushy spruce on point. There is a small spruce 20 m to the NW in a small grove of poplars. 2' above MHW.	1132

No. of Station	Description	Photo. No.
3286	Lone 25' spruce on SE side of creek. There is a juniper growing through the branches on the w. side. 7' above MHW.	1132
3287	Bushy 30' dark green fir on SW side of head of creek. There is a small row of birches 8 m. to north. 3' above MHW.	1132
3288	Lone 8' spruce on point in creek. 4' above MHW.	1132
3289	30' spruce on NE side of river. There is a very bushy double spruce 6 m. to SE and another 30' spruce 1 m. to N. 2' above MHW.	1132
3290	35' spruce on edge of brush line. It is the largest tree in the vicinity. 2' above MHW.	1132
3291	Double 12' bushy spruce most southwesterly of a group of scattered 12' spruces. 4' above MHW.	1131
3292	20' spruce on edge of brush line, on N. side of small creek, and at south side of small group of poplars. 2' above MHW.	1131
3293	Large double-top 28' spruce, most westerly on east side of stream. 2' above MHW.	1131
3294	Leaning 22' spruce. There is a pole fence 30 m. to N. and a pine tree 20 m. to N. 2' above MHW.	1131
3295	Lone 22' spruce on W. side of stream, on point. 2' above MHW.	1131
3296	Bushy 10' spruce on w. side of stream, 5 m. W. of MHW. Station is on back limits of marsh at foot of hill. 3' above MHW.	1131
3297	Dying 23' spruce on S. end of a line of spruces. 4' above MHW.	1131
3298	35' spruce, most conspicuous, largest tree on point. 3' above MHW.	1132
3299	20' spruce on bank on east side of creek, most southerly of three spruces. 15' above MHW.	1131
3300	35' lone spruce on NW side of creek, on south side of road. Tree has drooping branches. 7' above MHW.	1131
3301	Lone, 22' spruce at bottom of hill on west side of stream. 3' above MHW.	1131

No. of Station	Description	Photo. No.
3302	25' spruce, 2 m. from grass line, most southerly on small point. There is a very large pine 10 m. distant. 1' above MHW.	1131
3303	32' bushy spruce on w. side of creek; most northerly of a group of large spruces. To north is a large group of small spruces. 3' above MHW.	1148
3304	12' spruce on SE side of creek. It is smallest and most southwesterly of a group of spruces. 4' above MHW.	1148
3305	20' spruce on N. side of river. It is largest and most southerly of a small line of small spruces. 2' above MHW.	1148
3306 X	Red brick chimney on w. side of peaked roof of 2½ story, large house, brown and yellow, with white trim. 40' above MHW.	1148
3307	6' spruce shrub on n. side of river, on back limits of marsh, only spruce tree in vicinity. 4' above MHW.	1148
3308	Lone 30' spruce on 25' bank. Station is to southeast of a large barn with a grey shingled back. 25' above MHW.	1148
3309 X	SE gable of large, green, shingled, white trimmed, factory on east side of stream. 25' above MHW.	1148
3310	Lone 28' spruce on bank at back limits of marsh. 4' above MHW.	1148
3311	Lone 12' double spruce on N. side of river. There are some small poplars nearby. 5' above MHW.	1148
3312	Lone 10' spruce on bank at back limits of marsh, and east of a clump of alders. 7' above MHW.	1148
3313	32' double spruce with thin branches on top 8' grass bank, 2 m. to SW is a smaller spruce.	1148
3314	25' pine, only large tree in vicinity. 4' above MHW.	1148
3315	(Rejected)	
3316	30' very bushy spruce on edge of bank. 6' above MHW.	1131
3317	25' bushy spruce at edge of brush line, and on the MHW. Station is leaning slightly to E. 1' above MHW.	1132
3318	12' spruce 5 m. NW of brush line on rounding point, most southeasterly spruce on point. 5' above MHW.	1132

No. of Station	Description	Photo. No.
3319	25' spruce on east side of river on top of 6' bank at edge of brush line, largest spruce in near vicinity. 6' above MHW.	1132
3320	22' spruce on S. side of very small alder clearing. 10 m. to SE is a spruce which is largest in near vicinity, 4' above MHW.	1132
3321	Lone 45' spruce near head of small creek, largest tree in vicinity in a group of alders. There is a 10' spruce about 15 m NW of station. 4' above MHW.	1132
3322	15' bushy spruce on point in inlet. 3' above MHW.	1132
3323	20' spruce with very few branches, on top of 12' bank. 10 m. to east is a small group of leaning spruces. 12' above MHW.	1132
3324	6' white boulder on MHW on gravel beach, largest white boulder in vicinity. 5 m.S. is large brown boulder. 6' above MHW.	1132
3325	20' spruce, largest in vicinity, NW of small, rounding, point, on edge of brush line. 1' above MHW.	1132
3326	Lone 30' spruce in group of birch and alder trees, and about 10 m NE of woods line. 2' above MHW.	1132
3327	Lone 25' spruce on edge of brush line. There is another 25' double spruce about 100 m. N. 1' above MHW.	1132
3328	South gable of 1½ story green-roofed barn. Barn is attached to house and both are grey shingle. Green roof is very prominent. House has 2 chimneys. 25' above MHW.	1148
3329	20' spruce, leaning slightly to the east. There is a 15' spruce 3 m. to W. 1' above MHW.	1132
3330	Lone, 15' spruce on E. end of pasture land. There is a birch 10 m. to N.	1132
3331	SW abutment of concrete bridge at Harrington on U.S. Highway 1A. At MHW.	1148
3332	A 20' spruce, most westerly of 3. There is a 25' double spruce 10 m. to E. 1' above MHW.	1148
3333	20' double spruce on point. There is a 15' spruce 1 m. to SE and a lone 10' spruce about 20 m. to south. 2' above MHW.	1148

No of Station	Description	Photo. No.
3334	NW abutment of concrete bridge over Harrington River, U. S. Hwy. No. 1. At MHW.	1149
3335	SE abutment of Maine Central R.R. bridge. At MHW.	1149
3336	45' spruce. 1 m. to SW is a 42' spruce. These are the only large spruces in the vicinity. There is a group of 9' spruces NE of station. 3' above MHW.	1149
<u>3337</u> ✓	Red brick chimney in center of 1½ story section of white house. The main part of house is 2 story, is W. of 1½ story section, and has a red brick chimney also. Lower section has green roof, and 2 story section has grey shingle roof. There is a garage with green roof 1 m. to SE. 30' above MHW. Recoverable photo topo station.	1131
4401 ✓	East gable of white house. There are two windows with green shutters under gable. There is a barn attached to the house, and there are two chimneys on main house. 10' above MHW.	1163
4404 ✓	N. gable of most northerly house on woods line. House is painted brown, has two chimneys, and there is a road running parallel in rear of house. There is a line of trees running from shoreline to the house. Station is inshore from Dyer Cove. 20' above MHW.	1164
4405	25' leaning spruce on edge of rock ledge. There are many 20' birches inshore from signal and a 4' rock wall on river side of signal. 2' above MHW.	1164
4406	Lone 25' spruce on bank, most prominent spruce in vicinity. There is a dead 20' birch about 6 m. to river side of spruce. 8' above MHW.	1164
4407	5' gray boulder on beach, largest boulder in vicinity, about 2 m. S. of MHW and a 15' bank.	1164
4408	30' spruce on side of bank on north side of a small cove and about 12 m. from MHW. There are many small trees around signal tree. 4' above MHW.	1164
4410	20' overhanging spruce tree on the east side of small cove. There is a 5' ledge wall running in front of the signal. There are 25' spruces surrounding spruce. 6' above MHW.	1166
4411	15' spruce on the north side of small cove. There is a group of small spruces in rear of signal. 2' above MHW.	1166

No. of Station	Description	Photo. No.
4523	6' boulder, largest in vicinity, about 50 m. N. of MHW and north of point of land. 1' above MHW.	1165
4524	15' lone juniper, on 10' grassy bank, most prominent tree in vicinity. 11' above MHW.	1165
4539	8' flat top spruce with overhanging branches on west side of small cove. There is a group of 26' birches in back of spruce. 3' above MHW.	1166
4544	20' triple spruce 1 m. NW of 2 20' spruces. 6' above MHW.	1169
4545	3' white boulder on the NE part of island about 15 m. east of tree line and 5 meters east of MHWL. 2' above MHW.	1169
4546	Lone 25' spruce on the NE tip of island about 8 m. east of grass line and 10 m. west of MHWL. 4' above MHW.	1169
4547	25' leaning spruce on the SW tip of island. Station is 3 m. W of 10' leaning dead tree. Both trees are on top of ledge outcrop. 10' above MHW.	1169
4551	Lone 8' spruce on the northeast tip of island. Only tree in vicinity and very prominent. 12' above MHW.	1169
4576	20' pointed spruce tree about 3 m. N. of MHWL on the edge of a rock bank. There are two dead birches about 4 meters SW of signal. 3' above MHW.	1167
4577	30' spruce tree at the head of small cove. It is the most southerly spruce in a clump of spruces. 2' above MHW.	1167
4578	15' crooked spruce tree. There is a 20' dead spruce tree about 1 meter east of signal. Station is about 3 m. east of MHWL. 2' above MHW.	1167
4579	15' busy spruce tree on the north side of cove. Tree is on the rock ledge and is about 2 m. N. of MHWL. 4' above MHWL.	1166
4580	10' flat top spruce tree on the N side of small cove. There is a clump of spruces about 25 meters W of signal. Tree is on the side of a 10' bank. 1' above MHW.	1166
4581	West gable of tar papered camp on point of land. There is one window in gable. It has shingles in roof. 15' above MHW.	1167

1162

No. of Station	Description	Photo. No.
4582	20' lone spruce tree on point of land. Station is the most prominent tree in the vicinity. 5' above MHW.	1166
<u>45337</u>	Standard bronze disk (TOPO) set in grey ledge marked "GEAR 1946". It is on the shore of Pleasant River and due north of Gibbs Island. Station is located about 3 $\frac{1}{2}$ miles south of Addison on Seavey Point. It is 9 m. east of MHWL and 45 m. SE of the E gable of a tar paper shack. 10' above MHW. Recoverable photo. topo. station.	1167
<u>4591</u>	Located on the north part of Norton Island about 1/2 mile west of Cape Split, in the southern part of a small gravel cove. Station is the standard bronze topo disk marked "HEAL 1946" set in a 4' grey boulder 3 meters south of small bluff 14.6 m. south of MHWL. Boulder is the largest in the vicinity. Recoverable photo. topo. station.	1169







**TO BE CHARTED  
TOGETHER**

STRIKE OUT ONE

## NONFLOATING AIDS OR LANDMARKS FOR CHARTS

Millbridge, Maine

Nov. 14

1976

I recommend that the following objects which have ~~been~~ been inspected from seaward to determine their value as landmarks, be charted on ~~the~~ the charts indicated.

The positions given have been checked after listing by H. P. Eichert

Thos. B. Reed

*Chief of Party.*

This form shall be prepared in accordance with Hydrographic Manual, pages 800 to 804. Positions of charted landmarks and *nonfloating aids* to navigation, if redetermined, shall be reported on this form. The data should be considered for the charts of the area and not by individual field survey sheets. Information under each column heading should be given.



# NONFLOATING AIDS ORGANOCHLORINE PESTICIDES

TO BE CHARTED  
DOORS OPENED

## Maohias, Maine

1946 19

I recommend that the following objects which have ~~(been)~~ been inspected from seaward to determine their value as landmarks, be charted on ~~(charts)~~ the charts indicated.

The positions given have been checked after listing by

Ross A. Gilmore

Ross A. Gilmore

*Chief of Party.*

This form shall be prepared in accordance with Hydrographic Manual, pages 800 to 804. Positions of charted landmarks and *nonfloating aids* to navigation, if redetermined, shall be reported on this form. The data should be considered for the charts of the area and not by individual field survey sheets. Information under each column heading should be given.

# GEOGRAPHIC NAMES

Survey No. T-8644

HARRINGTON, Me.

1 Name on Survey

On Chart  
No.

On previous survey  
No.

On U. S. quadrangle  
Maps

From local  
information

On local Maps

P. O. Guide or Map

Rand McNally Atlas

U. S. Light List

A

B

C

D

E

F

G

H

K

Maine

USGB

1

Washington County

2

Towns or townships of Addison

3

Cherryfield

4

Columbia

5

Harrington

6

Millbridge

7

Maine Central

8

U.S. No. 1

9

U.S. No. 1A

10

11

South half, starting at southeast corner:

12

Norton Island

USGB

13

Gooseberry Nubble

14

Eagle Island

15

Eagle Island Reef

16

Halftide Ledge

17

Sheep Island

18

Nightcap Island

19

Nightcap Ledge

20

Barton Ledge

21

Pleasant Bay

22

Bay Ledge

(not Narrows Island Ledge)

USGB

23

Narrows Island

24

Willard Point

25

Hen Island

26

Hog Island

27

M 234

167

# GEOGRAPHIC NAMES

Survey No. T-8644

2

Name on Survey

On Chart  
No.

On previous survey  
No.

On U. S. quadrangle  
Maps

From local  
information

On local Maps

P. O. Guide or Map

Rand McNally Atlas

U. S. Light List

A

B

C

D

E

F

G

H

K

Bar Island

1

Ripley

(not Dewey)

USGB

2

Ripley Neck

3

Harrington Bay

4

Dry Ledge

5

Halftide Ledge

(east of Foster Island)

6

Shag Island

7

Strout Island

8

Strout Island Ledges

9

Dyer Island Narrows

(OK bet. Dyer I. & Foster I.)

10

Foster Island

11

Dyer Island

12

Squirrel Point

13

Otter Island

14

Northeast Cove

15

Northwest Cove

16

Narraguagus Bay

17

Smith Cove

18

Turner Hill

19

Turner Point

20

Wyman

21

Wyman Methodist Church

22

Lookout Mt.

23

Mitchell Point

24

Long Point

25

Timmy Point

(use this name pending decision  
by US Navy)

26

Lenroy Island

27

M 234

# GEOGRAPHIC NAMES

Survey No. T-8644

3

Name on Survey

	A	B	C	D	E	F	G	H	K	
<u>Narraguagus River</u>										1
<u>Halftide Rock</u>			(not ledge)							2
<u>Fickett Point</u>										3
<u>Glen Ledge</u>										4
<u>Crow Island</u>										5
<u>Sand Cove</u>										6
<u>Fish Point</u>										7
<u>Millbridge Grange</u>										8
<u>East Side Elementary School</u>										9
<u>Beaver Meadow Brook</u>										10
<u>Back Bay</u>										11
<u>Strout Point</u>										12
<u>Partridge Island</u>		Shift name as indicated on F-Edit sheet								13
<u>Kemps Folly</u>		Pinkham I.								14
<u>Bay Point</u>										15
<u>Flat Bay</u>										16
<u>Blasket Point</u>										17
<u>Chamberly Island</u>		(use this name pending action by U.S. B. & N.)								18
<u>Ripley Cove</u>		Shift name as shown on F-Edit Sheet								19
<u>Ripley Islands</u>										20
<u>Carrying Place Cove</u>									USGB	21
<u>Raspberry Island</u>										22
<u>Mink Island</u>										23
<u>Bunker Ledge</u>										24
<u>Birch Islands</u>			(not The Birch Is.)							25
<u>Gibbs Island</u>										26
<u>The Dick</u>			(waterway)							27

169

# GEOGRAPHIC NAMES

Survey No. T-8644

4

Name on Survey

On Chart  
No.  
A

On previous survey  
No.  
B

On U. S. quadrangle  
Maps  
C

From local  
information  
D

On local Maps  
E

P. O. Guide or Map  
F

Rand McNally Atlas  
G

U. S. Light List  
H

K

Name on Survey	A	B	C	D	E	F	G	H	K	
<u>Tumbledown Dick Head</u>										1
<u>Seal Cove</u>										2
<u>Seavey Point</u>										3
<u>Long Cove</u>			(not Looks Cove)						USCB	4
<u>Long Point</u>										5
<u>Hemlock Island</u>										6
<u>Goose Island</u>										7
<u>Deer Islands</u>										8
<u>Ramadell Cove</u>										9
<u>Little Fort Island</u>			(not Guard Island)							10
<u>Fort Island</u>										11
<u>Guard Point</u>										12
										13
<u>North half:</u>										14
<u>Pleasant River</u>										15
<u>Harthorne Ledge</u>										16
<u>Look Point</u>			(not Richards Point)						USCB	17
<u>Lower Wass Cove</u>										18
<u>Wards Cove School</u>										19
<u>Wass Point</u>										20
<u>Reef Point</u>										21
<u>Miscle Shoal</u>										22
<u>Channel Rock</u>										23
<u>Bray Ledge</u>			(not Reynolds Ledge)						USCB	24
<u>Wilmot Cove</u>										25
<u>Upper Wass Cove</u>										26
<u>Bray Point</u>			(not Reynolds Point)						USCB	27

170



## GEOGRAPHIC NAMES

Survey No.

T-8644

5

Name on Survey

A

B

C

D

E

F

G

H

K

✓ Coffins Rock

1

✓ Whites Point

(not White Point)

2

✓ Dyer Cove

3

✓ Baptist Church

4

✓ Church Hill Cemetery

5

✓ West Branch

(of Pleasant River)

6

✓ Marshville

7

✓ Advent Church

8

✓ Marshville School

9

✓ Union Church

10

✓ Harrington River

11

✓ Nash Point

12

✓ Oliver Lord Point

Plummer Pt.

13

✓ Eily Cove

14

✓ Gale Point

15

✓ Mill Creek

16

✓ Cranberry Island

Lords I. o

17

✓ Coffins Point

18

✓ Timber Cove

19

✓ Hardwood Point

20

✓ Five Islands

21

✓ Five Islands Cove

22

✓ Pineo Point

23

✓ Sandy Cove

24

✓ Flat Bay

(also on list for south half)

25

✓ Oak Point

26

✓ Mill River

27

171



# GEOGRAPHIC NAMES

Survey No.

T-8644

6

Name on Survey

On Chart  
No.

On previous survey  
No.

On U. S. quadrangle  
Maps

From local  
information

On local Maps

P. O. Guide or Map

Rand McNally Atlas

U. S. Light List

Cole Creek

1

Curtis Creek

2

Flat Bay Cemetery

3

West Harrington

4

Mill River Church

5

Church in the Wildwood

6

Rock Maple Cemetery

7

Dorman

8

Coffin ~~B~~ ~~at~~ School

9

Harrington

10

Baptist Church

11

Methodist Church

12

13

14

4/13/48: Names underlined in red 15  
are approved. Those not underlined 16  
are pending with the U.S.B.G.N. 16  
which has not yet rendered a deci- 17  
sion for them. The conflicts have 18  
been marked on the sheet that is to 19  
go to the Field Edit party, and 18  
any additional information that may 19  
be obtained will be useful in 19  
reaching a final decision.

L. Heck.

20

This list should be revised and 21  
completed by me after Field Edit 21  
and possible USBGN decisions in the 22  
meantime.

L. Heck.

23

24

25

26

27

M 234

172

# GEOGRAPHIC NAMES

Survey No. T-8644

GEOGRAPHIC NAMES		Survey No. T-8644										
7	Name on Survey	<div>On Chart No.</div> <div>On previous survey No.</div> <div>On U. S. quadrangle Maps</div> <div>From local information</div> <div>On local Maps</div> <div>P. O. Guide or Map</div> <div>Rand McNally Atlas</div> <div>U. S. Light List</div>										
		A	B	C	D	E	F	G	H	K		
	Strout Island Narrows										1	
	Isaac Ledge										2	
	Jordan Beach										3	
	Cow Island			(in place of formerly charted Partridge I)							4	
	The Folly										5	
	West Carrying Place Cove			(in place of formerly charted Ripley Cove)							6	
	Lower Birch Island										7	
	Upper Birch Island										8	
	Pleasant River Cemetery										9	
						Names added or changed after Field Edit Report. 2/14/49 L. Heck					10	
											11	
											12	
											13	
											14	
											15	
											16	
											17	
											18	
											19	
											20	
											21	
											22	
											23	
											24	
											25	
											26	
											27	

M 234

Names added or changed after  
Field Edit Report. 2/14/49  
L. Heck

172

**FIELD EDIT REPORT**

**TO ACCOMPANY**

**QUADRANGLE T-8644**

**JULY 1948**

**46 - METHODS.**

Field edit of this quadrangle was accomplished during the period 4 June to 29 July 1948, in accordance with Field Edit Instructions dated 24 August 1945 and Supplement 1 dated 4 February 1946.

A launch and an outboard motor powered skiff were used for all island, reef and shoreline identification.

Standard plane-table methods were employed for all contouring, verification and the Vertical Accuracy Test. Verification of contours and the Vertical Accuracy Test was done directly on the Field Edit Sheet. A small area was contoured on the photographs and a reference was made on the Field Edit Sheet.

Refer to paragraphs 2 to 5 inclusive of the Field Edit Report for quadrangle T-8641.

**47 - ADEQUACY OF THE COMPILATION.**

The compilation of this quadrangle is adequate with the following exceptions:

Areas adjacent to the shoreline that appear light gray on the photographs should not be labeled "Shoal". These areas slope gradually from the shoreline and are comprised of sand, mud and scattered boulders that are bare at M. L. W. The dashed line that encloses these areas is the approximate M. L. W. L. in the instances noted on the Field Edit Sheet.

Fish traps in the area covered by this project are known locally as "Fish Weirs".

Refer to paragraph 1 of Field Edit Report for quadrangle T-8641

**48 - ACCURACY TESTS.**

A Vertical Accuracy Test was run along the northern boundary of this quadrangle.

No Horizontal Accuracy Test was run.

Refer to Field Edit Report for quadrangle T-8641

174

17 - BOUNDARY MONUMENTS AND LINES.

The position of all township lines in the area covered by this quadrangle were checked. In areas where no recovery was made by the Field Inspection Party, township corners and points on tangent were either identified on the photographs or located by plane-table traverse.

No positive location could be determined for the township lines where they run through water areas. The approximate positions of these lines, verified by local information and an Atlas of Washington County Maine compiled from a survey in 1881, are shown on the Field Edit Sheet. See Review Report.

Mr. Charles Cirone, a resident of the area for thirty seven years, has examined the completed Field Edit Sheet and no errors were found.

*George E. Varnadoe*  
George E. Varnadoe  
Topo. Engr.

*Reviewer - Please examine refs  
shown in Harrington Bay  
and Pleasant Bay against photos.  
I think none or all of these bars of low  
water shown as indicated on field photos 1143  
and 1146 *mg* Shown as indicated on Field Photos and verified  
by the Nautical Chart Branch when the MLWk was  
added.*

Division of Photogrammetry  
Review Report of  
Topographic Map Manuscript T-8644

Subject numbers not used in this report have been adequately covered in other parts of the Descriptive Report.

26. Control.-The pricking card for the triangulation station "Look's, Joe, House, Chimney, 1862", is marked "station not identified". It is apparent on the photographs that the house and chimney have been destroyed. Only the foundation remains on an isolated point of land. The station has been considered lost.

Five bench marks have been recovered in the area covered by this quadrangle and are shown on the map manuscript. Descriptions are filed in the Division of Geodesy. Copies of these descriptions are filed in the Division of Photogrammetry, General Files.

28. Detailing.-Heath areas are to be shown on the quadrangle with the standard peat bog symbol and labelled "Heath".

Boundaries through water areas were added to the map manuscript approximately halfway between the land areas that they divide. The USGS Cherryfield quadrangle was used as a reference.

Four fish weirs in Narraguagus Bay were added to the map manuscript from the photographs.

31. Low-water and Shallow Lines.-See Review Report for T-8647.

32. Details Offshore from the MHWL.-Several offshore rocks and reefs were indicated on the map manuscript by the Nautical Chart Branch during the compilation of the depth curves. These features have been added with a note to the hydrographer to investigate their position and height. They do not appear on the photographs and were not located by the field inspector.

See #40 for Hydrographic Survey Sources

34. Landmarks and Aids to Navigation.-There are three aids to navigation and one landmark on the map manuscript. Two aids to navigation and the landmark were filed in the Nautical Chart Branch in Chart Letter 68 (43). A form 567 has been prepared and forwarded to the Nautical Chart Branch for "Halftide Rock Day beacon". Copies of the forms 567 have been made a part of the Descriptive Report.



40. Depth Curves and Soundings.-Depth curves, soundings and the approximate low water line have been added to the map manuscript by the Nautical Chart Branch from the following sources:

H-1610	1:10000	1884
H-1608	1:10000	1884-85
H-1644	1:10000	1885-86
H-1567a	1:10000	1883-87

44. Comparison with Existing Surveys.-USGS Cherryfield Quadrangle 1:62500, 1904, Repro. 1943.

T-1496	1:10000	1882
T-1506	1:10000	1881
T-1519	1:10000	1881
T-1521	1:10000	1881-83
T-1524	1:10000	1881

Common features on all previous surveys are superseded by the map manuscript in common areas.

45. Comparison with Nautical Charts.-

Chart No. 1201	1:80000	1941 Corr. 1948
305	1:40000	1931 Corr. 1946

Coffins Rock and Channel Rock Day beacons are shown on the charts as buoys. The map manuscript shows them as day beacons in their new positions. The landmark "Stack" at Wyman should be charted. See Chart Letter 68 (1948). *note*

48. Accuracy Tests.-The vertical accuracy test made along the northern boundary of this quadrangle meets the specifications for the project. This map complies with the national standards of map accuracy requirements.

The planetable traverse that was run along the northern boundary of this quadrangle also serves as a horizontal accuracy test. The features all proved to be in their correct relative position. The test has proven that this area is within the required accuracy because there is sufficient control in the northern section of this quadrangle.

49. Overlays.-An overlay was prepared showing the border information, road classifications and route numbers, triangulation stations, bench marks, topographic stations, landmarks and aids to navigation and spot elevations that are to be shown by the smooth draftsman.

51. Application to Nautical Charts.-The map manuscript has not been applied to the nautical charts.

177

Reviewed by:

Charles Theurer  
C. Theurer  
3-15-49

APPROVED:

L. V. Griffith  
Chief, Review Section *L. V. Griffith*

H. E. Edmonson  
Chief, Nautical Chart Br.  
Division of Charts

K. T. Adams  
Chief, Division of Photogrammetry

W. M. Scaife  
Chief, Div. of Coastal Surveys

T-8644

Record of Work Subsequent to the Manuscript Review,  
that is, Smooth Drafting, Checking, and Printing

Manuscript forwarded to the U. S. Geological  
Survey for smooth drafting and publication.

Color proof furnished by the Geological Survey and  
examined by

\_\_\_\_\_  
Name

\_\_\_\_\_  
Date

Published by the Geological Survey.



Partially applied to 305 9-1-53 ~~MSA~~

Completely applied to Reconst 305 1/3/58 - JFW