

9100

Diag. Cht. No. 1244.

Form 504

U. S. COAST AND GEODETIC SURVEY

DEPARTMENT OF COMMERCE

DESCRIPTIVE REPORT

Type of Survey Topographic

Field No. Ph-35B(48) Office No. T-9100

LOCALITY

State Florida

General locality Halifax River

Locality Daytona Beach

1949-52

CHIEF OF PARTY

H. F. Garber, Chief of Field Party
A. L. Wardwell, Tampa Photo. Office

LIBRARY & ARCHIVES

DATE 10/23/59

B-1670-1 (1)

9100

DATA RECORD

T - 9100

Project No. (II): **Ph-35B(48)** Quadrangle Name (IV):

Field Office (II): **Edenton, North Carolina**

Chief of Party: **Harry F. Garber**

Photogrammetric Office (III): **Tampa, Florida**

Officer-in-Charge: **Arthur L. Wardwell**

Instructions dated (II) (III): **30 December 1949**

Copy filed in Division of
Photogrammetry (IV)

Office Files

Method of Compilation (III): **Graphic**

Manuscript Scale (III): **1:20,000**

Stereoscopic Plotting Instrument Scale (III): **Inapplicable**

Scale Factor (III): **none**

Date received in Washington Office (IV): **DEC 18 1951**

Date reported to Nautical Chart Branch (IV): **DEC 23 1951**

Applied to Chart No.

Date:

Date registered (IV): **3/20/58**

Publication Scale (IV):

Publication date (IV):

Geographic Datum (III): **N. A. 1927**

Vertical Datum (III): **MSL**

Mean sea level except as follows:
Elevations shown as (25) refer to mean high water
Elevations shown as (5) refer to sounding datum
i.e., mean low water or mean lower low water

Reference Station (III): **DAYPORT 1934**

Lat.: **29° 10' 22".835 (703.0 m.)** Long.: **81° 04' 09".162 (247.6 m.)**

Adjusted

~~xxxxxxxxxxxx~~

Plane Coordinates (IV): **Transverse Mercator**

State: **Florida**

Zone: **East**

Y=

X=

Roman numerals indicate whether the item is to be entered by (II) Field Party, (III) Photogrammetric Office, or (IV) Washington Office.

When entering names of personnel on this record give the surname and initials, not initials only.

All contouring
done by
John R. Smith
Cartographic Survey Aid

Areas contoured by various personnel
(Show name within area)
(II) (III)

81-00-00

DATA RECORD

Field Inspection by (II): **John R. Smith,
Cartographic Survey Aid**

Date: **1 May 1950 to
7 Feb. 1951**

Planetable contouring by (II): **John R. Smith,
Cartographic Survey Aid**

Date: **1 May 1950 to
31 Jan. 1951**

Completion Surveys by (II): **James E. Hundley**

Date: **9 Dec. 1952**

Mean High Water Location (III) (State date and method of location):
Air Photo Compilation

14 April 1949

Projection and Grids ruled by (IV): **T. L. J. (W.O.)**

Date: **20 Oct. 1950**

Projection and Grids checked by (IV): **T. L. J. (W.O.)**

Date: **20 Oct. 1950**

Control plotted by (III): **R. R. Wagner**

Date: **9 Nov. 1950**

Control checked by (III): **R. A. Reece**

Date: **9 Nov. 1950**

~~Radial Plot or Stereoscopic~~

~~Contour extension~~ by (III): **M. M. Slavney**

Date: **6 Nov. 1950**

Stereoscopic Instrument compilation (III): **Planimetry
Inapplicable
Contours**

Date:

Date:

Manuscript delineated by (III): **R. R. Wagner**

Date: **29 June 1951**

Photogrammetric Office Review by (III): **J. A. Giles**

Date: **14 Sept. 1951**

Elevations on Manuscript
checked by (III): **R. R. Wagner**

Date: **28 June 1951**

Camera (kind or source) (III): **Fairchild Cartographic - 6" Metrogon lens - Camera 0**

Number	Date	Time	Scale	Stage of Tide
49-0-81 to 85	6 April 1949	1445	1:20,000	3.0
49-0-106 to 111	"	1445	"	3.0
49-0-132 to 137	14 April 1949	0945	"	4.4
49-0-147 to 152	"	0945	"	4.4
49-0-161 to 166	"	1000	"	4.4
51-0-4246 to 4250	9 April 1951	1307 <i>ENR</i>	"	"

Tide (III)

Reference Station: **Mayport, Florida**
Subordinate Station: **Daytona Beach, Florida**
Subordinate Station:

Ratio of Ranges	Mean Range	Spring Range
0.9	4.1	4.9

Washington Office Review by (IV): *Everett H. Ramsey*

Date: *8 Dec 1953*

Final Drafting by (IV): *A.P. Berry*

Date: *9/9/58*

Drafting verified for reproduction by (IV): *Wm O. Halluin*

Date: *10/3/58*

Proof Edit by (IV):

Date:

Land Area (Sq. Statute Miles) (III): **62 sq. mi.**

Shoreline (More than 200 meters to opposite shore) (III): **18**

Shoreline (Less than 200 meters to opposite shore) (III): **1**

Control Leveling - Miles (II): **26 mi.**

Number of Triangulation Stations searched for (II): **63** Recovered: **41**

Identified: **20**

Number of BMs searched for (II): **50** Recovered: **40**

Identified: **36**


Number of Recoverable Photo Stations established (III): **31**

Number of Temporary Photo Hydro Stations established (III): **none**


Remarks:

FLORIDA, East Coast

PH-35-A (48)



PH-35-B (48)



Summary to Accompany Topographic Map T-9100

Map T-9100 is one of ten topographic maps in Project Ph-35(48) and is located in Part B of the project. It covers portions of the Atlantic Ocean, Halifax River, Daytona Beach, and land area to the westward.

Project Ph-35(48) is a graphic compilation project. Field work in advance of compilation included the identification of horizontal and vertical control, complete field inspection, the delineation of contours by planetable methods directly of the photographs and the investigation of land lines, boundaries and geographic names.

Map T-9100 was compiled at a scale of 1:20,000 using single-lens photographs taken in 1949 and 1951. It covers $7\frac{1}{2}'$ in latitude by $7\frac{1}{2}'$ in longitude. The map was field edited. After the addition of hydrography, the map will be forwarded to the Geological Survey for publication as a standard topographic quadrangle.

Items registered under T-9100 will include the descriptive report, a copy of the map manuscript at a scale of 1:20,000 and a copy of the published topographic quadrangle.

FIELD INSPECTION REPORT

QUADRANGLE T-9100

29-07-30/81-00-00

PROJECT PH-35B(48)

Harry F. Garber, Chief of Party

The field work for this quadrangle was done in accordance with Instructions, dated 30 December 1949, Project Ph-35(48), under the direction of Joseph K. Wilson, Supervisor. Field work in addition to those phases listed on Pages 2 and 3, was done by the following personnel:

<u>Name and Title</u>	<u>Phase</u>	<u>Date</u>
Henry R. Spies	Horizontal Control	1 April 1950 to
Cartographic Survey Aid	Recovery and Shoreline	1 May 1950

This report is written in accordance with Paragraph 724 of the Topographic Manual, Part II, dated 1949.

2. AREAL FIELD INSPECTION

This quadrangle lies in the northeast portion of Volusia County in a heavily populated area which includes the incorporated towns of Daytona Beach, South Daytona and Holly Hill. The quadrangle includes a portion of the Atlantic Ocean and the Halifax River (Intra Coastal Waterway).

Numerous highways serve the area, including two state highways and one federal highway*. The Florida East Coast Railroad runs in a north-south direction through the entire quadrangle.

* Two highways with both federal and state numbers and one state highway. *ENR*

Daytona Beach Municipal Airport lies in the central part of the sheet. This airport was owned and operated by the U. S. Navy during World War II. It was leased to the City of Daytona Beach in 1946. *See § 57*

The field editor's attention is called to a new bridge which is under construction across the Halifax River, and to U. S. Highway 1, which was under construction during the field inspection. The road is being widened and should be checked during the field edit. In the west-central portion of the quadrangle, numerous buildings were being moved during the field inspection, and new buildings were under construction. *See § 58*

The photographs were not too clear, being slightly fuzzy. However, it is believed that adequate field notes will clear up any difficulty in photograph interpretation.

The field inspection is believed to be complete, except for the new construction mentioned in the above paragraph.

3. HORIZONTAL CONTROL

- (a) No supplemental control was established.
- (b) All stations are on the N.A. 1927 datum.
- (c) Stations not established by the USC & GS are:

<u>Station</u>	<u>Agency</u>	<u>Order</u>	<u>Datum</u>
K-1	Florida Geodetic Survey	Third	N.A. 1927
K-6	"	"	"
K-7	"	"	"
K-8	"	"	"
K-9	"	"	"
K-10	"	"	"
K-11	"	"	"
K-12	"	"	"
K-13	"	"	"
K-14	"	"	"
K-15	"	"	"
K-16	"	"	"
K-17	"	"	"
K-18	"	"	"
K-19	"	"	"
K-20-2	"	"	"
K-21	"	"	"
T-1	"	"	"
T-2	"	"	"
T-3	"	"	"
T-4	"	"	"
T-5	"	"	"
T-9	"	"	"
T-10	"	"	"
T-11	"	"	"

- (d) A search was made for all known control. Stations reported as "lost" or "not recovered" are:

Airway Beacon No. 24, 1934
 Bethune Point, 1874
 Burgoyne's Water Tank and Windmill, 1906
 City Hotel Cupola, 1906
 Daytona Colonnade Hotel Flag, 1906
 Daytona Ice Plant Smoke Stack, 1906
 Daytona Longitude, 1907
 Daytona Municipal Water Tank Center, 1934
 Gambles Water Tank and Windmill, 1906
 Hendricks, 1906
 McLaren's Windmill, 1906
 Methodist Church Spire, 1906
 Ridgewood Hotel Flag Staff, 1906

K-6 (Fla. Geod. Sur.), 1934		
K-7	"	"
K-8	"	"
K-11	"	"
K-12	"	"
K-16	"	"
K-17	"	"
T-2	"	"
T-3	"	"

Eight stations, which are located outside of the quadrangle limits, were identified to control the radial plot.

4. VERTICAL CONTROL

(a) A search was made for all known vertical control. Bench marks in the quadrangle are:

<u>Name</u>	<u>Agency</u>	<u>Order</u>
K-6	Florida Geodetic Survey	Third
K-7	"	"
K-8	"	"
K-9	"	"
K-10	"	"
K-11	"	"
K-12	"	"
K-13	"	"
K-14	"	"
K-15	"	"
K-16	"	"
K-17	"	"
K-18	"	"
K-19	"	"
T-1	"	"
T-2	"	"
T-3	"	"
T-4	"	"
T-5	"	"
Daytona Longitude	"	"
B-123	U.S. Coast & Geod. Survey	First
C-123	"	"
D-123	"	"
E-123	"	"
F-123	"	"
V-31	"	"
W-31	"	"
X-31	"	"
Y-31	"	"

<u>Name</u>	<u>Agency</u>	<u>Order</u>
Daytona Beach T.B.M. 1	U.S. Coast & Geod. Survey	First
" " T.B.M. 2	"	"
" " T.B.M. 3	"	"
" " T.B.M. 4	"	"
" " T.B.M. 5	"	"
" " T.B.M. 6	"	"
" " T.B.M. 7	"	"
" " T.B.M. 8	"	"
" " T.B.M. 9	"	"
" " T.B.M. 10	"	"
" " T.B.M. Bridge A1A	"	Unknown
" " T.B.M. 11.476	"	"
" " T.B.M. 11.982	"	"
R.M. 1 Dayport	"	First
R.M. 3 Dayport	"	"
Dayport	"	"
T.B.M. 177-H	"	"

(b) Twenty-six miles of supplemental levels were run with a Wye level, beginning and closing on bench marks of third order accuracy or better. The greatest closure on any line was 0.42 feet. This line was adjusted.

(c) The first and last fly level points are 00-1 and 00-31.

(d) Inapplicable.

5. CONTOURS AND DRAINAGE

The contouring was done by planetable methods directly on single-lens photographs (1:20,000 scale), at a contour interval of five (5) feet.

The natural drainage in the quadrangle is by the Tomoka River in the west, and by numerous canals draining into the Halifax River in the eastern portion.

The terrain is quite flat except for a sand ridge through the central section, and numerous sand dunes along the beach. The highest natural elevation on the sheet is 74 feet, which is located in the central portion.

6. WOODLAND COVER

The cover was classified in accordance with Paragraph 5433 of the Topographic Manual, Part II, dated 1949.

7. SHORELINE AND ALONGSHORE FEATURES

(a) The shoreline of this quadrangle was inspected on single-lens photographs (1:20,000 scale).

Measurements from identifiable points on the photographs were made to the high-water line along the beach, at approximately one-half mile intervals. The area along the Intracoastal Waterway was inspected by skiff and truck. The shoreline of the river has undergone no change since photography.

(b) The low-water line along the beach was located by the same methods used on the high-water line.

No attempt was made to accurately locate the low-water line along the Intracoastal Waterway. However, the area was inspected at low-water, and a low-water line has been shown in many places where it was discernible on the photographs.

(d) Bluffs - Along this portion of the Atlantic Ocean, sand dune heights range from 15 feet to 24 feet, and are depicted by the contours.

(e) All docks, wharves, piers, landings, etc. have been labeled on the photographs.

(f) There are no submarine cables within the quadrangle.

8. OFFSHORE FEATURES

There were no offshore features noted during the field inspection.

9. LANDMARKS AND AIDS

(a) Eleven landmarks have been recommended for nautical charts. *See § 37*
Form 567 was submitted 1 May 1950.

(b) One interior landmark is recommended. *Fire Lookout Tower. See § 11
W. of survey limits.*

(c) One aeronautical aid is reported on Form 524. *Also Form 567.*

(d) Along the Intracoastal Waterway (Halifax River) are numerous lights and daybeacons. These fixed aids were located by theodolite cuts from identifiable points on the photographs, and have been reported on Form 567. *Also see § 56*

10. BOUNDARIES, MONUMENTS AND LINES

A Special Report On Boundaries will be submitted at a later date by Joseph K. Wilson, Cartographer. *Filed in Div. of Photogrammetry*

Eight section corners and one grant corner were recovered and identified. Thirteen U.S. Navy airport boundary markers* were recovered and identified.

* Only 3 of 13 shown on map. *See § 57.*

*not all
shown*

The following maps were submitted with the quadrangle data:

- 1 - Blue print of Daytona Beach Municipal Airport
- 3 - Maps showing limits of old U. S. Navy property and city limits of Daytona Beach
- 1 - Map of towns of Daytona Beach, South Daytona and Holly Hill.

The limits of Daytona Beach Airport and the corporate limits of the towns of Daytona Beach, South Daytona and Holly Hill have been outlined on the photographs, with the aid of the City Engineer of Daytona Beach. *See §57*

11. OTHER CONTROL

Nine topographic stations were established. Two, which have not been reported as landmarks on Form 567, are:

Clock Tower, 1950 *See §37*
Tomoka Fire Lookout Tower, 1951

12. OTHER INTERIOR FEATURES

All roads and buildings have been classified in accordance with Paragraph 5441 and 5446 of the Topographic Manual, Part II, dated 1949.

The towns of Daytona Beach, Holly Hill and South Daytona have urban limits. The urban limits were delineated by the Washington Office and checked by the field inspection. These limits are shown on the contact prints. *These limits refined by field editor. ENR*

All bridge information as listed in the "U. S. Engineers List of Bridges Over Navigable Waters in the U. S., dated July, 1941, and its Supplement, dated January 1, 1948," was verified in the field. All clearances were carefully measured with a steel tape, and the published description verified except for discrepancies which were reported to the local District Engineer. (See copy attached to report of quadrangle T-9305, Project Ph-35A(48)).

13. GEOGRAPHIC NAMES

This is the subject of a "Special Report" which was submitted by Joseph K. Wilson, ^{*}Cartographer, on 21 July 1950.

** Filed in Div. of Charts - Geographic Names Section.*

14. SPECIAL REPORTS AND SUPPLEMENTAL DATA

A Coast Pilot Report for the Project was submitted by the Chief of Party in July 1950.* There are no other reports or special data, except as noted in Paragraphs 10 and 13.

* Filed in Coast Pilot Section, Div. of Charts.

15 February 1951

Submitted by:

John R. Smith

John R. Smith
Cartographic Survey Aid

9 March 1951

Approved by:

Harry F. Garber

Harry F. Garber
Chief of Party

MAP T 9100

PROJECT NO. PB-35B(48)

SCALE OF MAP 1:20,000

3 of 4

SCALE FACTOR 1.000

STATION	SOURCE OF INFORMATION (INDEX)	DATUM	LATITUDE OR Y-COORDINATE LONGITUDE OR X-COORDINATE	DISTANCE FROM GRID IN FEET. OR PROJECTION LINE IN METERS		DATUM CORRECTION	N.A. 1927 - DATUM DISTANCE FROM GRID OR PROJECTION LINE IN METERS		FACTOR DISTANCE FROM GRID OR PROJECTION LINE IN METERS
				FORWARD	(BACK)		FORWARD	(BACK)	
✓ T 10, 1934 (Fla. Geod. Sur.)	Volusia County Sta. Desc.	N.A. 1927	1,804,343.88 471,687.67	4,343.88 (5,656.12)	NORTH OF PROJECT				
/ T 11, 1934 (Fla. Geod. Sur.)	"	"	1,811,405.58 465,114.88	1,405.58 (8,594.42)	"				
✓ K 1, 1934 (Fla. Geod. Sur.)	"	"	1,772,306.61	2,306.61 (7,692.39)					
✓ K 9, 1934 (Fla. Geod. Sur.)	"	"	495,304.44	5,304.44 (4,695.56)					
✓ K 13, 1934 (Fla. Geod. Sur.)	"	"	1,763,845.0 487,219.7	3,845.0 (6,155.0)					
✓ K 10, 1934 (Fla. Geod. Sur.)	"	"	1,763,428.3 486,626.3	3,428.3 (6,571.7)					
✓ K 13, 1934 (Fla. Geod. Sur.)	"	"	1,760,220.4	220.4 (9,779.6)					
✓ K 14, 1934 (Fla. Geod. Sur.)	"	"	481,160.3 1,758,972.45	1,160.3 (8,839.7)					
✓ K 15, 1934 (Fla. Geod. Sur.)	"	"	477,227.04 1,757,372.27	8,972.45 (1,027.55)					
✓ K 18, 1934 (Fla. Geod. Sur.)	"	"	473,845.95 1,749,010.06	7,227.04 (2,772.96)					
✓ K 19, 1934 (Fla. Geod. Sur.)	"	"	461,780.53 1,747,831.71	7,372.27 (2,627.73)					
✓ K 20-2 (Fla. Geod. Sur.)	"	"	459,717.16 1,747,444.06	3,845.95 (6,154.05)					
✓ K 21, 1934 (Fla. Geod. Sur.)	"	"	458,272.52 1,746,347.80	9,010.06 (989.94)					
✓ K 22, 1934 (Fla. Geod. Sur.)	"	"	455,502.90	1,780.53 (8,219.47)					
✓ K 23, 1934 (Fla. Geod. Sur.)	"	"	455,502.90	7,831.71 (2,168.29)	WEST OF PROJECT				
✓ K 24, 1934 (Fla. Geod. Sur.)	"	"	455,502.90	9,717.16 (282.84)					
✓ K 25, 1934 (Fla. Geod. Sur.)	"	"	455,502.90	7,444.06 (2,555.94)					
✓ K 26, 1934 (Fla. Geod. Sur.)	"	"	455,502.90	8,272.52 (1,727.48)					
✓ K 27, 1934 (Fla. Geod. Sur.)	"	"	455,502.90	6,347.80 (3,652.20)					
✓ K 28, 1934 (Fla. Geod. Sur.)	"	"	455,502.90	5,502.90 (4,497.10)					

1 FT. = 3048006 METERS
COMPUTED BY: I. I. Saperstein

DATE: 10 July 1950

CHECKED BY: R. A. Reese

DATE: 1 Aug 1950

M. 2388-12

-6

MAP T. 9100

PROJECT NO. Ph-35B (48)

SCALE OF MAP 1:20,000

SCALE FACTOR 1.000

STATION	SOURCE OF INFORMATION (INDEX)	DATUM	LATITUDE OR U-COORDINATE LONGITUDE OR X-COORDINATE		DISTANCE FROM GRID IN FEET. OR PROJECTION LINE IN METERS		DATUM CORRECTION	N.A. 1927 - DATUM DISTANCE FROM GRID OR PROJECTION LINE IN METERS		FACTOR DISTANCE FROM GRID OR PROJECTION LINE IN METERS
DAYPORT, 1934	G.Ps. 123	N.A.	29	10	22.835			703.0	(1,144.2)	
			81	04	09.162			247.6	(1,373.7)	
WILBER, 1934	Pl. Coord. Pg. 2	"	1,742,229.71			2,229.71 (7,770.29)	EAST OF			
			514,348.98			4,348.98 (5,651.02)	PROJ.			
REVILLO, 1934	G.Ps. 123	"	29	13	01.774			54.6	(1,792.7)	
			81	00	18.305			494.4	(1,126.1)	
DUNES FM 1, 1934	Comp.	"	1,753,860.77			3,860.77 (6,139.23)	EAST OF			
			508,422.74			8,422.74 (1,577.26)	PROJ.			
DAYTONA TANK, 1934	G.Ps. 175	"	29	12	26.726			822.8	(1,024.4)	
			81	01	28.234			762.7	(858.1)	
HOLLY HILL, TANK 1934	"	"	29	14	43.540			1,340.5	(506.8)	
			81	02	20.035			541.0	(1,079.2)	
ORMOND, MUNICIPAL WATER TANK CENTER, 1934	Pl. Coord. Pg. 50	"	1,797,852.01			7,852.01 (2,147.99)	NORTH OF			
			479,958.53			9,958.53 (41.47)	PROJ.			
TOMOKO, 1934	Pl. Coord. Pg. 2	"	1,798,219.80			8,219.80 (1,780.20)	"			
			463,806.72			3,806.72 (6,193.28)	"			
HOMER, 1874	"	"	1,793,437.84			3,437.84 (6,562.16)	"			
			491,183.04			1,183.04 (8,816.96)	"			
SEABREEZE WATERWORKS TANK CENTER, 1934	G.Ps. 144	"	29	14	21.445			660.3	(1,187.0)	
			81	01	20.170			544.7	(1,075.6)	
SEABREEZE, 1934	"	"	29	14	21.319			656.4	(1,190.9)	
			81	01	20.197			545.4	(1,074.8)	
COQUINA, 1934	Pl. Coord. Pg. 15	"	1,802,115.06			2,115.06 (7,884.94)	NORTH OF			
			487,398.65			7,398.65 (2,601.35)	PROJ.			

1 FT. = 3048006 METER

COMPUTED BY: I. I. Saperstein

DATE 10 July 1950

CHECKED BY: R. A. Reese

DATE 1 Aug. 1950

M. 2388-12

SCALE FACTOR.....1.000

[illegible]

CHECKED BY: **R. A. Reece**

DATE 1 August 1950

M-2388-12

STATION	SOURCE OF INFORMATION (INDEX)	DATUM	LATITUDE OR U-COORDINATE LONGITUDE OR X-COORDINATE	DISTANCE FROM GRID IN FEET, OR PROJECTION LINE IN METERS	DATUM CORRECTION	N.A. 1927 - DATUM FROM GRID OR PROJECTION LINE IN METERS	FACTOR DISTANCE FROM GRID OR PROJECTION LINE IN METERS
OZONE, 1934	G.P.s. 144	N. A. 1927	29 07 51.714 81 01 24.630			1,592.1 (255.1) 665.8 (956.2)	
ORMOND, 1934	"	"	29 16 46.243 81 03 46.166		NORTH OF PROJECT	1,423.7 (423.6) 1,246.2 (373.4)	
DAYTONA, ST. PAULS CATHOLIC CHURCH SPIRE, 1906	G.P.s. 802	"	29 12 37.852 81 01 14.887	<i>Destroyed EHR</i>		1,165.3 (681.9) 402.2 (1,218.7)	
DAYTONA, AUTO CLUB FLAGSTAFF, 1906	"	"	29 12 46.885 81 00 03.452	<i>DESTROYED</i>		1,416.3 (430.9) 93.3 (1,527.6)	
DAYTONA, FIRST CONGREGATIONAL CHURCH SPIRE, 1906	"	"	29 12 43.719 81 01 19.483	<i>Destroyed EHR</i>		1,246.0 (501.2) 526.3 (1,094.5)	
DAYTONA, YACHT CLUB, JACKSTAFF, 1906	"	"	29 12 26.429 81 01 00.079			813.6 (1,033.6) 2.1 (1,618.8)	
DAYTONA, DESPLANDS HOTEL, FLAG, 1906	G.P.s. 803	"	29 12 32.945 81 01 12.743			1,014.3 (832.9) 344.2 (1,276.5)	
ORMOND HOTEL CHIMNEY, 1906	Pl. Coord. Pg. 173	"	1,801,879.86 485,124.15	1,879.86 (8,120.14) 5,124.15 (4,875.85)	NORTH OF PROJECT		
T 1, 1934 (Fla. Geod. Sur.)	Velusia County Sta. Desc.	"	1,767,563.0 494,164.6	7,563.0 (2,437.0) 4,164.6 (5,835.4)			
T 4, 1934 (Fla. Geod. Sur.)	"	"	1,777,065.0 489,728.9	7,065.0 (2,935.0) 9,728.9 (271.1)			
T 5, 1934 (Fla. Geod. Sur.)	"	"	1,785,130.7 485,845.0	5,130.7 (4,869.3) 5,845.0 (4,155.0)			
T 9, 1934 (Fla. Geod. Sur.)	"	"	1,800,464.85 478,378.26	464.85 (9,535.15) 8,378.26 (1,621.74)	NORTH OF PROJECT		

1 FT. = .3048006 METER

COMPUTED BY: I. I. Saperstein

DATE 10 July 1950

CHECKED BY: R. A. Reece

DATE 1 August 1950

M-2388-12

5

COMPILATION REPORT T-9100PHOTOGRAMMETRIC PLOT REPORT.

Submitted with T-9101.

31. DELINEATION.

The graphic method was used.

After the manuscript was complete, a later flight of photographs along the shoreline was received. These photographs were used to correct the manuscript.

* 1951 single-lens. See § 51.

32. CONTROL.

The identification of control was good. It is sufficiently spaced to insure good detail points.

33. SUPPLEMENTAL DATA.

None used. GLO plats used for land lines. ENR

34. CONTOURS AND DRAINAGE.

Contours have been changed in a few places around swamp areas. Such changes have been noted on the discrepancy overlay.

No difficulty was encountered in delineation of drainage.

35. SHORELINE AND ALONGSHORE DETAILS.

The shoreline inspection was adequate.

Low-water line data were furnished by the field inspector.

36. OFFSHORE DETAILS.

No statement.

37. LANDMARKS AND AIDS.

Item 9 states there are eleven landmarks. There are twelve with the addition of a clock tower which was recommended on Form 524 but omitted from Form 567. The tower has been added to the latter form. *See § 56 and attached Forms 567*

38. CONTROL FOR FUTURE SURVEYS.

Thirty-one (31) Forms 524 are submitted with the manuscript data. *Only 21 filed. See § 10. ENR*

A list of recoverable topographic stations has been prepared and included under Item 49.

39. JUNCTIONS.

There is no contemporary survey to the west of this quadrangle. C. of E. PORT ORANGE quadrangle, 1:50,000 scale, 1947, on the east and C. of E. ORMOND quadrangle, 1:50,000 scale, 1946, on the north, are not in agreement. Detail has been carried approximately 1.25 cm over the neat line. Survey No. T-9101 to the south is in agreement.

40. HORIZONTAL AND VERTICAL ACCURACY.

No statement.

41. PUBLIC LAND LINES.

Section and grant lines have been shown on an ozalid print of the map manuscript for investigation by the field editor.

46. COMPARISON WITH EXISTING MAPS.

Comparison was made with planimetric map T-4553, scale 1:20,000, dated 1930. The two are in fair agreement.

47. COMPARISON WITH NAUTICAL CHARTS.

Comparison was made with Chart 843, scale 1:40,000, published 1938, corrected 23 December 1949.


It appears that the map listed in Item 46 is the source of most of the topography on the nautical chart, and the same small differences are to be found between said chart and the map manuscript.

ITEMS TO BE APPLIED TO NAUTICAL CHARTS IMMEDIATELY.


None.

ITEMS TO BE CARRIED FORWARD.

None.


Robert R. Wagner
Cartographic Survey Aid

APPROVED AND FORWARDED:


Arthur L. Wardwell
Chief of Party

48. GEOGRAPHIC NAME LIST.

- ATLANTIC OCEAN ✓
BETHUNE-COOKMAN COLLEGE ✓✓
CARLTON BLANK BRIDGE ✓
 COUNTY COMMISSIONER DISTRICT 2 } Not mapped. ENR
 COUNTY COMMISSIONER DISTRICT 4 }
 COUNTY COMMISSIONER DISTRICT 5 }
CYPRESS STREET SCHOOL RECREATION PARK ✓
DAYTONA BEACH ✓
DAYTONA BEACH GOLF AND COUNTRY CLUB ✓
DAYTONA BEACH MUNICIPAL AIRPORT ✓
DAYTONA BEACH MUNICIPAL YACHT BASIN ✓ (See below) ENR
FAIRVIEW-MAIN STREET BRIDGE ✓
FLORIDA ✓
HALIFAX DISTRICT HOSPITAL ✓
HALIFAX RIVER ✓
HOLLY HILL ✓
LIVEOAK PARK ✓
MAINLAND HIGH SCHOOL ✓
MEMORIAL STADIUM ✓
MOUNT ARAT CEMETERY ✓
MOUNT SINAI CEMETERY ✓
MUNICIPAL WATERFRONT PARK ✓
PINEWOOD CEMETERY ✓
U. S. 1 Fla 5
U. S. 92 Fla 60
SEABREEZE ✓
SEABREEZE GOLF COURSE ✓ Deleted by field editor. ENR
SEABREEZE HIGH SCHOOL ✓
SOUTH BRIDGE ✓
SOUTH DAYTONA ✓
SUNNYLAND PARK ✓
STATE 1A ✓
STATE 5 } See above
STATE 600 }
Florida East Coast RR ✓
Intracoastal Waterway ✓
Municipal Yacht Basin ✓
City Island ✓
Seabreeze Bridge ✓✓
 Names approved:
 12-7-53
 aju

48. GEOGRAPHIC NAME LIST (CONTINUED)TOMOKA RIVER
TOMOKA ROAD

(Pending with B-G-N.)

VOLUSIA COUNTY
VOLUSIA COUNTY KENNEL CLUBPUBLIC LAND GRANTSC. W. BULOW ✓
BRIGGS AND ROBERTSON ✓
B. SEGUI ✓
PATRICK DEAN ✓
F. BETHUNE ✓HEIRS OF THOMAS FITCH ✓
J. M. HERNANDEZ ✓

SAMUEL WILLIAMS ✓

Names underlined in red
are approved on basis
of project names report

1-23-52

L. Hock

(Subject to Field Edit)

Checked + approved

12-7-55

GJW

Florida
Halifax River
7417

~~70 - Ref Signature~~

~~731 - For Recording~~

Vault - For Registering

9100

49. NOTES FOR THE HYDROGRAPHER.

Recoverable topographic stations of use to the hydrographer area as follows:

RADIO TOWER 1950 (WNDB) (HIGHEST 3 Towers)

RADIO TOWER 1950 (WMFJ)

STACK 1950

DOM ~~E~~ 1950

RADIO TOWER 1950 (WROD) ✓

FLAGSTAFF ~~FLAG~~ 1950 ✓

~~CLOCK~~ TOWER 1950 See attached forms 567. Other control in area. ENR
(ELEV)
TANK ₁ 1950

TIDE COMPUTATION

PROJECT NO. Ph. 35(48)T. 9100

Time and date of exposure 0945 April 14, 1949 Reference station MAYPORT Mean range 4.1
 Date of field inspection _____ Subordinate station DAYTONA BEACH (OCEAN) Ratio of ranges 0.9

	Time		Height feet	Height x Ratio of ranges	Time h. m.	Time h. m.
	h.	m.				
High tide	9	05	4.9	4.4	9	05
Low tide	14	56	- 0.9	- 0.8	-	30
Duration of rise or fall	5	51	Range of tide		8	35
				5.2		
			Corrected time at Subordinate station		Corrected time at Subordinate station	
					14 26	

	h.	m.	feet	feet	Photo. No.
Time H. T. or L. T.	8	35			
Required time Interval	9	45	Ht. H. T. or L. T. Tabular correction Stage of tide above MLW	4.9 0.5 4.4	49-0-132 to 49-0-136
Time H. T. or L. T.			Ht. H. T. or L. T. Tabular correction Stage of tide above MLW		
Required time Interval			Ht. H. T. or L. T. Tabular correction Stage of tide above MLW		
Time H. T. or L. T.			Ht. H. T. or L. T. Tabular correction Stage of tide above MLW		
Required time Interval			Ht. H. T. or L. T. Tabular correction Stage of tide above MLW		
Time H. T. or L. T.			Ht. H. T. or L. T. Tabular correction Stage of tide above MLW		
Required time Interval			Ht. H. T. or L. T. Tabular correction Stage of tide above MLW		
Time H. T. or L. T.			Ht. H. T. or L. T. Tabular correction Stage of tide above MLW		
Required time Interval			Ht. H. T. or L. T. Tabular correction Stage of tide above MLW		

M-2617-12

Computed by Robert R. Wagner Checked by Webber W. Dawsey

TIDE COMPUTATION

PROJECT NO. Ph-35(48) T- 9100

Time and date of exposure 1445 April 6, 1949 Reference station MAYPORT Mean range 4.1
 Date of field inspection Subordinate station DAYTONA BEACH (OCEAN) Ratio of ranges 0.9

	Time		Height feet	Height x Ratio of ranges	Time
	h.	m.			
High tide	13	54	3.4	3.1	13 54
Low tide	19	58	0.3	0.3	- 30
Duration of rise or fall	6.04		2.8		13 24

	Range of tide	Height feet	Height x Ratio of ranges	Time	
				h.	m.
High tide	High tide	3.4	3.1	13	54
Low tide	Low tide	0.3	0.3	-	30
Range of tide				Corrected time at Subordinate station	
				13 24	
				High tide at Ref. Sta.	
				Time difference	
				Corrected time at Subordinate station	
				13 24	
				Time difference	
				Corrected time at Subordinate station	
				13 24	
				Time difference	
				Corrected time at Subordinate station	
				13 24	
				Time difference	
				Corrected time at Subordinate station	
				13 24	
				Time difference	
				Corrected time at Subordinate station	
				13 24	
				Time difference	
				Corrected time at Subordinate station	
				13 24	
				Time difference	
				Corrected time at Subordinate station	
				13 24	
				Time difference	
				Corrected time at Subordinate station	
				13 24	
				Time difference	
				Corrected time at Subordinate station	
				13 24	
				Time difference	
				Corrected time at Subordinate station	
				13 24	
				Time difference	
				Corrected time at Subordinate station	
				13 24	
				Time difference	
				Corrected time at Subordinate station	
				13 24	
				Time difference	
				Corrected time at Subordinate station	
				13 24	
				Time difference	
				Corrected time at Subordinate station	
				13 24	
				Time difference	
				Corrected time at Subordinate station	
				13 24	
				Time difference	
				Corrected time at Subordinate station	
				13 24	
				Time difference	
				Corrected time at Subordinate station	
				13 24	
				Time difference	
				Corrected time at Subordinate station	
				13 24	
				Time difference	
				Corrected time at Subordinate station	
				13 24	
				Time difference	
				Corrected time at Subordinate station	
				13 24	
				Time difference	
				Corrected time at Subordinate station	
				13 24	
				Time difference	
				Corrected time at Subordinate station	
				13 24	
				Time difference	
				Corrected time at Subordinate station	
				13 24	
				Time difference	
				Corrected time at Subordinate station	
				13 24	
				Time difference	
				Corrected time at Subordinate station	
				13 24	
				Time difference	
				Corrected time at Subordinate station	
				13 24	
				Time difference	
				Corrected time at Subordinate station	
				13 24	
				Time difference	
				Corrected time at Subordinate station	
				13 24	
				Time difference	
				Corrected time at Subordinate station	
				13 24	
				Time difference	
				Corrected time at Subordinate station	
				13 24	
				Time difference	
				Corrected time at Subordinate station	
				13 24	
				Time difference	
				Corrected time at Subordinate station	
				13 24	
				Time difference	
				Corrected time at Subordinate station	
				13 24	
				Time difference	
				Corrected time at Subordinate station	
				13 24	
				Time difference	
				Corrected time at Subordinate station	
				13 24	
				Time difference	
				Corrected time at Subordinate station	
				13 24	
				Time difference	
				Corrected time at Subordinate station	
				13 24	
				Time difference	
				Corrected time at Subordinate station	
				13 24	
				Time difference	
				Corrected time at Subordinate station	
				13 24	
				Time difference	
				Corrected time at Subordinate station	
				13 24	
				Time difference	
				Corrected time at Subordinate station	
				13 24	
				Time difference	
				Corrected time at Subordinate station	
				13 24	
				Time difference	
				Corrected time at Subordinate station	
				13 24	
				Time difference	
				Corrected time at Subordinate station	
				13 24	
				Time difference	
				Corrected time at Subordinate station	
				13 24	
				Time difference	
				Corrected time at Subordinate station	
				13 24	
				Time difference	
				Corrected time at Subordinate station	
				13 24	
				Time difference	
				Corrected time at Subordinate station	
				13 24	
				Time difference	
				Corrected time at Subordinate station	
				13 24	
				Time difference	
				Corrected time at Subordinate station	
				13 24	
				Time difference	
				Corrected time at Subordinate station	
				13 24	
				Time difference	
				Corrected time at Subordinate station	
				13 24	

	h. m.		Ht. H. T. or L. T.	Tabular correction	Stage of tide above MLW	feet	Photo. No.
	h.	m.					
Time H. T. or L. T.	13	24	Ht. H. T. or L. T.	Tabular correction	Stage of tide above MLW	3.4	49-0-81 to
Required time	14	45	Tabular correction	Stage of tide above MLW	Stage of tide above MLW	0.4	49-0-84
Interval	1	21	Stage of tide above MLW	Stage of tide above MLW	Feature above MLW	3.0	49-0-106 to
Time H. T. or L. T.			Ht. H. T. or L. T.	Tabular correction	Stage of tide above MLW		49-0-112
Required time			Tabular correction	Stage of tide above MLW	Feature above MLW		
Interval			Stage of tide above MLW	Stage of tide above MLW	Feature above MLW		
Time H. T. or L. T.			Ht. H. T. or L. T.	Tabular correction	Stage of tide above MLW		
Required time			Tabular correction	Stage of tide above MLW	Feature above MLW		
Interval			Stage of tide above MLW	Stage of tide above MLW	Feature above MLW		
Time H. T. or L. T.			Ht. H. T. or L. T.	Tabular correction	Stage of tide above MLW		
Required time			Tabular correction	Stage of tide above MLW	Feature above MLW		
Interval			Stage of tide above MLW	Stage of tide above MLW	Feature above MLW		
Time H. T. or L. T.			Ht. H. T. or L. T.	Tabular correction	Stage of tide above MLW		
Required time			Tabular correction	Stage of tide above MLW	Feature above MLW		
Interval			Stage of tide above MLW	Stage of tide above MLW	Feature above MLW		

FIELD EDIT REPORT
Project Ph-35(48)
Quadrangle T-9100

51. METHODS

The field edit of this area was accomplished by standard surveying methods in conjunction with visual inspection. Actual field work was started 9 October 1952 and was completed 12 November 1952.

Field edit data appears on the field edit sheet, discrepancy prints, photographs 51-0-4248, 4249, 4250, 49-0-134, 163 and 164 and in this report.

A legend appears on the field edit sheet which is self-explanatory.

52. ADEQUACY OF COMPILATION

The map compilation is adequate and will be complete after field edit data have been applied.

53. MAP ACCURACY

The horizontal accuracy of the map detail is relatively good.

The accuracy of the contouring, in general, is good.

A few minor corrections were made in the contouring to improve the topographic expression.

Five small areas have been earth-filled along the west bank of the Halifax River and elevations of these are shown. The contours were not shown on these fills due to the fact that the grading had not been completed.

The contours have been dropped at the present edge of the active borrow pits at Lat. $29^{\circ} 13' \dagger$ N., Long. $81^{\circ} 03' \dagger$ W.

54. RECOMMENDATIONS

None.

55. EXAMINATION OF PROOF COPY

It is believed that Mr. C. H. Moneypenny, City Engineer and Director of Public Works of Daytona Beach, Florida, is best qualified to examine a proof copy of this work.

56. LANDMARKS AND AIDS

Ref. to item 37 - Compilation Report

Ten prominent objects (Landmarks for Nautical Charts) have been listed on Form 567 and two previously listed landmarks have been recommended for deletion. The heights of all recommended landmarks were rechecked, and are correct as indicated on Forms 524 and 567.

The name of one recommended landmark (DOME, 1950) has been changed to SPIRE, 1952 as this is more prominent than the dome.

Dome retained. See Chart Ltr 921(1952) EHK

Eleven fixed aids have been listed on Form 567 for deletion as they no longer exist.

SIX ^{*} Nineteen fixed aids have been listed on Form 567 for charting. Four of these aids, HALIFAX RIVER DAYBEACON 91, BOAT WORKS CHANNEL DAYBEACONS 3, 4 and 6 were located on the field edit sheet by planetable methods.

** Includes aids submitted by F.I. party [Ch. Ltr. 921(1952)] EHK Only six changes. & 848(1951)*

57. BOUNDARIES, MONUMENTS AND LINES

Ref. to item 10 - Field Inspection Report.

Several additional boundary monuments and theoretical corners were recovered, confirmed, and are shown on the field edit sheet.

The corporate limits of Daytona Beach include all of the land formerly acquired by the U. S. Government for the use of the Daytona Beach Naval Air Station (Daytona Beach Municipal Airport).

The area in the vicinity of Lat. $29^{\circ} 12'$, Long. $81^{\circ} 03'$ has been included, and indicated as such on the field edit sheet, as urban.

58. OTHER INTERIOR FEATURES

Ref. to item 12 - Field Inspection Report.

Numerous additional roads, city streets and buildings have been shown on the field edit sheet.

The reclassification of roads has been indicated where justifiable.

Two submarine cables and two submarine pipe lines have been shown on the field edit sheet.

The following data is for the new bridge spanning Halifax River near Lat. $29^{\circ} 14'$, Long. $81^{\circ} 01'$:

Name: SEABREEZE BRIDGE
 Type: Bascule
 Horizontal Clearance: 89.7 feet
 Vertical Clearance: 20.1 feet (closed at Est. M.H.W.)

In reference to the widening of U. S. Highway No. 1, the centerline of the island separating the two lanes is shown on the field edit sheet. Continue the compilation of this dual land road from the dual lane road now shown on the manuscript to the northern limits of the area. ✓

59. JUNCTIONS

Satisfactory junctions have been made with all contemporary quadrangles.

2 December 1952
 Submitted by:

James E. Hundley
 James E. Hundley, by *P. Taylor*?
 Cartographer

SW

9 December 1952
 Approved by:

Paul Taylor
 Paul Taylor
 Lt. Comdr., USCGS
 Chief of Party

50.

PHOTOGRAMMETRIC OFFICE REVIEW

T. 9100

1. Projection and grids J.G. 2. Title J.G. 3. Manuscript numbers J.G. 4. Manuscript size J.G.

CONTROL STATIONS

5. Horizontal control stations of third-order or higher accuracy M.M.S. 6. Recoverable horizontal stations of less than third-order accuracy (topographic stations) J.G. ~~7. Bench marks~~ 8. Bench marks J.G.
9. Plotting of sextant fixes J.G. 10. Photogrammetric plot report J.G. 11. Detail points J.G.

ALONGSHORE AREAS

(Nautical Chart Data)

12. Shoreline J.G. 13. Low-water line J.G. 14. Rocks, shoals, etc. J.G. 15. Bridges J.G. 16. Aids to navigation J.G. 17. Landmarks J.G. 18. Other alongshore physical features J.G. 19. Other along-shore cultural features J.G.

PHYSICAL FEATURES

20. Water features J.G. 21. Natural ground cover J.G. 22. Planetable contours J.G. ~~23. Spot elevations~~
~~24. Contours in general~~ 24. Contours in general J.G. 25. Spot elevations J.G. 26. Other physical features J.G.

CULTURAL FEATURES

27. Roads J.G. 28. Buildings J.G. 29. Railroads J.G. 30. Other cultural features J.G.

BOUNDARIES

31. Boundary lines J.G. 32. Public land lines J.G.

MISCELLANEOUS

33. Geographic names J.G. 34. Junctions J.G. 35. Legibility of the manuscript J.G. 36. Discrepancy overlay J.G. 37. Descriptive Report J.G. 38. Field inspection photographs J.G. 39. Forms J.G.
40. Jesse A. Giles Jesse A. Giles William A. Rasure
Reviewer Supervisor, Review Section or Unit

41. Remarks (see attached sheet)

FIELD COMPLETION ADDITIONS AND CORRECTIONS TO THE MANUSCRIPT

42. Additions and corrections furnished by the field completion survey have been applied to the manuscript. The manuscript is now complete except as noted under item 43.

Jesse A. Giles
Compiler

William A. Rasure
Supervisor

43. Remarks:

Review Report
Topographic Map T-9100
8 December 1953

62. Comparison with Registered Topographic Surveys.-

T-1343	1:20,000	1874
T-4067	"	1924
T-4132	"	1925
T-4552	"	1928
T-4553	"	1928

There are numerous cultural and physical changes since the date of these earlier surveys. Survey T-9100 supersedes the prior surveys for nautical charting of areas of the prior surveys common to T-9100.

63. Comparison with maps of other Agencies.- None

64. Comparison with contemporary Hydrographic surveys.-None

65. Comparison with Nautical Charts.-

843	1:40,000	1952	corrected to 53-4/27
1244	1:80,000	1930	corrected to 51-3/19

Charts do not show shoreline changes in the Halifax River as effected by dredging. There are also changes in roads and other features to add to the charts (see sub-heading 58). See also sub-heading 67 below.

66. Adequacy of Results and Future Surveys.-This map meets the National Standards of map accuracy and complies with project instructions.

67. Landmarks and Aids.-Forms 567, copies attached, showed "Radio Mast" for skeleton steel towers. These were corrected at the time of review. Chart 843 should accordingly be corrected.

A new form 567 was prepared in conjunction with this review for "Radio Tower, Highest of Three". Two lower towers were positioned at this station by the field editor.

Radio Tower (WMFJ, southeast tower) is shown on both charts. It was recommended for deletion by Chart Letter L 848 (1951) and was not reported in existence by the field editor for this survey in 1952.

68. Land Lines.-The boundaries of the C W Bulow and F. Bethune grants, T-16S, R-32 and 33E, according to G.L.O. plats pbt 5 to 6 chains N of the positions shown on this map manuscript. However, the mappositions have been retained because they were referenced to recovered manuments and adjacent map features.

69. Junctions: The junction of this survey with surveys T-9911 and T-9912 of project Ph-82(51) was made by comparison with the field inspection photographs of project Ph-82(51). Differences which involved slight shifts in contours were reconciled. No recovery of land lines was noted in project Ph-82(51). Unless compilation and field edit of project Ph-82 discloses further discrepancies, the surveys junction.

Reviewed by:

Everett H. Ramey
Everett H. Ramey

APPROVED

L. C. Landy
Chief, Review Branch
Div. of Photogrammetry

Max D. Kelts
Chief, Nautical Chart Branch
Division of Charts

L. W. Seaman
Chief, Div. of Photogrammetry
1 Oct 59

J. Bowie
Chief, Div. of Coastal Surveys

PHOTOGRAMMETRIC REVIEW SECTION

DEPARTMENT OF COMMERCE

U. S. COAST AND GEODETIC SURVEY

NONFLOATING AIDS OR LANDMARKS FOR CHARTS

STRIKE OUT ONE!

TO BE DELETED

Daytona Beach, Florida

May 1

195

I recommend that the following objects which have ~~been~~ been inspected from seaward to determine their value as landmarks be ~~deleted~~ *deleted from* the charts indicated.

The positions given have been checked after listing by **Joseph K. Wilson**

Harry P. Garber

Chief of Party.

STATE	FLORIDA			SIGNAL NAME	POSITION				METHOD OF LOCATION AND SURVEY NO.	DATE OF LOCATION	HARBOR CHART	INSHORE CHART	OFFSHORE CHART	CHARTS AFFECTE
	CHARTING NAME	DESCRIPTION	LATITUDE		LONGITUDE		DATUM							
			°		'	°		'						
EN.	BOAT WORKS CHANNEL DAYBEACON 5		29 12.1		81 00.5				1950	X			843	
EN.	BOAT WORKS CHANNEL DAYBEACON 6		29 12.2		81 00.5				"	X			843	
EN.	BOAT WORKS CHANNEL DAYBEACON 7		29 12.1		81 00.6				"	X			843	
EN.	BOAT WORKS CHANNEL DAYBEACON 8		29 12.2		81 00.6				"	X			843	
			Bris #1 to #10 per in 1959 light list											
			ATTENTION: COAST PILOT SECTION											
			CHIT. No 848 (1951)											

This form shall be prepared in accordance with Hydrographic Manual, pages 800 to 804. Positions of charted landmarks and *nonfloating* *beacons* *shall* *be* *considered* *for* *the* *charts* *of* *the* *area* *and* *not* *be* *omitted* *on* *this* *form*. The data should be considered for the charts of the area and not be omitted on this form.

DEPARTMENT OF COMMERCE
U. S. COAST AND GEODETIC SURVEY

PHOTOGRAMMETRIC REVIEW SECTION

NON-POLYMERIZABLE OR LANDMARKS FOR CHARTS

TO BE DELETED

STRIKE OUT ONE

Jacksonville, Florida

31 May 1941

I recommend that the following objects which have ~~been examined~~ been inspected from seaward to determine their value as landmarks be ~~examined~~ *(deleted from)* the charts indicated.

The positions given have been checked after listing by ~~Ernest R. Wilson~~

HARRY F. CARBER	<i>Chief of Party.</i>
------------------------	------------------------

[illegible]

This form shall be prepared in accordance with Hydrographic Manual, pages 800 to 804. Positions of charted landmarks and *nonfloating*, *nonfixed*, *nonbuoyed*, *nonlighted*, *nonpowered*, *nonmanned*, *nonoperational*, *nonactive* aids to navigation shall be considered for the charts of the area and not be shown on the chart. The data should be considered for the charts of the area and not be shown on the chart.

PHOTOGRAMMETRIC REVIEW SECTION DEPARTMENT OF COMMERCE
U. S. COAST AND GEODETIC SURVEY

Page 1 of 4

TO BE CHARTED
~~TO BE DELETED~~

STRIKE OUT ONE

NONFLOATING AIDS OR LANDMARKS FOR CHARTS

Tampa, Florida

26 June, 1951

I recommend that the following objects which have ~~been~~ been inspected from seaward to determine their value as landmarks be charted on ~~charts~~ the charts indicated.

The positions given have been checked after listing by

Robert R. Wagner

Tampa Photogrammetric Office

Arthur L. Wardwell

Chief of Party

STATE	CHARTING NAME	DESCRIPTION	SIGNAL NAME	POSITION				METHOD OF LOCATION AND SURVEY NO.	DATE OF LOCATION	HARBOR CHART	INSHORE CHART	OFFSHORE CHART	CHARTS AFFECTED
				LATITUDE	LONGITUDE	D. M. METERS	D. P. METERS						
FLORIDA	BN. 82	HALIFAX RIVER (Red band pointer with yellow top on white pile. Red reflector)		29 15	81 02	80	39	N. A. T-9100 1927 Radio Plot	April 1950	X			843
	BN. 83	HALIFAX RIVER (Black band and pointer with yellow top on white pile. Green reflector)		29 14	81 01	1157	1239	"	Feb. 1951	X			"
	LT. 84	HALIFAX RIVER (Red triangular daymark with yellow border on white pile-dolphin)		29 14	81 01	130	820	"	April 1950	X			"
	BN. 86	HALIFAX RIVER (Red band and pointer with yellow top. Red reflector)		29 13	81 01	1185	485	"	"	X			"
	BN. 88	HALIFAX RIVER (Red triangular daymark with yellow border on white pile. Red reflector)		29 13	81 01	791	392	"	"	X			"
	BN. 95	HALIFAX RIVER (Black square daymark with yellow border on white pile. Green reflector)		29 12	81 00	1607	1266	"	"	X			"
	BN. 96	HALIFAX RIVER (Red band and pointer with yellow top on white pile-red reflector)		29 12	81 00	1409	1053	"	"	X			"
													27

This form shall be prepared in accordance with Hydrographic Manual, pages 800 to 804. Positions of charted landmarks and nonfloating aids should be considered for the charts of the area and not for

PHOTOGRAMMETRIC REVIEW SECTION DEPARTMENT OF COMMERCE
U. S. COAST AND GEODETIC SURVEY

Page 2 of 4

NONFLOATING AIDS OR LANDMARKS FOR CHARTS

TO BE CHARTED
TO BE DELETED
XXXXXXXXXX

STRIKE OUT ONE

Tampa, Florida 26 June 1951

I recommend that the following objects which have ~~been~~ been inspected from seaward to determine their value as landmarks be charted on ~~deleted from~~ the charts indicated.

The positions given have been checked after listing by

Robert R. Wagner

Tampa Photogrammetric Office

Arthur L. Wardwell

Chief of Party

STATE	FLORIDA	CHARTING NAME	DESCRIPTION	SIGNAL NAME	POSITION					METHOD OF LOCATION AND SURVEY NO.	DATE OF LOCATION	HARBOR CHART	INSHORE CHART	OFFSHORE CHART	CHARTS AFFECTED	
					LATITUDE		LONGITUDE		DATUM							
					°	'	°	'								D. M. METERS
BN. 1	DAYTONA BEACH (Pointer on pile)	Green reflector			29	12	1291	81	00	1931	1927	T-9100	April	X		843
BN. 2	DAYTONA BEACH (Pointer on pile)	Red reflector			29	12	1159	81	00	1941				X		
BN. 3	DAYTONA BEACH (Pointer on pile)				29	12	1051	81	00	1167				X		
BN. 4	DAYTONA BEACH (Pointer on pile)				29	12	1098	81	00	1201				X		
BN. 5	DAYTONA BEACH (Pointer on pile)				29	12	974	81	00	1321	"	"		X	"	
BN. 6	DAYTONA BEACH (Red pointer on pile)				29	12	1016	81	00	1949				X	"	
LIGHT	DAYTONA BEACH RANGE FRONT (White diamond daymark with red border and yellow center)				29	12	974	81	00	1421	"	"		X	"	28

This form shall be prepared in accordance with Hydrographic Manual, pages 800 to 804. Positions of charted landmarks and nonfloating aids should be considered for the charts of the area and not for

PHOTOGRAMMETRIC REVIEW SECTION

DEPARTMENT OF COMMERCE

U. S. COAST AND GEODETIC SURVEY

Page 3 of 4

NONFLOATING AIDS OR LANDMARKS FOR CHARTS

TO BE CHARTED
~~TO BE DELETED~~

STRIKE OUT ONE

Tampa, Florida

26 June, 1951

I recommend that the following objects which have ~~(has been)~~ been inspected from seaward to determine their value as landmarks be charted on ~~(deleted from)~~ the charts indicated.

The positions given have been checked after listing by

Robert H. Wagner

Tampa Photogrammetric Office

Arthur L. Wardwell

Chief of Party.

STATE	CHARTING NAME	DESCRIPTION	SIGNAL NAME	POSITION						METHOD OF LOCATION AND SURVEY NO.	DATE OF LOCATION	HARBOR CHART	INSHORE CHART	OFFSHORE CHART	CHARTS AFFECTED
				LATITUDE		LONGITUDE									
				°	'	D. M. METERS	°	'	D. P. METERS						
FLORIDA	Ch. L. No. 848C (1957)			29	12	893	81	00	1590	N.A. 1927		X		843	
	LIGHT	DAYTONA BEACH RANGE REAR (White diamond daymark with red border and yellow center)		29	12	360	81	00	599	"	"	X		"	
	BN. 1	BOAT WORKS CHANNEL (Black number on white pile and pointer)		29	12	409	81	00	614	"	"	X		"	
	BN. 2A	BOAT WORKS CHANNEL (Red number on white pile and pointer)		29	12	321	81	00	672	"	"	X		"	
	BN. 3	BOAT WORKS CHANNEL (Black number on white pile and pointer)		29	12	362	81	00	692	"	"	X		"	
	BN. 4	BOAT WORKS CHANNEL (Red number on white pile and pointer)		29	12	202	81	00	918	"	"	X		"	
	BN. 7	BOAT WORKS CHANNEL (Black number on white pile and pointer)		29	12	231	81	00	938	"	"	X		"	
	BN. 8	BOAT WORKS CHANNEL (Red number on white pile and pointer)													
														29	

This form shall be prepared in accordance with Hydrographic Manual, pages 800 to 804. Positions of charted landmarks and nonfloating aids should be considered for the charts of the area and not by

PHOTOGRAMMETRIC REVIEW SECTION

DEPARTMENT OF COMMERCE
U. S. COAST AND GEODETIC SURVEY

Page 4 of 4

NONFLOATING AIDS OR LANDMARKS FOR CHARTS

TO BE CHARTED
~~TO BE DELETED~~

STRIKE OUT ONE

Tampa, Florida

26 June

19 51

I recommend that the following objects which have ~~been~~ been inspected from seaward to determine their value as landmarks be charted on ~~(Nautical Chart)~~ the charts indicated.

The positions given have been checked after listing by

Robert R. Wagner

Tampa Photogrammetric Office

Arthur L. Wardwell

Chief of Party.

STATE	FLORIDA	Ch. L. No 848 (1957)	SIGNAL NAME	DESCRIPTION	POSITION						METHOD OF LOCATION AND SURVEY No.	DATE OF LOCATION	HARBOR CHART	INSHORE CHART	OFFSHORE CHART	CHARTS AFFECTED	
					LATITUDE		LONGITUDE		DATUM								
					0	1	D. M. METERS	0		1							D. P. METERS
LIGHT		BOAT WORKS CHANNEL RANGE FRONT (Not in Light List)			29	12	87	81	00	1203	N.A. 1927	T-9100 Radial Flot	April 1950	X			843
LIGHT		BOAT WORKS CHANNEL RANGE REAR (Not in Light List)			29	12	60	81	00	1249	"	"	"	X			"
BN. 98		HALIFAX RIVER (Red band and pointer with yellow top on white pile. Red reflector)			29	12	422	81	00	578	"	"	"	X			"
LT. 99		HALIFAX RIVER (Black square daymark with yellow border on white pile dolphin)			29	11	1736	81	00	342	"	"	"	X			"
BN.100		HALIFAX RIVER (Red triangular daymark with yellow border on white pile. Red reflector)			29	11	1238	81	00	167	"	"	"	X			"
																	30

This form shall be prepared in accordance with Hydrographic Manual, pages 800 to 804. Positions of charted landmarks and nonfloating aids should be considered for the charts of the area and not for

NONFLOATING AIDS OR LANDMARKS FOR CHARTS

TO BE CHARTED
TO BE DELETED

STRIKE OUT ONE

Tampa, Florida

1 May, 1950

I recommend that the following objects which have ~~(have now)~~ been inspected from seaward to determine their value as landmarks be charted on ~~(deleted from)~~ the charts indicated.

The positions given have been checked after listing by

Robert R. Wagner

Tampa Photogrammetric Office

Arthur L. Wardwell

Chief of Party.

STATE			FLORIDA Ch L No 848 (1957)			POSITION						METHOD OF LOCATION AND SURVEY NO.	DATE OF LOCATION	HARBOR CHART	INSHORE CHART	OFFSHORE CHART	CHARTS AFFECTED
CHARTING NAME	DESCRIPTION	SIGNAL NAME	LATITUDE		LONGITUDE		DATUM										
			°	'	D. M. METERS	°		'	D. P. METERS								
(ELEV) TANK	HOLLY HILL TANK (Elev. steel water tank ht=135(147))		29	14	1340.5	81	02	541.0	N.A. 1927		1934	X	X		843 1244		
(ELEV) TANK	SEABREEZE WATER TANK (Elev. steel water tank ht = 150 (165))		29	14	660.2	81	01	544.7	"		"	X	X		843 1244		
FLAGSTAFF	SHERATON PLAZA HOTEL FLAGSTAFF (Metal flagstaff ht = 100 (108) 110 (123))		29	14	232	81	00	1194	"		April 1950	X	X		843 1244		
TANK (ELEV)	EAST DAYTONA BEACH MUNICIPAL WATER TANK (Elev. steel water tank ht = 150 (165) 170)		29	13	408	81	00	945	"		"	X	X		843 1244		
DOME	ST. PAULS CATHOLIC CHURCH DOME ht = 100(125)		29	13	60	81	01	1033	"		"	X	X		843 1244		
STACK	MAINLAND HIGH SCHOOL STACK (Red brick stack ht = 100(110) 90 (97))		29	12	1514	81	01	576	"		"	X	X		843 1244		
SPIRE	DAYTONA ST. PAULS CATHOLIC CHURCH SPIRE (SPANISH WAR VETERANS HALL) Grey shingled spire ht=60(69)		29	12	1165.4	81	01	402.1	"		1906	X	X		843 1244		

32

32

This form shall be prepared in accordance with Hydrographic Manual, pages 800 to 804. Positions of charted landmarks and nonfloating aids to navigation, if redetermined, shall be reported on this form. The data should be considered for the charts of the area and not by

TO BE CHARTED
TO BE DELETED

STRIKE OUT ONE

NONFLOATING AIDS OR LANDMARKS FOR CHARTS

Tampa, Florida

1 May 1950

I recommend that the following objects which have ~~just been~~ been inspected from seaward to determine their value as landmarks be charted on ~~(deleted from)~~ the charts indicated.

The positions given have been checked after listing by

Robert H. Wagner

Tampa Photogrammetric Office

Arthur L. Wardwell
Chief of Party.

STATE	CHARTING NAME	DESCRIPTION	SIGNAL NAME	POSITION					METHOD OF LOCATION AND SURVEY	DATE OF LOCATION	HARBOR CHART	INSHORE CHART	OFFSHORE CHART	CHARTS AFFECTED
				LATITUDE		LONGITUDE		DATUM						
				°	'	°	'							
FLORIDA	TOWER RADIO MAST	STATION WMFJ RADIO TOWER (Skeleton steel radio tower ht=178 (185))	29 12 1091	81 01 309	N. A. 1927	Radial Plot	April 1950	X	X	843 1244				
	TANK (ELEV)	DAYTONA MAIN WATER TANK (Elev. steel water tank ht=170(177))	29 12 818.3	81 01 787.5	"	Tri.	1947	X	X	843 1244				
	TOWER RADIO MAST	STATION WHOD RADIO TOWER (Skeleton steel radio tower ht=185(190))	29 11 564	81 00 746	"	Radial Plot	April 1950	X	X	843 1244				
	TOWER RADIO MAST	STATION WND B RADIO TOWER (Skeleton steel radio tower ht=351(359))	29 13 1362	81 03 81	"	"	1951 Elev	X	X	843 1244				
	TOWER	COQUINA ROCK CLOCK TOWER ht = 75(85) 55(65)	29 13 1382	81 00 835	"	"	"	X	X	843 1244				
														33

This form shall be prepared in accordance with Hydrographic Manual, pages 800 to 804. Positions of charted landmarks and *nonfloating aids* to navigation, if redetermined, shall be reported on this form. The data should be considered for the charts of the area and not by

NONFLOATING AIDS OR TENDRINKS FOR CHARTS

STRIKE OUT ONE

**TO BE CHARTED
REPEATED**

Tampa Photogrammetric Office, Tampa, Fla. 21 Jan. 1953

I recommend that the following objects which have ~~(44723-74723)~~ been inspected from seaward to determine their value as landmarks be charted on ~~(2472200-77722)~~ the charts indicated.

The positions given have been checked after listing by

Robert M. Wagner

J. E. March *Chief of Party.*

Chief of Party.

[illegible]

This form shall be prepared in accordance with Hydrographic Manual, pages 800 to 804. Positions of charted landmarks and *nonfloating*

**TOX BEX CHARTED
TO BE DELETED**

STRIKE OUT ONE

FOUNDATIONS FOR LANDMARKS FOR CHARTS

St. Augustine, Florida

1 December 1952

I recommend that the following objects which have ~~(been inspected from seaward)~~^(not been inspected from seaward) been inspected from seaward to determine their value as landmarks be charted on ~~(deleted from)~~^(added to) the charts indicated.

The positions given have been checked after listing by James E. Hudley

Paul Taylor

LEON, USCG'S

[illegible]

This form shall be prepared in accordance with Hydrographic Manual, pages 800 to 804. Positions of charted landmarks and *nonfloating*

DEPARTMENT OF COMMERCE
U. S. COAST AND GEODETIC SURVEY

TO BE CHARTED

STRIKE OUT ONE

NONFLOATING AIDS OR LANDMARKS FOR CHARTS

Washington, D.C. 24 Nov. 1953

I recommend that the following objects which have ~~not~~ been inspected from seaward to determine their value as landmarks be charted on ~~charts~~ the charts indicated.

The positions given have been checked after listing by

S. V. Lippitz

S. V. Grifith;

Chief of Party.

Lab. Office

[illegible]

This form shall be prepared in accordance with Hydrographic Manual, pages 800 to 804. Positions of charted landmarks and *nonfloating aids* to navigation, if redetermined, shall be reported on this form. The data should be considered for the charts of the area and not by individual field survey sheets. Information under each column heading should be given.

*** TABULATE SECONDS AND METERS**

M.2836.3

DEPARTMENT OF COMMERCE
U. S. COAST AND GEODETIC SURVEY

NONFLOATING AIDS OR LANDMARKS FOR CHARTS

STRIKE OUT ONE

NOT TO BE DELETED

Washington, D. C.

January 5 1961

I recommend that the following objects which have ~~been~~ been inspected from seaward to determine their value as landmarks be ~~deleted from~~ the charts indicated *Edward A. Kanner* *7.18.61*

The positions given have been checked after listing by

S. V. Griffin
Wash. Office

Chief of Party.

[illegible]

This form shall be prepared in accordance with Hydrographic Manual, pages 800 to 804. Positions of charted landmarks and *nonfloating aids* to navigation, if redetermined, shall be reported on this form. The data should be considered for the charts of the area and not by individual field survey sheets. Information under each column heading should be given.

* TABULATE SECONDS AND METERS

NAUTICAL CHARTS BRANCH

SURVEY NO. T-9100

Record of Application to Charts

[illegible]

M-2168-1

A basic hydrographic or topographic survey supersedes all information of like nature on the uncorrected chart. Give reasons for deviations, if any, from recommendations made under "Comparison with Charts" in the Review.