9504 N\$5

Diag. Cht. Nos. 1216-2 & 1217-2

Form 504

U. S. COAST AND GEODETIC SURVEY

DEPARTMENT OF COMMERCE

DESCRIPTIVE REPORT

Type of Survey Photo-Topographic

Field No. Ph-59 (50) Office No. T-9504 N & S

LOCALITY

State New Jersey

General locality Oceanville & Atlantic County

Locality Absecon

19/152

CHIEF OF PARTY

Harry F. Garber, Chief of Party Hubert A. Paten, Baltimore Phote, Office

LIBRARY & ARCHIVES

DATE November 17, 1955

B-1870-1 (1)

DATA RECORD

T - 9504

Project No. (II): Ph-59(50)

Quadrangle Name (IV):

Field Office (II): Pleasantville, N. J.

Chief of Party: Harry F. Garber

Photogrammetric Office (III): Baltimore, Maryland

Officer-in-Charge: H. A. Paton

Instructions dated (II) (III): 26 May 1950

Copy filed in Division of Photogrammetry (IV)
Office Files

Method of Compilation (III): Graphic

Manuscript Scale (III): 1:10,000

Stereoscopic Plotting Instrument Scale (III):

Scale Factor (III):

1,000

Date received in Washington Office (IV): 5-17-52 Date reported to Nautical Chart Branch (IV): 5-24-52

Applied to Chart No. 1216

Date: 7-53

Date registered (IV):

SEP 6 1955

Publication Scale (IV): 1:24,000

Publication date (IV):

Geographic Datum (III): N.A. 1927

Vertical Datum (III):

Mean sea level except as follows:

Elevations shown as (25) refer to mean high water Elevations shown as (5) refer to sounding datum i.e., mean low water or mean lower low water

Reference Station (III): FLY, 1931

Lat.:39 27' 02.431" (75.0) Long.: 74° 27' 28.838" (689.5")

Adjusted XXXXXXXXX

Plane Coordinates (IV):


State:

Zone:

X=

Roman numerals indicate whether the item is to be entered by (II) Field Party, (III) Photogrammetric Office, or (IV) Washington Office.

When entering names of personnel on this record give the surname and initials, not initials only.



(11) (111)

DATA RECORD

M. A. Stewart M. C. Moody Field Inspection by (II): H. R. Moore Date: July-Nov. 1950 L. F. Beugnet E. L. Williams Date: July-Nov. 1950 Planetable contouring by (II): See Page 2 Joseph K. Wilson Date: 5/23/52 Completion Surveys by (II): Mean High Water Location (III) (State date and method of location): 1950 - Field inspection Projection and Grids ruled by (IV): T. L. Janson Date: 1/8/51 Projection and Grids checked by (IV): H. D. Wolfe Date: 1/15/51 Control plotted by (III); Ruth M. Whitson Date: 4/30/51 Control checked by (III): Ruth R. Hartley Date: 5/9/51 Radial Plot or Stereoscopic Frank J. Tarcza Date: 5/29/51 Control extension by (III): **Planimetry** Date: Stereoscopic Instrument compilation (III): Contours Date: Manuscript delineated by (III): Judson Y. Council Date: 11/6/51 Ruth M. Whitson Photogrammetric Office Review by (III): Leroy A. Senasack Date: 1/31/52

Form T-Page 3

Raymond Glaser

Leroy A. Senasack

Raymond Glaser

Elevations on Manuscript

checked by (II) (III):

M-2618-12(4)

Date: 1/31/52

Camera (kind or source) (III): U.S.C. & G.S. Single lens, type "O" camera - 6" focal length

•		PHOTOGRAPHS (II	H)		
Number	Date	Time	Scale	Stage of Tide	1
~~ 5 0 -5 0 -0 68 56	4/16/50	1148	1:10,000	0.8	
857-859	11	1149	n	1.2	
860-862	tt	1150	11	land area	
884	ff	1208	11	1.6	
885	11	1208	tı	land area	
886-888	n	1209	tt	D.0	
§§§-89 0	11	1210	u	0.6	
896	17	1222	, n	0.1 (-0.2	ocean)
897	tt	1222	11	0.1	•
898	tt	1223	11	0.5	
899-900	- 11	1224	tt	0.8	
901-903	n	1225	11	0.8	

Tide (III)

**	Ratio of Ranges	Mean Range	Spring Range
Reference Station: Sandy Hook, N. J. Subordinate Station: Beach Thorofare (Shelter Island)	0.8	3.9	4.7
Subordinate Station: Absecon Cr. Entr. Absecon Bay	0.8		4.4

Washington Office Review by (IV): K. N. Maki

Final Drafting by (IV): RONALD HOPKINS T 9504 N
RONALD HOPKINS T 95045

Drafting verified for reproduction by (IV):

Date: 2/14/55

Date: 30 June 1953

Date: 3/3/55

Date:

Proof Edit by (IV):

Land Area (Sq. Statute Miles) (III): 38 sq. mi.

Shoreline (More than 200 meters to opposite shore) (III): 71 mi. Shoreline (Less than 200 meters to opposite shore) (III): 72 mi.

Control Leveling . Miles (II): 24.6

Number of Triangulation Stations searched for (II): 53 Recovered: 42 Identified: 22 Number of BMs searched for (II): 32 Recovered: 24 Identified:

Number of Recoverable Photo Stations established (III): 2 Stations searched for - 21

Number of Temporary Photo Hydro Stations established (III): none "recovered - 8


Remarks:

No.	Date	Time	Scale	Stage of Tide
** 927 - 929	4/16/50	1242-1243	1:10,000	0.6
930-931	tt	1244	u	0.5
932	ù	Ħ	ü	0.5 (0.0 ocean)

		Matio of	Mean	Spring
*Mullica River Hwy. Bridge		Ranges	Range	Range
Broad Creek Middle Thoro.		0.7	3.3	4.0
Beach Thorofare (R.R. Bridges)		0.7	3.4	4.1
Atlantic City (Steel Pier)		0.8	3.8	4.6
Absecon Inlet Gardner Basin		0.9	4.1	5.0
Grassy Bay		0.8	3.6	4.4
Main Marsh Thorofare		0.7	3.4	4.1
Brigantine Channel	Form T-Page 4	8.7	3.3 M-26:	18-12(4)1.0
prigguatue (manner		0.8	3•5	4.2

TOPOGRAPHIC MAPPING PROJECT PH-59 (50)

NEW JERSEY COAST, Townsend Inlet to Barnegat City



T-9497-N, T-9497-S to T-9509-N, T-9509-S are Topographic Maps Mapped by the U.S.C. and G.S. from aerial photographs to be taken in 1950 Scale 1:10,000

Topographic map T-9504 is one of 13 similar maps in project Ph-59(50). This project covers the New Jersey coast from Townsend Inlet north to the borough of Barnegat Light. This map was compiled by graphic methods. The field operations preceding compilation included complete field inspection and the determination of numerous elevations for planetable contouring. The compilation was at a scale of 1:10,000. manuscript consists of 2 sheets each 3 3/4' in latitude by $7\frac{1}{2}$ ' in longitude. The entire map was field edited. The map is to be published by the Geological Survey at a scale of 1:24,000 as a standard $7\frac{1}{2}$ topographic quadrangle. The registered copies under T-9504 will include 2 one-half quadrangle cloth-mounted prints at scale 1:10,000 identified as T-9504 N/2 and T-9504 S/2 and one cloth-mounted color print at scale 1:24,000 of the entire quadrangle. Hydrographic information furnished by this Bureau, depth curves and soundings, will be included on the color print.

FIELD INSPECTION REPORT QUADRANGLE T-9504 Project Ph-59

Harry F. Garber, Chief of Party

The field work for this quadrangle, being the last of the season to be completed, was accomplished by various personnel under the direction of Messrs. George E. Varnadoe, Cartographic Engineer, and Joseph K. Wilson, Cartographer. In addition to Page 3, the work was accomplished by the following:

Name and Title	<u>Phase</u>	Date
E. L. Williams Cartographer	Horizontal and Vertical Control Recovery and Identification - Shoreline Inspection	July-Oct. 1950
H. R. Moore Cart. Sur. Aid	Horizontal and Vertical Control Recovery and Identification	Aug. 1950
R. G. Holland Cartographer	¥	June 1950
N. S. Schultz Cartographer	H	Aug. 1950
L. F. Beugnet Cart. Sur. Aid	11	Oct. 1950

2. AREAL FIELD INSPECTION

Four large, shallow bays, numerous coves, reaches, tide water creeks, and the low marsh land bordering these, comprise approximately 65% of the quadrangle.

The mainland, which lies in the northwestern part, is high and well drained. Part of the town of Absecon and two villages, Oceanville and Leeds Point are within the quadrangle. The area is adequately served by hard-surfaced highways and secondary roads. For description of the beach areas (a small portion of Atlantic City and Brigantine) see reports for T-9505 and T-9508.

The photographs were of good quality and no difficulty was encountered in their interpretation.

The field inspection is believed to be complete.

3. HORIZONTAL CONTROL

All known horizontal control stations were searched for and reported on Form 526.

(a) The following intersection stations were established by observing four directions with a Wild T2 theodolite from three triangulation stations using triangulation stations for azimuth:

Radio Mast WMID, 1950 Radio Mast WFFG, 1950 Radio Mast, WBAB, 1950

- (c) Control established by the USED and the NJGCS was used along with that established by the USC&GS. No datum adjustment was made.
 - (e) Stations reported lost are:

Grassy, 1935
Red Beacon, 1935
"D" Absecon Inlet (USED)
Gut (USED)
Ham (USED)
Mon. 1884 (NJGCS)
" 1887 "
" 4852 "
" 10899 "

4. VERTICAL CONTROL

All known vertical control was searched for and reported on Form 685A. Listed are the Bench Marks of third-order or higher accuracy recovered:

Desi	gnation	Agency
C-4 H-8		USC&GS
J-8 Atla		NJGCS
BM 5 Mon.	4 1846	11
n	1847	11
Ħ	1848	11

Des	<u>ignation</u>	Agency
Mor	1. 1849	nuges
11	1886)1
H	4820	11
. #	4821	11
Ħ	4852	11
RV	1840	11
11	1841	tt
Ħ	1842	n
Ħ	1888	11

- (b) 24.6 Miles of differential levels were run with a Wye level to establish supplemental elevations for contouring. The lines originated and closed on bench marks; the greatest error of closure was 0.44 foot. Adjustments were prorated according to the number of instrument set-ups.
 - (c) The first and last level points are 04-1 and 04-60.

5. CONTOURS AND DRAINAGE

The contouring was done by plane-table methods directly on single lens 1:10,000 scale photographs at an interval of ten (10) feet. The highest elevation is in the northwestern part and is 64.0 feet.

6. WOODLAND COVER

Classified in accordance with current instructions.

7. SHORELINE AND ALONG SHORE FEATURES

- (a) The mean high water line on the sandy point on the south end of Brigantine Island at Absecon Inlet is shown as of the date of photography. At this inlet, the strong current and storms make frequent changes in the shoreline. Except for the ocean side of Brigantine Island and for several short stretches of sand beach in the sheltered waters, the shoreline is all apparent.
- (b) At almost all places where the shoreline is apparent, the low water line and the apparent shoreline are synonymous.
- (c) The foreshore is delineated on the photographs accurately where shoal areas bare close to the shore. Where the shoals bare some distance offshore and cover a considerable area, the delineation is approximate and depends to a large extent on interpretation of the photographs.

- (d) There are no bluffs or cliffs.
- (f) The submarine cables as charted are in error. Information obtained from the U.S. Coast Guard telephone section supervisor at 35 S. Annapolis Avenue in Atlantic City, enabled the field inspector to find cable crossings which are not marked as such on the ground.

8. OFFSHORE FEATURES

A group of shell banks in Great Bay were visited during field inspection. Elevations were determined for those above M.H.W. by assuming the elevation of the M.H.W.L. to be 2 feet and from there hand-leveling to the top.

·A group of large piles form a semi-circle about LT. "92". They are very close to the west side of the Inland Waterway channel.

Two very large piles just east of LT. "106" were located by theodolite cuts from triangulation stations.

A single pile off the end of the 44th Street pier in Brigantine extends about 4 feet above M.H.W. and is correct as charted.

Two wrecks in Broad Creek are identified on the photograph. Only two steel rods of the most southerly of these two wrecks are visible above water. The most northerly wreck is awash at M.H.W. These wrecks were very large steel barges and are a hazard to those fishing skiffs propelled by outboard motors which frequent these waters in large number during the summer.

A small wreck just south of LT. "92" is also of steel. It is identified on the photograph.

9. LANDMARKS AND AIDS

(a) A water tank at the south end of Brigantine and a standpipe at the Seaview Country Club are identified on the photographs as landmarks.

Two new landmarks are recommended for charting. They are:

- 1. Radio Mast WMID
- 2. Radio Mast WFPG

For method of location see paragraph 3 - Horizontal Control, this report.

(d) Twenty-nine fixed aids to navigation, which are lights supported by single wooden piles, were located by theodolite cuts from triangulation stations.

Three sets of ranges were located by sextant fixes. These were checked by theodolite cuts from one or more triangulation stations. The azimuth of the ranges were also located by sextant fixes. Each set of ranges consist of (1) a front range which is a wooden triangle with the apex of the triangle down, and (2) a rear range which is a wooden triangle with the apex of the triangle up. The rear ranges are approximately 10 feet high and the front range approximately 5 feet high.

At two places the front range has been destroyed and only the rear range remains. Since this does not constitute a range, no point on range could be located. Sec 1+cm 56

10. BOUNDARIES, MONUMENTS, AND LINES

This will be the subject of a special report to be submitted by Mr. R. L. McGlinchey, Cartographic Survey Aid. Filed in Div. Photogrammetry general files.

11. OTHER CONTROL

Recoverable topographic stations are:

Chy. Tile Roofed House, 1935 Horn, 1935 Incinerator Stack, 1935 Nik, 1935 Oke, 1935 Oyster C&N, 1935

12. OTHER INTERIOR FEATURES

The data for two bridges with skiff clearance only, and which are not listed in the "List of Bridges Over Navigable Waters of the U.S.", are to be found on the photographs.

Roads and buildings were classified in accordance with current instructions.

The Seaview Country Club and Golf Course is located in the quadrangle, and is identified on photograph 50-0-885.

That part of U.S. Highway 30 (N.J. 43) between Absecon and Atlantic City was improved during July and August 1950. The original centerline was held, along which a three-foot wide center island 10 inches high was constructed, and the road was widened 6.3 feet on each side.

* The Rear Range 5 of Lt. 95 was reported destroyed by Field Edit
The range line is not shown on the map manuscript.

Khim

13. GEOGRAPHIC NAMES

This will be the subject of a special report to be submitted by Mr. Merle W. Smith, Cartographic Survey Aid. Filed in Geographic Names Section, Div. of Charles.

14. SPECIAL REPORTS AND SUPPLEMENTAL DATA

In addition to the above-mentioned reports, the field data are listed in transmitting letter dated 24 Nov. 1950. Filed in Div. of Photogram metry.

Submitted by: 24 Nov 1950

George &. Varnadoe George &. Varnadoe Cartographic Engineer

Approved by:

Harry F. Garber Chief of Party

- 12 -

STATION	SOURCE OF INFORMATION (INDEX)	DATUM	LATITUDE OR y-COORDINATE LONGITUDE OR x-COORDINATE	DISTANCE FROM GRID IN FEET. OR PROJECTION LINE IN METERS FORWARD (BACK)	DATUM	N.A. 1927 BISTA FROM GRID OR P IN ME	N.A. 1927 - DATUM BISTANCE FROM GRID OR PROJECTION LINE IN METERS FORWARD	FACTOR DISTANCE FROM GRID OR PROJECTION LINE IN METERS FORWARD (BACK)
ATLANTIC, 1932	G-1447 P.23	N.A. 1927	39 22 57.125 74 25 44.032			1761.7 1053.8	(88.6)	
, BEACHES, 1935 /	G_3121 P.335	=	39 23 29,907 74 26 49,519			922.3 1185.0	(928.0)	
BIG SHAD / (C&N) 1935	G-3126 P.343	=	39 27 35.921 74 23 44.188			1107.8	(742.6)	
BLEV USE,	USE P.13	=	222,234.73			681.2	(842.8)	
BRIGANTINE BEACH WATER TANK (SOUTH OF) 1932	G-1447 P.31	=	39 23 41.95 74 23 28.56			1293.7	(752.3)	
BUM USE, 1946 V	USE P. 14	=	214,589.23			1398.8 554.5	(125.2) (969.5)	
CHANNEL (USE)	G-3126 P.344	=	39 23 38.875 74 23 53.919			1198.9	(651.5)	
CIRCLE, 1932 V	G-1447 P.23	2	39 23 40.859 74 23 23.744			1260.1	(590.3) (867.5)	
COAST GUARD / FLAG TOWER, USE,	USE 424-009	=	39 22 42.91 74 25 24.02			1323.3	(527.0) (861.2)	
DIRTY (C&N) // 1935	G-1326 P-343	€	39 26 05.100 74 22 34.264		3	157.3 819.5	(1693.0)	
FLY, 1931)	G-1346 P.39	2	39 27 02.431 74 27 28.838			75.0	(1775.4)	
		,						13
1 FT. = ,3048006 METER								M . 2388-32

0				0			0
MAP T. 9504		PROJEC	PROJECT NOPh-59(50)	SCALE OF MAP 1:10,000	000,	SCALE FACTOR	JR.
	SOURCE OF INFORMATION (INDEX)	DATUM	LATITUDE OR y-COORDINATE LONGITUDE OR x-COORDINATE	DISTANCE FROM GRID IN FEET. OR PROJECTION LINE IN METERS FORWARD (BACK)	DATUM FROI	N.A. 1927 - DATUM DISTANCE FROM GRID OR PROJECTION LINE IN METERS FORWARD (BACK)	FACTOR DISTANCE FROM GRID OR PROJECTION LINE IN METERS FORWARD (BACK)
KILLER USE 1946	USE P.14	N.A. 1927	2,063,376.60		.9	618.7 (905.3) 1029.2 (494.8)	
KNOLL, 1931	G-1346 P-39	=	39 28 33.600 74 26 20.671		1036.	N	
LEEDS POINT, 1867	G-1447 P-18	п	39 29 01.967 74 26 00.114		60.7	7 (1789.7)	
MAIN, 1935	G-3126 P-334	=	39 29 02.158 74 22 46.518		66.6	6.6 (1783.8) 1111.7 (322.2)	
PASS, 1935	G-3126 P.335	=	39 24 44.424	DESTROYED IN 1952		1370.0 (480.3) 997.0 (438.4)	
SALT (C&N),1935	G-3126 P-343	=	39 23 57.227 74 25 17.512		77	1764.8 (85.5) 419.0 (1016.6)	
SEAVIEW COUNTRY CLUB STACK, 1935	G-3126 P-343	=	39 26 59.152 74 28 29.675		31.	709.5 (725.1)	
SEAVIEW COUNTRY CLUB STANDPIPE	G-3126 P.343	=	39 26 57.998 74 28 30.266		72	1788.6 (61.7) 723.7 (710.9)	
SHACK (C&N), 1935	G-3126 P.343	=	39 25 30.465 74 23 20.476		87 86	939.5 (910.8)	
STEELMAN, 1886	G-1346 P. 39	=	39 25 09.421		29	290.5 (1559.8) 808.8 (626.5)	
STEELMAN 2, 1932	447 P. 19	=	39 25 07.096 74 29 35.343		21	218.8 (1631.5) 845.4 (589.8)	
THEM USE, 1946	USE P.13	8	225,508.50		15	155.0 (1369.0)	
1 FT 3048006 METER COMPUTED BY. J. C. Richter	chter	70	DATE 26 Dec. 1950	CHECKED BY.M.F.Kirk	irk	DATE 12/29/50	/50 М-2388-12

SOURCE OF INFORMATION DATIUM LATITUDE OR V. COORDINATE CINDEX) MJGCS N.A. 216,852,18 2,048,159.34 2,049,193.77 " " 2,054,085,56 223,357.31 2,054,942.23 " " " 2,054,942.23 " " " 2,054,942.23 " " " 2,054,942.23 " " " 2,054,942.23 " " " 2,054,942.23 " " " 2,054,942.23 " " " 2,054,942.23 " " " 2,054,942.23 " " " 2,054,942.23 " " " 2,054,942.23 " " " 2,054,942.24 " " 2,058,000.52	DISTANCE FROM GRID IN FEET. DATUM FROM GRID IN FEET. OR PROJECTION LINE FROM GRID OR PROJECTION LINE IN METERS FORWARD FORWA
NJGCS N.A. 1927 " " " " " " " " " " " " " " " "	
	0 0 7 7 7
	1354.4 (169.6) 1506.4 (17.6) 687.2 (836.8)
	(836.8)
	914.5 (605.4)
n n n	1169.6 (354.4) 953.2 (570.8)
, , , , , , , , , , , , , , , , , , ,	1261.8 (262.2)
п п	1459.0 (65.0)
	8943 (629.7)
MON 1885 / " 201,982.77 NJGCS, 1934 " 2,054,039.19	604.4 (919.60)
MON 1886 / " 201,576.08 NJGCS,,1934 " " 2,055,817.25	480.4 (1043.6)
FT.=.3048006 METER 26 Dec. 1950	M.F.Kirk 29 Dec. 1950

MAP T9504		PROJEC	PROJECT NOPh-59(50)	SCALE OF MAP	222	SCALE FACTOR	TOR
STATION	SOURCE OF INFORMATION (INDEX)	DATUM	LATITUDE OR y-COORDINATE LONGITUDE OR x-COORDINATE	DISTANCE FROM GRID IN FEET. OR PROJECTION LINE IN METERS FORWARD (BACK)	DATUM	N.A. 1927 - DATUM BISTANCE FROM GRID OR PROJECTION LINE IN METERS FORWARD (BACK)	FACTOR DISTANCE NE FROM GRID OR PROJECTION LINE IN WETERS FORWARD (BACK)
MON 4808	NJGCS	N.A.	235,435.65			132.8 (1391. 2)	(2)
-		1927	2,061,090.32			- 1	
MON 4809 NJGCS, 1935	Ε	=!	2,062,097.13			639.2 (884.8)	
MON 4820 /	æ	2	204,630.59			1411.4 (112.6)	
1 🗥	£	=	205,864.25 2,081,011.70			263.4 (1260.6) 308.4 (1215.6)	(9)
MON 7813 NJGCS, 1939	F	=	218,333.64			1016.1 (507.9)	
MON 7814 NJGCS,,1939	z	=	218,185.97			971.1 (552.9) 877.9 (646.1)	
MON 13800 NJGCS, 1940	=	=	198,629,99			1106.4 (417.6)	
RADIO MAST WBAB 1950	Computed	=	39° 22' 37.67" 74 27 21.26			1161.7 (688.6) 508.9 (927.3)	
RADIO MAST WFPG, 1950	`> =	=	39° 22' 34.50 74 27 07.58/			1063.9 (786.4) 181.5 (1254.7)	(†
Sub. Pt. ATLANTIC, 1932	```	=	39 22 74 25			1843.7 (06.6) 1004.9 (431.1)	(
Sub. Pt. BEACHES RM 2,1935	,	= 	39 23 74 26				(2)
Sub Pt BIG SHAD (C&N)1935)	=	39 27 74 23			1091.8 (758.5) 1073.5 (360.9)	(6)
1 FT = 3048006 METER	T C But Dit		10/28/50	35 17 17 18	- 3		17/7/ E

		- - 			, , , , , , , , , , , , , , , , , , ,		
STATION	SOURCE OF INFORMATION (INDEX)	DATUM	LATITUDE OR V-COORDINATE LONGITUDE OR x-COORDINATE	DISTANCE FROM GRID IN FEET, OR PROJECTION LINE IN METERS FORWARD (BACK)	DATUM	N.A. 1927 - DATUM DISTANCE FROM GRID OR PROJECTION LINE IN METERS FORWARD (BACK)	FACTOR DISTANCE FROM GRID OR PROJECTION LINE IN METERS FORWARD (BACK)
Sub Pt							
BUM USE, 1936 V			Plot graphically			-	
Sub Pt	1	=	39 23 74 23			1306 5 (129.2)	
⊸ [ŀ	
FLY , 1931		\$	74 27			640.8 (793.8)	
Sub Pt			39 26			513.8 (1336.5)	
GRASSY RM 2,1935		2				363.3 (1071.6)	
) 			39 29	/		(£ 1/08L) [.97]	
MAIN, 1935		=	74 22			1123.5 (310.4)	
			39 28			(868.0)	
KNOLL, 1931	•	tt.	74 26				
Sub Pt			39 23			1728 3 (122.0)	
SALT (C&N),1935		#	74 25				
Sub Pt SHACK			39 25			(0.018) 6.0401	i
(C&N) 1935		#					
Sub Pt		#	10 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0				
11174 COLO MATIT			rior grainteally				
MON 1844 MJGCS 1934		æ	Flot ensurant				
Sub Pt							
MON 1847 NJGCS 1934		=	Plot graphically				
MON 4832			213.342.11			(6 303) 4 6101	13
NJGCS, 1936 v	NJGCS	2	2,081,908.54			8 (1603	

GRASSY FM 2,	SOURCE OF INFORMATION (INDEX)	DATUM	LATITUDE OR y-COORDINATE LONGITUDE OR x-COORDINATE	DISTANCE FROM GRID IN FEET, OR PROJECTION LINE IN METERS FORWARD (BACK)	DISTANCE FROM GRID IN FEET. OR PROJECTION LINE IN METERS FORWARD (BACK)	N.A. 1927 - DATUM DISTANCE FROM GRID OR PROJECTION LINE IN METERS FORWARD (BACK)	FACTOR DISTANCE FROM GRID OR PROJECTION LINE IN NETERS FORWARD (BACK)
T 7.72		N.A. 1927	39 26 14.877 74 24 14.418			313	
Sub Pt MON 1886 NJGCS, 1934		=	Plot graphically				
		1					
		 - -					
		J —					
	. [
•			•				
				•			
		- <u>-</u> h					
		—. J.					
							8

COMPILATION REPORT T-9504

The radial plot report for this manuscript is submitted as a part of the descriptive report for T-9508.

31. DELINEATION

Manuscript No. T-9504 was delineated by graphic methods.

32. CONTROL

Identification of horizontal control was adequate. See Radial Plot Report for this manuscript, submitted with Descriptive Report for T-9508.

33. SUPPLEMENTAL DATA

Geographic Name Standard, dated January 27, 1951, on Corps of Engineers, Atlantic City, N. J. quadrangle, was furnished by the Washington office.

Road map of Atlantic County, New Jersey.

Photostat Map of Brigantine National Wild Life Refuge.

Special Report of Boundaries, New Jersey.

U. S. C. & G. S. Charts Nos. 826 & 1217 (Landmarks and Aids Report).

34. CONTOURS AND DRAINAGE

No comment.

- 35. SHORELINE AND ALONG SHORE DETAILS
- 55. Shoreline inspection is considered adequate.

The low-water line was delineated from information on the field photographs.

36. OFFSHORE DETAILS

See Field Report, paragraph No. 8.

37. LANDMARKS AND AIDS

Forms 567 for five (5) landmarks and thirty-one (31) non-floating aids to navigation, which appear on the manuscript are submitted with this report. Forms 567, for six (6) non-floating aids are submitted and recommended for deletion. (One new landmark "RADIO MAST WMID", is listed in the field report as being in this survey. It is shown on Survey T-9508).

38. CONTROL FOR FUTURE SURVEYS

Refer to item No. 24 Photogrammetric Flot Report filed in the report for T950g

Forms 524 are submitted for two (2) recoverable topographic Stations established and eight (8) previous stations recovered. Forms 524 are also submitted for eleven (11) stations searched for but not recovered.

Three recoverable topo stations and two azimuth marks for which forms 524 have been prepared in this office, are not listed in paragraph eleven of the field inspection report.

A list of all recoverable topographic stations appear under item 49 of this report.

39. JUNCTIONS

Junction has been made and is in agreement as follows:

to the N with T-9500

to the S with T-9508

to the E with T-9505

and to the W with T-9503

40. HORIZONTAL AND VERTICAL ACCURACY

No comment.

41 thru 45.

Inapplicable.

46. COMPARISON WITH EXISTING MAPS

Survey No. T-9504 has been compared with:

- (1) Corps of Engineers, Atlantic City, New Jersey quadrangle, scale 1:62,500, published 1941.
- (2) U.S.C. & G. S. topographic maps Nos. T-5634(1936), T-5635(1935), T-5636(1936), and T-5637(1935), scale 1:10,000.

47. COMPARISON WITH NAUTICAL CHARTS

Survey Nos. T-9504, has been compared with U.S.C. & G.S. Nautical Charts Nos. 826, scale 1:40,000 published June 1949, corrected to September 4, 1950, and Chart No. 1217, scale 1:80,000, published December 1948, corrected to November 3, 1950.

Items to be applied to nautical charts immediately:

None

Items to carried forward

None

Respectfully submitted

Jacqueline B. Phillips Jacqueline B. Phillips Photogrammetric Aid

Approved and forwarded

Hubert A. Paton Comdr. U.S.C. & G. S. Officer in Charge

48. GEOGRAPHIC NAMES LIST

Absecon Bay
Absecon Boulevard
Absecon Channel
Absecon Creek
Absecon Heights
Absecon Inlet
Atlantic City
Atlantic City Sea Plane Base
Atlantic County
Atlantic Ocean

Beach Thorofare

Big Fish Thorofare

Black Foint

Ronita Tideway.

Boet Island

Brigantine

Brigantine Beach

Brigantine Boulevard

Brigantine Channel

Brigantine National Wildlife Refuge

Broad Creek To S. (B.C. N. decision)

*Broad Creek To N. Trib. Great Bay

Clam Creek
Clam Thorofare
Coast Guard Base
Collins Road
Conover Channel
Conovertown
Cordery Creek
Cordery Thorofare

Doles Point
Doughty Creek
Duck Thorofare

Eagle Bay
East Point Channel
Egg Harbor Township
Emmans M. E. Church (Smithville) (historical site)

Flat Creek Flat Thorofare Lith St. Pier

Galloway Township
Gardner Basin
Golden Hammock Thorofare
Grassy Bay
Great Bay

48. GEOGRAPHIC NAMES LIST (cont'd)

Great Creek Road Great Thorofare Gull Island Thorofare

Hammock Cove

Intracoastal Waterway
Intracoastal Waterway Alternate Route
Jim Leeds Road
Jonathan Thorofare

Lakes Bay
Landing Creek
Leeds Point (settlement)
Lily Lake
Little Bay (to S, near Newfound Thorofore)
*Little Bay To N.
Low Water Thorofore

Main Marsh Creek
Main Marsh Thorofare
Mankiller Bay
Mankiller Island
Mattix Run
Meadow Cut
Middle Thorofare
Moss Mill Road
Mud Creek

N. J. 43 Since Jan, 1953 former M. J. State
N. J. 43 Since Jan, 1953 former M. J. State
N. J. 43 Since Jan, 1953 former M. J. State
N. J. 48 Since Jan, 1953 former M. J. State
N. J. 48 Since Jan, 1953 former M. J. State
N. J. 48 Since Jan, 1953 former M. J. State
N. J. 48 Since Jan, 1953 former M. J. State
N. J. 48 Since Jan, 1953 former M. J. State
N. J. 48 Since Jan, 1953 former M. J. State
N. J. 48 Since Jan, 1953 former M. J. State
N. J. 48 Since Jan, 1953 former M. J. State
N. J. 48 Since Jan, 1953 former M. J. State
N. J. 48 Since Jan, 1953 former M. J. State
N. J. 48 Since Jan, 1953 former M. J. State
N. J. 48 Since Jan, 1953 former M. J. State
N. J. 48 Since Jan, 1953 former M. J. State
N. J. 48 Since Jan, 1953 former M. J. State
N. J. 48 Since Jan, 1953 former M. J. State
N. J. 48 Since Jan, 1953 former M. J. State
N. J. 48 Since Jan, 1953 former M. J. State
New York Avenue

Obes Thorofare
Ocean County
Oceanville
Old Port Road
Oyster Creek Road
Oyster Thorofare

Pennsylvania Reading Seashore Lines
Penrose Canal
Perch Cove
Peter Beach
Pitney Road
Pleasantville
Fleasantville Boulevard
Point Bar Thorofare
Port Republic
Pleasantville
Port Republic
Pleasantville
Port Republic

48. GEOGRAPHIC NAMES LIST (cont'd)

Roundabout Thorofare
Rum Point

Sand Thorofare
Seaview_Country_Club
Seaview_Park
Shad Island
Sheepshank Thorofare
Sloop Thorofare
Smithville
Snug Harbor
Somers Bay
Somers Cove
Stake Thorofare
Steelman Thorofare
Sunflower Island

Turtle Cove

U. S. 9 U. S. 30 U. S. 40 U. S. 322

Venice Park Canal

Wading Thorofare
Weakfish Island
West Atlantic City
Wills Thorofare

Venice Park School (sedge of Verona Avenue

* NOTE: There is a large BROAD CREEK in the center of S/2 and a small BROAD CREEK in the NE section of the N/2. There is a LITTLE BAY in the SE section of N/2 and a LITTLE BAY in the SW section of the S/2.

49. NOTES FOR THE HYDROGRAPHER

The following is a list of the ten (10) recoverable topographic stations shown on the manuscript.

/ATLANTIC AZ MK (1932) 1950

LEEDS POINT AZ MK (1867) 1950

A SUADR (CON 1932) 1970

A SUADR (CON 1932) 1970

ATLANTIC AZ MK (1932) 1950

* LEEDS POINT AZ MK (1867) 1950

6502 & SHARK (C&N - 1935) 1950

C501 a. DOT 1935 (1956)

6503 a. STACK (INCINERATOR-STACK-1935) 1950

6502 & CHIMNEY (CHY. TILE ROOFED HOUSE-1935) 1950

6502 & OYSTER (C. & N.) -1935 (1950)

6502 a. OKE (1935) 1950

6502 a. NIK (1935) 1950

6502 a. NIK (1935) 1950

Note: 1950 geographic position determined by photogrammetric methods differs from previously determined position; therefore, the date, 1950, is retained on the imanuscript. The 1950 position supersedes the previous position

Kh.m.

~

PHOTOGRAMMETRIC OFFICE REVIEW

T. 9504

1. Projection and grids2. Title3. Manuscript numbers4. Manuscript size
CONTROL STATIONS
5. Horizontal control stations of third-order or higher accuracy6. Recoverable horizontal stations of less
than third-order accuracy (topographic stations)7. Photo hydro stations the stations8. Bench marks
9. Plotting of sextant fixes 10. Photogrammetric plot report 11. Detail points
3. Floreing of Sexual 1993 10. Floreing annihilative plot report 11. Detail points
ALONGSHORE AREAS
(Nautical Chart Data)
12. Shoreline13. Low-water line 14. Rocks, shoals, etc 15. Bridges 16. Aids
to navigation 17. Landmarks 18. Other alongshore physical features 19. Other along -
shore cultural features
PHYSICAL FEATURES
20. Water features 21. Natural ground cover 22. Planetable contours 23. Stereoscopic
Instrument contours 10 24. Contours in general 25. Spot elevations 26. Other physical
features
CULTURAL FEATURES
27. Roads 28. Buildings 29. Railroads 30. Other cultural features
27. Noddo 25. Sandings 25. Namodas 250. Other cartain reaters
BOUNDARIES
31. Boundary lines 32. Public land lines
or boundary miceor rubic land mice
MIGOELLANEOUS
MISCELLANEOUS
33. Geographic names 34. Junctions 35. Legibility of the manuscript 36. Discrepancy
overlay 37. Descriptive Report 38. Field inspection photographs 39. Forms
Reviewer Supervisor, Review Section or Unit
41. Remarks (see attached sheet)
FIELD COMPLETION ADDITIONS AND CORRECTIONS TO THE MANUSCRIPT
42. Additions and corrections furnished by the field completion survey have been applied to the manuscript. The
manuscript is now complete except as noted under item 43.
Jacqueline B. Phillips Frank V. Tareza
/ Compiler / Supervisor
43. Remarks: M-2623-12

FIELD EDIT REPORT Quadrangle T-9504 Project Ph-59(50)

Paul Taylor, Chief of Party

The field edit of this quadrangle was accomplished during the months of April and May, 1952.

51. METHODS

The quadrangle was inspected by traversing all passable roads by truck, walking to areas which required special investigation and by skiff along water portions. In addition to visual inspection, standard surveying methods were used for corrections and additions.

All additions, corrections and deletions have been either indicated on the field edit sheets, referenced to the field photographs or answered directly on the discrepancy print. A legend describing the symbols and colored inks used is shown on the field edit sheets.

Two 1:20,000 scale sheets are submitted with the field edit information.

52. ADEQUACY OF COMPILATION

The compilation of this map is considered to be adequate with the exception of the few corrections and additions of the field edit data that are to be applied.

Attention is invited to U. S. Highway 40, U. S. Highway 322 and N. J. Highway 48. N. J. Highway 48 ends at Jonathan Thoroughfare and U. S. Highways 40 and 322 end at the circle in Atlantic City on sheet T-9508. The portion of this highway from Jonathan Thoroughfare east is known as Albany Avenue. The portion west of Jonathan Thoroughfare to the western limits of the City of Pleasantville is known as Verona Avenue, and from the western city limits of Fleasantville west it is known as the Black Horse Pike. The road should be classed Rd. 3 from Atlantic City to the east urban limits of Pleasantville and from there to the project limits as Rd. 1. The information in this paragraph should supersede any other information Verified during review.

K. W. Ja. 6/10/53 shown on quadrangles T-9503 and T-9508.

U. S. Highway 30 is a four-lane heavy-duty road from Absecon to Atlantic City and should be classed as Rd. 1. It has been erroneously shown as Rd. 3 on quadrangle T-9508.

Some changes have been made in the swamp delineation in a few areas. These changes have been shown on field photographs in purple ink and have been referenced on the field edit sheets.

The boundary lines as indicated by dashed red lines on the discrepancy print are considered correct with the two exceptions that whave been crossed out with black ink on the discrepancy print.

The position of the boundary limits on the City of Absecon, which were questioned on the discrepancy print, have recently been changed. The new location is shown on Photograph 50-0-857.

53. MAP ACCURACY

The horizontal positions of the map detail appear to be good. No standard vertical accuracy test was required for this sheet. The contours however were visually checked throughout the quadrangle and were found to adequately depict the terrain.

A few contour corrections were made.

There are no large active borrow pits on this sheet.

54. RECOMMENDATIONS

It was noted on this sheet that contours cross all roads perpendicularly. For all roads, except class seven and trails, this adequately depicts the terrain. In this project, the majority of all class seven roads and trails are natural ground features and are not man-made.

55. EXAMINATION OF PROOF COPY

Mr. Walter Buzby, New Jersey State Highway Engineer, who has been a resident of this area for a number of years, states that he would be willing to examine a proof copy of this quadrangle for possible errors. Mr. Buzby's address is: New Jersey State Highway Department, Main Street, Pleasantville, New Jersey.

56. LANDMARKS AND AIDS

In regards to the range beacons at Lt. 95 as questioned on \checkmark the discrepancy print - one has been removed; they are day beacons and have no name.

Lt. 100 has been moved into the water at Gull Island Thoroughfare. The old light 100 is now "Pile 100" and the new position 🗸 for Lt. 100 is shown on the field edit sheet.

Lt. 2 at Absecon Inlet was also located by planetable and is shown on the field edit sheet. Form 567 is submitted in quadruplicate V with the field edit information.

According to Captain Huber of the New Jersey State Department of Navigation, the front and rear day beacons which are out will not be replaced any time soon.

Lt. 2 at Absecon Inlet will be moved about 50 feet southeast of its present position in the near future, according to Captain Huber.

57. HORIZONTAL CONTROL

Triangulation Station PASS and Topo Station FLAGFOLE were found destroyed. Forms 524 and 526 are submitted with the field edit information.

> 23 May 1952" Submitted by:

Joseph K. Wilson, Cartographer

27 May 1952 .Approved by:

Paul Taylor Lt. Comdr. USC&GS

Chief of Party

Review Report T-9504 Topographic Map 30 June 1953

62. Comparison with Registered Topographic Surveys .-

T-119	1:20,000	1840-41	
T-142	Iţ.	1841	
T-952	1:10,000	1863-64	
T-1166	1:20,000	1869-70	
T-2455	. 11	1899	
T-2694	1:10,000	1904	
T-5634	n -	1932	
т-5635	11	Ħ	
т-5636	n	11	
T-5637	11	17	
T-6501a	Ħ	1935-36	(Planetable)
T-6501b	Ħ	11	Ħ
T-6502a	11	11	11
T-6502b	11	11	72
T-6503a	11	11	17

The north shore of Absecon Inlet and the Brigantine Beach shoreline (T-9504 S) have receded in comparison with the previous surveys. The Brigantine Beach shoreline has receded approximately 50 meters and the sand and marsh point southwest of Brigantine which is the north side of Absecon Inlet has receded as much as 200 meters. The boardwalk fronting Brigantine Beach is no longer in existance. Other minor shoreline differences exist between the previous surveys and T-9504, but with the exception of the above noted changes and additional cultural development the previous surveys (1932, 1935-36) and T-9504 are in good agreement.

T-9504 supersedes all the above surveys in common areas for nautical charting purposes.

63. Comparison with Maps of Other Agencies .-

Atlantic City, N.J., U.S.E. 15' quadrangle, 1:62,500, 1941. Also at scale 1:50,000 with revision of marginal data, 1946 and UTM grid added 1948. AMS.

The boundary line between Atlantic City and Galloway Township in Steelman Thoroughfare and Broad Creek differs on the quadrangle from that shown on T-9504. Natural and cultural changes have occured subsequent to the publication of the quadrangle.

64. Comparison with Contemporary Hydrographic Surveys .- None

65. Comparison with Nautical Charts .-

826, 1:40,000, Intracoastal Waterway, ed. 1951, corr. to 6/9/52.
1217, 1:80,000, ed. 1948, corr. to 2/13/50.

Chart 826 shows Light 1 in Absecon Channel whereas T-9504(S) shows Pile 14A (no lantern) in the same location.

Three of the four ranges N and E of Light 100 shown on

Three of the four ranges N and E of Light 100 shown o Chart 826 are destroyed and not shown on T-9504(S)

The rear range SW of light 95 shown on Chart 826 is destroyed and not shown on T-9504 (S).

Geographic positions of all aids to navigation are listed on the attached forms 557.

Some differences in shoreline occur between the charts and T-9504 particularly in the area of Absecon Inlet and Rum Pt. where several small marsh islands have been formed and the marsh areas have become more extensive.

66. Accuracy of Results and Future Surveys.-This map complies with all instructions and is adequate as a base for hydrographic surveys and the construction of nautical charts. This map complies with the National Map Accuracy Standards.

Reviewed by: M. Makei

Approved by: A Land

Chief, Review Branch
Div. of Phytogrammetry

Chief, Div. of Photogrammetry

Chief, Div. of Photogrammetry

Chief, Div. of Coastal Surveys

Photogrammetry Chief, Div. of Coastal Surveys!

under constructions

felly one next lecine Chiefe while to one inset flowers of heart 1217, met shown one this survey T-9504 Kin.

Form 567 April 1945

DEPARTMENT OF COMMERCE U. S. COAST AND GEODETIC SURVEY

NONFLOATING AIDS ORXEMNEMARKS FOR CHARTS

STRIKE OUT ONE TO BE CHARTED RECYPETATION OF THE PRINTED

Baltimore, Maryland

September

19 52

I recommend that the following objects which have (have-nat) been inspected from seaward to determine their value as landmarks be charted on (delated-strate) the charts indicated.

The	The positions given have been checked after listing	listing by	R. Glaser	Laser			H	Hubert A. Paton	Paton		
										0	Chief of Party.
N Here	New Jersey				POSITION			METHOD		Ĺ	тван:
			4	LATITUDE	LONG	LONGITUDE		LOCATION	DATE		CHARTS
CHARTING	DESCRIPTION	SIGNAL	•	D.M.METERS	•	D.P.METERS	DATUM	súrver T-9504	LOCATION	H ARBO	A2110
* LT.100	Gull Island Thoroughfare		39 24	1193	74 26	168	N.A. 1927	Plane- table	May 1952	×	826
** IT. 2	_		l .		74 25	358	#	E	ħ		826 x 1217
						4					
* *	New position for LT. 100 - former position is now FILE 100 LT 2, will be moved 50 ft SE in near future (See field edited)	osition ar future	1s now	is now FILE 100 (See field edit	- a	report T-9504)					!

This form shall be prepared in accordance with Hydrographic Manual, pages 800 to 804. Positions of charted landmarks and nonfloating aids to navigation, if redetermined, shall be reported on this form. The data should be considered for the charts of the area and not by Iteld survey sheets. Information under each column heading should be given.

U. S. GOVERNMENT PRINTING OPPICE: 1949 O - 853418

Я

Form 567 April 1945

W

DEPARTMENT OF COMMERCE

U. S. COAST AND GEODETIC SURVEY

NONFLOATING AIDS CREATANDMARKS FOR CHARTS

TO BE CHARTED YOUNGER MOREON

STRIKE OUT ONE

September 19 52

I recommend that the following objects which have (NEXEXECK) been inspected from seaward to determine their value as landmarks be charted on factorization the charts indicated.

Baltimore, Maryland

The positions given have been checked after listing by

												Chief of Party.	·.
STATE	New Jersey					POSITION	7		METHOD			тяан	
			_	LATITUPE	UDE.	0,1	LONGITUDE	 	LOCATION	DATE			90
CHARTING	DESCRIPTION	SIGNAL	c	-	D. M. METERS	0	D. P. METERS	N.A.	survey T-9504	7	OSNAH IOHENI	OFFE CTE O	ņ
LT 102	Lantern on File (Middle Thorn)		39	777	54.8	74 26	165	1927	THEOD	1950	×	826	
LT 1	Lantern on File (Broad Creek)	>	39	শ্ব	262	74 25		=	E	=	×	=	
LT 2	Lantern on Pile (Absecon Channel)		39 24	77	183	74 27	130	E	E	=	×	=	
LT JOL	Lantern on Pile (Middle Thorn)		39	77.	3	74 26	213	E	E	=	×	=	-
LT 105	Lantern on Pile (Absecon Channel)		39	23	965	74 25	996	=	E	Ę	Ħ	5	1
LT 106	Lantern on Pile (Absecon Channel)		8	23	840	74 26	8	=	Ħ	=	×	=	
LT 2	Lantern on Pile (Beach Thorofare)		39	23	5%	74 26	1417	E	2	n	×	£=	<u>_</u>
7447-747		į											
													1
													1
						ļ							
											-		l
, T.	This forms about the	17.	∦:],	100							. []

This form shall be prepared in accordance with Hydrographic Manual, pages 800 to 804. Positions of charted landmarks and nonfloating aids to navigation, if redetermined, shall be reported on this form. The data should be considered for the charts of the area and not by 'dividual field survey sheets. Information under each column heading should be given.

U. S. GOVERNMENT PRINTING OFFICE: 1948 O - 853418

9. 5.

DEPARTMENT DE COMMERCE

U. S. COAST AND GEODETIC SURVEY

NONFLOATING AIDS OR CHARTS

STRIKE OUT ONE TO BE CHARTED TOOMER / INFINED

Baltimore, Maryland

19 52 September

I recommend that the following objects which have xaxxaxx been inspected from seaward to determine their value as landmarks be

R. Glaser charted on **deletath formy** the charts indicated.
The nositions given have been checked after listing by

										3	2	Chief of Party.
GTATE	Now Jarsey	 				POSITION	2		METHOD			тяАнз
	Corpo non		<u> </u>	LATI	LATITUDE	9	LONGITUDE		LOCATION	DATE		CHARTS
CHARTING	DESCRIPTION	SIGNAL	•	-	D. M. METERS	•	D.P. METERS	N.A.	SURVEY No.	LOCATION	HENE OHENI	
BEACON	Front Range (SW of LT 95)		8	26	52	74 24	1480	1927	THEOD	1950	×	826
LT 96A	Lantern on Pile		39	25	1394	74 25	802		=	E	×	2
LT 98	Lantern on File		33	25	431	74 25	988	£	E	E	×	=
, ,	Lantern on File (Absecon Channel FL white Light is not red as shown		38	25	प्रा	74 28	1353	#	=	=	×	\$1
LT 99	Lantern on Pile		33	27	1764	74 25	786	P	a		×	#
BEACON	Rear Range (E of LT 99)		38	77	1769	74 25	959	=	=	F	×	=
BEACON	Front Range (S of LT 99)		33	24	1743	74 25	982	=	=	=	×	£
1. T.1	Lantern on Pile (Obes thorofare)			24	1798	74 23	21.7	=	=	=	×	=
BEACON	Rear Range (N of LT 100)		39	24	गुनुष	74 26	32	#	c	E .	×	#
ւր և	Lantern on File (Absecon Channel)		39	24	978	74 28	102	E	E	E	×	
		}							·			-7.
- '												

This form shall be prepared in accordance with Hydrographic Manual, pages 800 to 804. Positions of charted landmarks and nonfloating aids to navigation, if redetermined, shall be reported on this form. The data should be considered for the charts of the area and not by The state of the starvey sheets. Information under each column heading should be given.

U. S. GOVERNMENT PRINTING OFFICE: 1948 O - 853/18

w of

Form 567 April 1945

DEPARTMENT OF COMMERCE

U. S. COAST AND GEODETIC SURVEY

NONFLOATING AIDS ORX TANDEMARKS FOR CHARTS

STRIKE OUT ONE TO BE CHARTED TOMBENDEWERKED

Baltimore, Maryland

September

Chief of Party. I recommend that the following objects which have (historian) been inspected from seaward to determine their value as landmarks be Hubert A. Faton R. Glaser The positions given have been checked after listing by charted on (specializations) the charts indicated.

07.470								METHOD		_	12
1	new Jersey			LATITUDE	9	LONGITUDE		LOCATION		OB CH	CHARTS AFFECTED
CHARTÍNG NAME	DESCRIPTION	SIGNAL	•	D. M. METERS	0	D. P. METERS	N.A.	SOURVEN	LOCATION		
LT 82	Lantern on Pile		39 29) 1682	74 22	1277	1927	THEOD	1950	×	826
17 84	Lantern on Pile		39 29	5 743	74 22	1367	1927	=	1950	×	826
DAY	(Daymark Rear range) Main Marsh Thorofare		39 28	3 1055	74 23	175	1927	=	1950	K .	826
LT :88	Lantern on Pile		39 28	3 768	74 23	386	1927	5	1950	K	826
LT 90	Lantern on File		39 27	7 1769	74 23	1011	1927	=	1950	×	928
LT 92	Lantern on File		39 27	7 1006	74 23	939	1927	=	1950	×	826
LF 93	Lantern on File		39 26	5 1052	74 23	713	1927	=	1950	×	826
LT 8	Lantern on Pile		39 26	5 235	74 22	1188	1927	2	1950	_ ×	826
BEACON	Rear Range (N of LT 96)		39 26	5 328	74 24	1082	1927	=	1950	×	826
BEACON	Front Range (N of LT 96)		39 26	5 230	74 24	1153	1927	=	1950	×	826
LT 96	Lantern on Pile		39 26	5 186	74 24	1188	1927	=	1950	×	826
LT 95	Lantern on File		39 26	5 128	74 24	380	1927	=	1950		826
					٠						

This form shall be prepared in accordance with Hydrographic Manual, pages 800 to 804. Positions of charted landmarks and nonfloating aids to navigation, if redetermined, shall be reported on this form. The data should be considered for the charts of the area and not by ividual field survey sheets. Information under each column heading should be given.

U. S. GOVERNMENT PRINTING OFFICE: 1949 O - 853418

Form 567 April 1945

DEPARTMENT OF COMMERCE

U. S. COAST AND GEODETIC SURVEY

NAUTICAL CHART BRANCH

MONTEACHTENGRADES OF LANDMARKS FOR CHARTS

BTRIKE OUT ONE TO BE CHARTED TOUGHT WEEK EVER

Baltimore, Maryland

Sept.

1952

H. A. Iaton

I recommend that the following objects which bases (have not) been inspected from seaward to determine their value as landmarks be charted on (distantistions) the charts indicated.

R. Glaser The positions given have been checked after listing by

CHARTS APFECTED Chief of Party. 1217 826 1217 1217 121.7 826 121.7 826 OLEZHOBE CHYEL H H × M H INSHORE CHART Ħ H H × THARD HOBRAH LOCATION 1935 1950 1933 1933 2935 2935 1950 DATE P METHOD OF LOCATION AND SURVEY TRI Photo. T-9501 TH THI 댎 Plot DATUM 1927 1927 1927 1927 1927 D. P. METERS 181.5 508.9 723.7 683.4 353 LONGITUDE POSITION 23 56 28 27 27 0 7 7 77 77 17 D. M. METERS 1063.9 1788.6 1293.7 1161.7 98 LATITUDE 23 56 22 22 22 0 33 33 33 33 SIGNAL NAME of) Elev. Brigantine Beach W.T. (S Incinerator stack, 125' high Radio Mast WRAB 1950 Skeleton Steel, ht = 340(343) STANDFIPE Seaview Country Club, 1935
RADIO Radio Mast WFFG 1950 Ht * 125 (132) DESCRIPTION Steel ht-420 (428) New.Jersey 1932 CHARTING NAME STACK RAIII O TOWER STATE MAST TANK

Positions of charted landmarks and nonfloating aids to navigation, if redetermined, shall be reported on this form. The data should be considered for the charts of the area and not by This form shall be prepared in accordance with Hydrographic Manual, pages 800 to 804.

بر ها

Form **567** April 1945

DEPARTMENT OF COMMERCE

U. S. COAST AND GEODETIC SURVEY

NONFLOATING AIDS ORNIVANDMANRINGAROR CHARTS

TXXXEEXCHANNEDX TO BE DELETED

STRIKE OUT ONE

Baltimore, Maryland

September

1952

I recommend that the following objects which have (hereaved) been inspected from seaward to determine their value as landmarks be obsertad now (deleted from) the charts indicated.

R. Glaser The positions given have been checked after listing by

H. A. Paton

Chief of Party.

STATE	Non Towns			14.	POSITION			METHOD	L		тнано	
	New Serect		LATIN	LATITUDE	LONG	LONGITUDE		LOCATION				CHARTS
CHARTING	DESCRIPTION	SIGNAL		D, M, METERS	-	D. P. METERS	DATUM	SURVEY No.	LOCATION	HANBI)
BEACON	Front Range N of LT 100 (destroyed)	1	39 24		74 26					×	826	9
BEACON	Front Range E of LT 100 (destroyed)	,	39 24		74 25		-			×	82	826
BEACON	Rear Range B of LT 100 (destroyed)	1	39 24		74 25					X	82	826
17 1	Absecon Channel File (no tenterna) No. 14A is at this position	1	39 23		74 27					K	8	826
BEACON	Rear Range (SW of LT 95)		39 26		74 24					M	80	826
* 11 100	Lantern on File		39 24		74 26					×	8	826
٠						- 					· 	
												1
								,				
*	LT has been repositioned - former	position :	1s now FILE	TE 100								
			,		-		-					

Hydrographic Manual, pages 800 to 804. Positions of charted landmarks and nonfloating form. The data should be considered for the charts of the area and not by inver-

History of Hydrographic Information Quadrangle T-9504

Hydrography was applied to the manuscript of this quadrangle in accordance with Division of Photogrammetry general specifications dated 18 May 1949.

Depth curves and soundings at mean low water datum originate with the following surveys:

Hydrographic	Survey	н-5893	(1935)	1:10,000
91	11	н-6144	(1936)	1:10,000
11	11	H-6213	(1936)	1:10,000
77	Ħ	H-6214	(1935,6,7)	1:5,000
?!	77	H-6230	(1936.7)	1:10.000

USC&GS Nautical Chart 826, 1:40,000, latest print date 9/7/53
USC&GS Nautical Chart 1217, Inset at 1:20,000 on Absecon Inlet, latest print date 2/16/53

Single-lens 1:10,000 scale photographs taken with the "O" camera in April 1950, numbers 855-862, 885-889, 897-902, and 927-931 were used in conjunction with the above listed hydrographic surveys and charts for the interpretation of the mean low water line and the determination of channels subject to constant changes.

Hydrography was compiled by K. N. Maki and verified by O. Svendsen.

K. N. Maki

Div. of Photogrammetry

2 November 1953

NAUTICAL CHARTS BRANCH



SURVEY NO. 7-9504

Record of Application to Charts

DATE	CHART	CARTOGRAPHER	REMARKS
7-53	1216	Henderson	Refere After Verification and Review applied
			Before After Verification and Review
			Before After Verification and Review
	l. =]	Before After Verification and Review
			Before After Verification and Review
			Before After Verification and Review
			Before After Verification and Review
			Before After Verification and Review
			Before After Verification and Review
			Before After Verification and Review

M-2168-1

A basic hydrographic or topographic survey supersedes all information of like nature on the uncorrected chart. Give reasons for deviations, if any, from recommendations made under "Comparison with Charts" in the Review.