

Original

TP-00448

TP-00448

NOAA FORM 76-35	
U.S. DEPARTMENT OF COMMERCE NATIONAL OCEANIC AND ATMOSPHERIC ADMINISTRATION NATIONAL OCEAN SURVEY	
DESCRIPTIVE REPORT	
Type of Survey ...Coastal Boundary.....	
Job No. ...PH-7119.....	Map No. ...TP-00448....
Classification No. Final	Edition No. ...1.....
Field Edited Map	
LOCALITY	
State ...Florida.....	
General Locality ...Monroe County.....	
Locality ...Main Key to.....	
.....Rattle Snake Key.....	
<hr/> 19 72 TO 19 75 <hr/>	
REGISTRY IN ARCHIVES	
DATE .....	

NOAA FORM 76-36A (3-72)		U. S. DEPARTMENT OF COMMERCE NATIONAL OCEANIC AND ATMOSPHERIC ADMIN.					
<b>DESCRIPTIVE REPORT - DATA RECORD</b>		<table border="1" style="width:100%; border-collapse: collapse;"> <tr> <td style="width:50%;">           TYPE OF SURVEY  <input checked="" type="checkbox"/> ORIGINAL  <input type="checkbox"/> RESURVEY  <input type="checkbox"/> REVISED         </td> <td style="width:50%;">           SURVEY TP-00448             MAP EDITION NO. (1)             MAP CLASS Final             JOB PH-7119         </td> </tr> </table>		TYPE OF SURVEY <input checked="" type="checkbox"/> ORIGINAL <input type="checkbox"/> RESURVEY <input type="checkbox"/> REVISED	SURVEY TP-00448  MAP EDITION NO. (1)  MAP CLASS Final  JOB PH-7119		
TYPE OF SURVEY <input checked="" type="checkbox"/> ORIGINAL <input type="checkbox"/> RESURVEY <input type="checkbox"/> REVISED	SURVEY TP-00448  MAP EDITION NO. (1)  MAP CLASS Final  JOB PH-7119						
PHOTOGRAMMETRIC OFFICE  Rockville, Maryland		<table border="1" style="width:100%; border-collapse: collapse;"> <tr> <td colspan="2" style="text-align: center;"> <b>LAST PRECEDING MAP EDITION</b> </td> </tr> <tr> <td style="width:50%;">           TYPE OF SURVEY  <input type="checkbox"/> ORIGINAL  <input type="checkbox"/> RESURVEY  <input type="checkbox"/> REVISED         </td> <td style="width:50%;">           JOB PH-            MAP CLASS            SURVEY DATES:            19__ TO 19__         </td> </tr> </table>		<b>LAST PRECEDING MAP EDITION</b>		TYPE OF SURVEY <input type="checkbox"/> ORIGINAL <input type="checkbox"/> RESURVEY <input type="checkbox"/> REVISED	JOB PH- MAP CLASS SURVEY DATES: 19__ TO 19__
<b>LAST PRECEDING MAP EDITION</b>							
TYPE OF SURVEY <input type="checkbox"/> ORIGINAL <input type="checkbox"/> RESURVEY <input type="checkbox"/> REVISED	JOB PH- MAP CLASS SURVEY DATES: 19__ TO 19__						
OFFICER-IN-CHARGE  * Commander James Collins							
<b>I. INSTRUCTIONS DATED</b>							
<b>1. OFFICE</b>		<b>2. FIELD</b>					
General-Instructions-OFFICE-NOS Cooperative Coastal Boundary Mapping, Job PH-7000, June 19, 1973 OFFICE-Supplement 1, August 19, 1973 NOTE: Office and Field Edit Instructions (1973) incorporate applicable prior operational instructions. OFFICE-Supplement II, Sept. 24, 1973		Aerial photography 9/2/69 Supplement I, 1/28/70 Supplement II, 3/26/70 Supplement III, 8/10/72 Field Edit (PH-7000, General Instructions for Florida Coastal Zone Mapping) 1973					
<b>II. DATUMS</b>							
<b>1. HORIZONTAL:</b>		<b>OTHER (Specify)</b>					
<input checked="" type="checkbox"/> 1927 NORTH AMERICAN							
<b>2. VERTICAL:</b>		<b>OTHER (Specify)</b>					
<input checked="" type="checkbox"/> MEAN HIGH-WATER <input type="checkbox"/> MEAN LOW-WATER <input type="checkbox"/> MEAN LOWER LOW-WATER <input type="checkbox"/> MEAN SEA LEVEL		Mean water level Refer 76-36 B-1: Remarks					
<b>3. MAP PROJECTION</b>  Traverse Mercator		<b>4. GRID(S)</b>					
<b>5. SCALE</b>  1:10,000		<table border="1" style="width:100%; border-collapse: collapse;"> <tr> <td style="width:50%;">           STATE            Florida         </td> <td style="width:50%;">           ZONE            East         </td> </tr> <tr> <td>           STATE         </td> <td>           ZONE         </td> </tr> </table>		STATE Florida	ZONE East	STATE	ZONE
STATE Florida	ZONE East						
STATE	ZONE						
<b>III. HISTORY OF OFFICE OPERATIONS</b>							
<b>OPERATIONS</b>		<b>NAME</b>	<b>DATE</b>				
<b>1. AEROTRIANGULATION</b> METHOD: Analytic LANDMARKS AND AIDS BY		V. McNeel	6/74				
<b>2. CONTROL AND BRIDGE POINTS</b> METHOD: Calcom PLOTTED BY CHECKED BY		R. Robertson Inapplicable	2/75				
<b>3. STEREOSCOPIC INSTRUMENT COMPILATION</b> INSTRUMENT: SCALE: PLANIMETRY BY CHECKED BY CONTOURS BY CHECKED BY		Inapplicable Inapplicable					
<b>4. MANUSCRIPT DELINEATION</b> METHOD: Graphic SCALE: 1:10,000 PLANIMETRY BY CHECKED BY CONTOURS BY CHECKED BY HYDRO SUPPORT DATA BY CHECKED BY		P. Gibson C. Lewis Inapplicable Inapplicable	4/75 4/75				
<b>5. OFFICE INSPECTION PRIOR TO FIELD EDIT</b> BY		J. Battley - D. Brant	4/75				
<b>6. APPLICATION OF FIELD EDIT DATA</b> BY CHECKED BY		J. McClure C. Lewis	11/75 11/75				
<b>7. COMPILATION SECTION REVIEW</b> BY		J. Battley	12/75				
<b>8. FINAL REVIEW</b> BY		D. Brant	6/76				
<b>9. DATA FORWARDED TO PHOTOGRAMMETRIC BRANCH</b> BY							
<b>10. DATA EXAMINED IN PHOTOGRAMMETRIC BRANCH</b> BY		D. Brant	7/76				
<b>11. MAP REGISTERED - COASTAL SURVEY SECTION</b> BY		R.T. CATOR	9/76				

NOAA FORM 76-36B  
(3-72)U. S. DEPARTMENT OF COMMERCE  
NATIONAL OCEANIC AND ATMOSPHERIC ADMINISTRATION  
NATIONAL OCEAN SURVEY

TP-00448

## COMPILATION SOURCES

## I. COMPILATION PHOTOGRAPHY

CAMERA(S) Wild RC-8 E, K,L Cameras		TYPES OF PHOTOGRAPHY LEGEND		TIME REFERENCE	
TIDE STAGE REFERENCE <input type="checkbox"/> PREDICTED TIDES <input type="checkbox"/> REFERENCE STATION RECORDS <input checked="" type="checkbox"/> TIDE CONTROLLED PHOTOGRAPHY		(C) COLOR <u>IR</u> (P) PANCHROMATIC (I) INFERRED <u>B&amp;W</u>		ZONE <u>Eastern</u> MERIDIAN <u>75th</u>	
				<input checked="" type="checkbox"/> STANDARD <input type="checkbox"/> DAYLIGHT	

NUMBER AND TYPE	DATE	TIME	SCALE	STAGE OF TIDE
72E(C) 509	2/14/72	1230	1:30,000	The stage of tide is inapplicable for the color photography.
73L(C) 2959R-2960R	3/18/73	1042	1:40,000	
73L(C) 2911R-2917R	3/18/73	0945	1:20,000	
72K6318R	2/14/72	1243	1:30,000	Refer to NOAA Form 76 B1
72K6552R-6555R	2/20/72	0933	1:30,000	
72K6343R-6345R	2/14/72	1340	1:30,000	
72K6368R-6369R	2/14/72	1406	1:30,000	
72K6513R-6515R	2/16/72	1107	1:20,000	
72K6253R-6255R	2/12/72	1112	1:30,000	

REMARKS

## 2. SOURCE OF MEAN HIGH-WATER LINE:

The source of the MHW and the MWL links is the black-and-white, tide-coordinated infrared photography listed under item 1. The shoreline on this map is symbolized with the MHW symbol except for the shoreline along Blackwater Sound and Lake Surprise that is symbolized with the MWL symbol. Refer to NOAA Form 76-36 B 1 "Remarks" for explanation the MWL datum.

Where the line is obscured by vegetation, the apparent shoreline was mapped.

## 3. SOURCE OF MEAN LOW-WATER OR MEAN LOWER LOW-WATER LINE:

The source of the MLW line is the tide-coordinated, black-and-white infrared photography listed under item 1.

## 4. CONTEMPORARY HYDROGRAPHIC SURVEYS (List only those surveys that are sources for photogrammetric survey information.)

SURVEY NUMBER	DATE(S)	SURVEY COPY USED	SURVEY NUMBER	DATE(S)	SURVEY COPY USED
Inapplicable					

## 5. FINAL JUNCTIONS

NORTH	EAST	SOUTH	WEST
TP-00446	TP-00449	TP-00451	TP-00447

REMARKS

Final junctions were made in the Coastal Mapping Section.

NOAA FORM 76-36B(1)  
(7-75)U. S. DEPARTMENT OF COMMERCE  
NATIONAL OCEANIC AND ATMOSPHERIC ADMINISTRATION  
NATIONAL OCEAN SURVEY

## TIDE - COORDINATED PHOTOGRAPHY

TP - 00448

LOCATION AND PHOTOGRAPHY	TIDE STATIONS (In operation at time of photography)	STAGE OF TIDE	MEAN RANGE
<u>ATLANTIC OCEAN</u> 72K5513R-6515R	Ocean Reef	-0.04MHW	At tide station 2.33
72K6343R-6345R	" "	+0.03MLW	
72K6368R-6370R	" "	+0.09MLW	
<u>BARNES SOUND</u>			
72K6318R	Basin Hills	+0.29MHW	0.43
72K6513R-6515R	" "	-0.22MHW	
72K6554R-6555R	" "	+0.15MLW	
72K6253R-6255R	" "	+0.66MLW	
<u>BLACKWATER SOUND</u>			
72K6319R-6320R	Barnes Sound	+0.31MWL	- - -
72K6369R-6370R	" "	+0.03MWL	- - -

**REMARKS:** The periodic tide on TP-00448 (Blackwater Sound) was masked by non-tidal forces and the mean range was substantially less than two-tenths of a foot. In this situation the mean high/low water datums converge, and for mapping purposes, the mean high and low water lines are indistinguishable. As a consequence, special treatment was given to the portrayal of the shoreline on this map: the mean water level line was mapped in lieu of the mean high water line and shown by a distinctive symbol.

NOAA FORM 76-36D  
(3-72)U. S. DEPARTMENT OF COMMERCE  
NATIONAL OCEANIC AND ATMOSPHERIC ADMINISTRATION

## RECORD OF SURVEY USE

TP-00448

## I. MANUSCRIPT COPIES

COMPILATION STAGES			DATE MANUSCRIPT FORWARDED	
DATA COMPILED	DATE	REMARKS	MARINE CHARTS	HYDRO SUPPORT
No map copies of TP-00448 were furnished to Marine Chart Division prior to final review.				
			9/9/76	

## II. LANDMARKS AND AIDS TO NAVIGATION

## 1. REPORTS TO MARINE CHART DIVISION, NAUTICAL DATA BRANCH

NUMBER	CHART LETTER NUMBER ASSIGNED	DATE FORWARDED	REMARKS
		1/27/76	Two (2) digitized Forms 76-40 were submitted to Marine Chart Division as final report.

2. ☒ REPORT TO MARINE CHART DIVISION, COAST PILOT BRANCH. DATE FORWARDED: 1/27/763. ☐ REPORT TO AERONAUTICAL CHART DIVISION, AERONAUTICAL DATA SECTION. DATE FORWARDED: \_\_\_\_\_

## III. FEDERAL RECORDS CENTER DATA

1. ☐ BRIDGING PHOTOGRAPHS; ☒ DUPLICATE BRIDGING REPORT; ☒ COMPUTER READOUTS.  
 2. ☒ CONTROL STATION IDENTIFICATION CARDS; ☒ FORM NOS 567 SUBMITTED BY FIELD PARTIES.  
 3. ☒ SOURCE DATA (except for Geographic Names Report) AS LISTED IN SECTION II, NOAA FORM 76-36C.  
 ACCOUNT FOR EXCEPTIONS:

4. ☐ DATA TO FEDERAL RECORDS CENTER. DATE FORWARDED: \_\_\_\_\_

## IV. SURVEY EDITIONS (This section shall be completed each time a new map edition is registered)

SECOND EDITION	SURVEY NUMBER TP - _____ (2)	JOB NUMBER PH - _____	TYPE OF SURVEY <input type="checkbox"/> REVISED <input type="checkbox"/> RESURVEY  MAP CLASS <input type="checkbox"/> II. <input type="checkbox"/> III. <input type="checkbox"/> IV. <input type="checkbox"/> V. <input type="checkbox"/> FINAL
	DATE OF PHOTOGRAPHY	DATE OF FIELD EDIT	
THIRD EDITION	SURVEY NUMBER TP - _____ (3)	JOB NUMBER PH - _____	TYPE OF SURVEY <input type="checkbox"/> REVISED <input type="checkbox"/> RESURVEY  MAP CLASS <input type="checkbox"/> II. <input type="checkbox"/> III. <input type="checkbox"/> IV. <input type="checkbox"/> V. <input type="checkbox"/> FINAL
	DATE OF PHOTOGRAPHY	DATE OF FIELD EDIT	
FOURTH EDITION	SURVEY NUMBER TP - _____ (4)	JOB NUMBER PH - _____	TYPE OF SURVEY <input type="checkbox"/> REVISED <input type="checkbox"/> RESURVEY  MAP CLASS <input type="checkbox"/> II. <input type="checkbox"/> III. <input type="checkbox"/> IV. <input type="checkbox"/> V. <input type="checkbox"/> FINAL
	DATE OF PHOTOGRAPHY	DATE OF FIELD EDIT	

ESSA FORM 76-36c  
(2-70)U.S. DEPARTMENT OF COMMERCE  
ENVIRONMENTAL SCIENCE SERVICES ADMINISTRATION  
COAST AND GEODETIC SURVEY

TP-00448

## HISTORY OF FIELD OPERATIONS

I. ☒ FIELD INSPECTION OPERATION Feb. 1972 ☒ FIELD EDIT OPERATION July 1975  
Mar.

OPERATION	NAME	DATE
1. CHIEF OF FIELD PARTY	R.R. Wagner	
2. HORIZONTAL CONTROL	RECOVERED BY R.R. Wagner ESTABLISHED BY Inapplicable PRE-MARKED OR IDENTIFIED BY Inapplicable	7/75
3. VERTICAL CONTROL	RECOVERED BY R.R. Wagner ESTABLISHED BY Inapplicable XXXXXXXXXXXX IDENTIFIED BY R.R. Wagner	7/75
4. LANDMARKS AND AIDS TO NAVIGATION	RECOVERED (Triangulation Stations) BY Inapplicable LOCATED (Field Methods) BY R.R. Wagner IDENTIFIED BY R.R. Wagner	7/75
5. GEOGRAPHIC NAMES INVESTIGATION	TYPE OF INVESTIGATION <input type="checkbox"/> COMPLETE <input type="checkbox"/> SPECIFIC NAMES ONLY <input checked="" type="checkbox"/> NO INVESTIGATION	
6. PHOTO INSPECTION	CLARIFICATION OF DETAILS BY R.R. Wagner	7/75
7. BOUNDARIES AND LIMITS	SURVEYED OR IDENTIFIED BY Inapplicable	

## II. SOURCE DATA

1. HORIZONTAL CONTROL IDENTIFIED		2. VERTICAL CONTROL IDENTIFIED	
PHOTO NUMBER	STATION NAME	PHOTO NUMBER	STATION DESIGNATION
	Refer to Field Reports	73L2960R 73L2917R 73L2915R 73L2914R	N 274 R 274, Z 316, Tidal BM1 E 275 F 275

3. PHOTO NUMBERS (Clarification of details)  
72K6343, 6344, 6513; 73L2912R, 2914R thru 2917R, 2960R

## 4. LANDMARKS AND AIDS TO NAVIGATION IDENTIFIED

PHOTO NUMBER	OBJECT NAME	PHOTO NUMBER	OBJECT NAME
73L2916R 73L2917R	Jewfish Cr. Daybn. 32 Jewfish Cr. Daybn. 34	73L2917R 73L2917R	Tower Tower

5. GEOGRAPHIC NAMES: ☐ REPORT ☒ NONE6. BOUNDARY AND LIMITS: ☐ REPORT ☒ NONE

## 7. SUPPLEMENTAL MAPS AND PLANS

None

## 8. OTHER FIELD RECORDS (Sketch books, etc. DO NOT list data submitted to the Geodesy Division)

Sketch Book Pages  
Refer to Field Reports bound in this Descriptive Report.

SUMMARY  
for  
TP-00444 thru TP-00454

Coastal Zone Map TP-00448 is one of eleven (11), 1:10,000 scale (shoreline type) maps in Job PH-7119. These maps will not be published. Interior detail is limited to a narrow zone of planimetry usually back to and including the first road.

A layout of Job PH-7119 (revised since the aerotriangulation operation) will show the location of the individual maps. A copy of this layout is included in this Descriptive Report.

The maps are intended for planning purposes for the State of Florida and for the construction and maintenance of NOS nautical charts.

The area is covered by aerial photography taken in 1972 and 1973 on color and black-and-white infrared film. The infrared film was tide coordinated.

The field operations consisted of the following:

1. Premarking of horizontal control for aerotriangulation.
2. Establishment of tidal datums.
3. Field Edit.

Horizontal control was extended by analytical aerotriangulation method using the STK stereocomparator.

The shoreline and alongshore details were compiled from tide-coordinated, black-and-white infrared photography using a B-8 stereoplotter and/or graphic methods. The rectified color photography was used as an aid in interpreting cultural features and compiling the limits of vegetation. The interior details were compiled from a stereoscopic examination of the color photography without field edit.

All line work is scribed, approved symbols are shown in the marginal data of the map.

A registration copy of each map is prepared. The registration copy shows additional offshore details such as shoal and

shallow lines used by the Marine Chart Division but not required on the Coastal Zone Maps. This copy of the map is labeled "Registration Copy" in the title block.


The following items will be registered in the NOS Archives:

1. A stable base copy of the Registration Copy.
2. The Descriptive Report.

The negative of the Registration Copy is filed in the Reproduction Division.

Field records such as field edit sheets, discrepancy prints, field edit photographs, and other field records are filed in the National Archives.





# Official Mileage for Cost Accounts

Sheet No.	Sq. Miles
TP-00444	2
TP-00445	8
TP-00446	6
TP-00447	10
<u>TP-00448</u>	8
TP-00449	2
TP-00450	8
TP-00451	4
TP-00452	4
TP-00453	6
TP-00454	5

Total 63

JOB PH-7119  
CARD SOUND to PLANTATION KEY  
FLORIDA  
SHORELINE MAPPING  
SCALE 1:10000

REVISED 12/9/75 RWW

80°



## FIELD REPORT

JOB PH-7119

This report is on work done in accordance with Instructions-field-Job PH-7119; Horizontal Control for Aerotriangulation and Field Support for Aerial Photography; Coastal Boundary Mapping, Card Sound to Plantation Key, Florida. The field work was done during the period 20 July - 7 September 1971.

1. PREMARKING OF CONTROL

One control station, IRVING 1971, was established on Soldier Key. Eighteen stations were paneled for 1:30,000 scale photography. The deviations from the job diagram and target specifications were recommended in the field by Mr. Saperstein, Photogrammetrist and authorized by the Chief, Surveys Planning Branch. The locations of the paneled stations are shown on the chart section accompanying this report.

2. BRIDGING PHOTOGRAPHY

Flight lines are shown on the accompanying chart. Bridging photography was accomplished on March 8, 1971 for lines 30-4, 30-5, and 30-6 under Job PH-7113. Line 30-6 was redesignated 30-1 for Job PH-7119. Line 20-1 was photographed on Aug. 4 and all other lines on Aug. 11 - the only suitable day in the period 4-26 August. This photography was unacceptable and will be rescheduled for February 1972.

3. TIDE-COORDINATED PHOTOGRAPHY

Locations of the tide staffs are shown on the accompanying chart. Lines 30-4 and 30-5 carried over from Job PH-7113 were completed. Lines 20-2 and 30-3 (Outside) were also completed. Clouds throughout the period prevented completing all lines and the job except for 30-4 and 30-5 will be rescheduled for February 1972. The times are summarized below in case the pictures will be used to supplement the future February work.

Recordings entered in the tide volumes, Form 277, were at 5 minute intervals during photography and at 15 minute intervals near photography. Tolerances of  $\pm 0.3$  ft. for MHW and  $\pm 0.1$  ft. for MLW were observed. Wet staff readings - crest, mean, and trough - were recorded while photography was in progress. Eastern Standard Time was used.

Line 30-4. Flown for MHW on March 2, 1971 at 1319-1325 when both MIAMI BISCAYNE BAY and CUTLER were in range. The north end

was flown for MLW at 1325-1335 on August 6 when the MIAMI BISCAYNE BAY staff read 2.3 and 2.2. The south end was flown for MLW at 1425-1435 on August 6 when the CUTLER staff read 2.75 and 2.69.

Line 30-5. MHW North half flown at 805-815 on August 7 when CUTLER staff read 4.5 to 4.7. South half flown at 1220-1235 on August 7 when the TURKEY POINT staff read 3.15 to 3.05. MLW North half was flown at 1430-1435 on 6 August when the CUTLER staff read 2.73 to 2.69. South half flown at 850-855 on August 11 when the TURKEY POINT staff read 1.65. This was flown at a reduced altitude of 14,000 feet to get under some clouds. A triplicate was flown at 855-900 to get outlying islands which might not have been covered at the reduced altitude.

Line 20-2. MHW The northern two-thirds were flown at 802-815 on August 9 when the OCEAN REEF staff read 4.58 to 4.70. The remainder was flown at 830-840 on August 10 when the staff read 4.25 to 4.35. MLW Due to clouds this was flown in three parts. The NE end to the Ocean Reef Club was flown at 1328-1342 on August 7 when the staff read 2.25 to 2.11, the NE end was flown at 1530 on August 6 when the staff read 2.2, and the south part flown at 955-1001 on 16 August when the staff read 2.30.

Line 30-3 (Outside) MHW Flown at 939-947 on August 11 when the TAVERNIER HAWK CHANNEL staff read 4.00 to 4.12, MLW Flown at 1315-1322 on August 4 when the staff read 2.1.

Line 30-3 (Inside) No photography. Clouds and seasonal high tides during the rest of the period prevented it.

Line 20-1. MHW No photography. MLW Line was flown at 927-945 on August 16 when the RAGGED KEYS staff read 1.8 to 1.75.

Line 30-1. MHW The middle third was flown at 1020-1025 on August 4 when the CARD SOUND staff read 3.7 and the MANATEE CREEK staff read 3.5. The remainder was flown at 1110-1115 the same day when the CARD SOUND staff read 3.6 and the MANATEE CREEK staff read 3.5. MLW No photography.

Line 30-2. Line was flown at 835-842 on August 9 when the CARD Sound staff read 3.6 and the MANATEE CREEK staff read 3.75. Line was unacceptable because of clouds in the middle segment and possible smoke in the northern third. This and the MLW photography were not accomplished due to clouds and seasonal high water.

#### 4. ADDITIONAL PHOTOGRAPHY

Tide coordinated photography was taken on a small shoal about one

mile NNE of the Molasses Reef light. The shoal was photographed at about 0900 on August 10 when the TAVERNIER HAWK CHANNEL staff was in MHW range. It was flown at 1206 on August 16 when the staff read 2.31. This shoal was also photographed in color and false color, but the times were not obtained from the photographer.

#### 5. FORESHORE PROFILES

Four planetable beach profiles were run within the limits of the job by Mr. Dale Fuller during the photography period. A brief report accompanies the profile sheet.

#### 6. FIELD RECORDS

All CSI cards, recovery notes, profiles and the original field records for IRVING 1971 were forwarded to C3413 on 1 March 1972. Form 277, Tides Volumes for the MIAMI BISCAYNE BAY, TURKEY POINT, and CUTLER Tide staffs were also forwarded on 1 March. The 277's for the other staffs will be forwarded with the report for the February 1972 photography.

Submitted 29 February 1972

*John C. Veselenak*

John C. Veselenak  
Chief, Photo Party 65

## FIELD REPORT

JOB PH-7119

This report is on work done in accordance with Instructions-Field-Job PH-7119; Horizontal Control for Aerotriangulation and Field Support for Aerial Photography; Coastal Boundary Mapping, Card Sound to Plantation Key, Florida, dated January 31, 1972. The field work was done during the period 7-23 February 1972.

1. PREMARKING OF CONTROL

Four stations were paneled for 1:30,000 scale photography. The locations are shown on the chart section accompanying this report.

2. AEROTRIANGULATION PHOTOGRAPHY

Flight lines are shown on the chart. Color photography was accomplished on February 19, 1972 between the approximate times of 1045 and 1230 hours. The skies were exceptionally clear for this area and the ground winds was from the north-west at 20-25 knots all morning. These lines were also flown on February 14, but the photography was unacceptable because of a bad film emulsion.

3. TIDE-COORDINATED PHOTOGRAPHY

Locations of the tide staffs are shown on the chart. The job was completed; photography taken on the 12, 14, 15, 16, and 20, of February. Lines 20-2 and 30-3 were also photographed and portions of the other lines were also partially photographed during August 1971.

Recordings entered in the tide volumes, Form 277, were at 5 minute intervals during photography and at 15 minute intervals near photography. An exception to this is the readings for the MANATEE CREEK and BARNES SOUND staff where the tide varies only a few hundredths of a foot per day. Tolerances of  $\pm 0.30$  foot for MHW,  $\pm 0.20$  foot for MWL, and  $\pm 0.10$  foot for MLW were observed. Wet staff readings - crest, mean, and trough - were recorded while photography was in progress. Eastern Standard Time was used.

Line 20-1. MHW Completed at 1050 on February 14 when the RAGGED KEYS staff read 3.38-3.26. MLW Completed at 1500 on February 14 when the staff read 1.80.

Line 20-2. MHW Flown at 1035-1052 on 16 February when the OCEAN REEF staff read 4.75-4.61. This line was also flown at 1006 on February 15, but the pilot recommended it be rescheduled. MLW Flown at 1338-1350 on February 14 when the staff read 2.31-2.32.

Line 30-1. This line is controlled by three staffs, the MANATEE CREEK staff has a MWL datum and the EAST ARSENICKER and CARD SOUND staffs have mean high and mean low datums. MHW The line was flown at 1120-1142 on 14 February. At this time the EAST ARSENICKER staff read 3.95-3.86 and the MANATEE CREEK staff read 3.54-3.57(MWL). The line was flown again at 1445 on 14 February when the CARD SOUND staff read 3.8 and the MANATEE CREEK staff read 3.60. MLW Was flown at 945-1000 on 20 February when the CARD SOUND staff read 3.2 and the EAST ARSENICKER staff read 2.78-2.81.

Line 30-2. MHW It was completed at 1250 on February 14 when the TAVERNIER, FLA. BAY staff read 3.05 (MWL Range), the BARNES SOUND staff read 3.92, the MANATEE CREEK staff read between 3.6 and 3.5, the CARD SOUND staff read 4.0 and the EAST ARSENICKER staff read 3.65. MLW Completed at 0945 on February 20 when the CARD SOUND staff read 3.20 and the EAST Arsenicker staff read 2.77-2.78.

The BARNES SOUND staff read 0.31 foot higher than its 3.61 Mean Water Level. Since the shoreline in this area is overhung with mangrove this section of the line was not rescheduled.

Line 30-3 (ATLANTIC SIDE). MHW Completed at 1107 on February 16 when the TAVERNIER, HAWK CHANNEL staff read 4.62-4.43. MLW Completed at 1412 on February 14 when the staff read 2.30-2.28.

Line 30-3 (Florida Bay Side). MWL The north side was completed on February 12 at 1150 hrs. when the BARNES SOUND staff read 3.78 and the TAVERNIER, FLA. BAY staff read 2.72. The south end was in range at 1412 on February 14 when 30-3(ATLANTIC SIDE) MLW was flown. The south half was also in range at 1107 on February 16 when 30-3 MHW was flown although the staff was not manned at that time.

#### 4. ADDITIONAL PHOTOGRAPHY

Special photography over Florida's test area was flown between 1005 and 1240 on 20 February with various films. The staff at the EAST ARSENICKER gage was observed and its value recorded at 5 minute intervals during this period. The staff at the

mouth of the northern cut (MANGROVE POINT) was observed and its value recorded at 5 minute intervals from 1135 to 1300 hours. The latter staff values are listed in the EAST ARSENIKER Form 277.

#### 5. FORESHORE PROFILES

Four planetable beach profiles were run within the limits of the job during the photography period of August 1971. The few small beaches found for the profiles were of coral, and since erosion is not considered a problem, these profiles were not rerun.

#### 6. MONITORING OF TEMPORARY TIDE STAFFS IN THE JOB AREA

On February 15 verbal instructions were received from the Chief, Tidal Datum Planes: Temporary staffs were to be put in at 11 selected locations and observed every 12, 15, or 30 minutes through one high and one low water. All 11 need not be observed simultaneously and the actual location could be varied slightly. Four were observed on the 16th., two on the 17th., 1 on the 20th., and four on the 21st. The chart accompanying this report shows the exact location of each staff.

#### 7. FIELD RECORDS

All CSI cards, Form 277's and a copy of the records from the 11 tide staffs were sent to C3413 on 13 March 1972. The original field records for the 11 staffs were forwarded to C3311 on 23 February 1972. Profiles and recovery notes were sent to C3413 on 1 March 1972 with the report for work done on this job in August 1971.

Submitted 14 March 1972

*John C. Veselenak*

John C. Veselenak  
Chief, Photo Party 65

Photogrammetric Plot Report  
Hillsboro Inlet to Card Sound, Florida  
Job PH-7113  
and  
Card Sound to Plantation Key, Florida  
Job PH-7119

21. Area Covered

This report covers an area on the east coast of Florida immediately south of Hillsboro Inlet to the southwestern end of Plantation Key. Job PH-7113 and Job PH-7119 are combined in this one report because the southern portion of Job PH-7113 is included in the block adjustment of Job PH-7119.

Job PH-7113 consists of twenty (20) 1:10,000 scale sheets: TP-00416 through TP-00420, and TP-00422 through TP-00436.

Job PH-7119 consists of twelve (12) 1:10,000 scale sheets: TP-00444 through TP-00455.

Subsequent to the initial bridging in this area, three small areas were re-bridged using new photography. The reports are attached:

- (1) Port Everglades, Florida
- (2) Miami to Mangrove Point, Florida
- (3) Hollywood to Miami Beach, Florida

22. Method

Eleven (11) strips of photography were bridged using aerotriangulation methods. Tie points were made between strip No. 1 of PH-7113 and strip No. 2 of the Jupiter Inlet to Hillsboro Inlet, Florida report to the north of this area.

Due to the placement of control in relation to flight lines and due to large areas of water coverage, two block adjustments were made. Strip No. 2, No. 3, and No. 4 comprised one block. Strip No. 7, No. 9, No. 10, and No. 11 comprised the other block. Attached is a sketch showing the location of the strips and the blocks.

Image points were located to rectify photographs for orthophoto, nautical, and small craft charts. All points were drilled by the PUG method. Closure to control has been noted on the read-outs. A sketch is attached which shows the control used in the strip and block adjustments. All points were plotted on the Florida East Zone Plane Coordinate System using the Coradomat Plotter or the Calcomp Plotter.



Ratio points were located on twenty-eight (28) strips of infrared contact prints. Additional ratio points were located on contact prints which have a large portion of water coverage so that they could be individually enlarged to scale. A sketch showing the location of the infrared photographs is attached.

### 23. Adequacy of Control

The control was adequate. Horizontal control was pre-marked on strip No. 1, No. 2, No. 3, No. 4, No. 5, and No. 6. Because of the placement of flight lines in relation to control, it was necessary to extend Strip No. 5 one model past its terminal control station in order to have an area of common coverage with strip No. 6. Tie points were located in this area and tie point 544801 was used as a terminal control point for strip No. 6.

Most of the horizontal control for Strip No. 7, No. 8, No. 9, No. 10, and No. 11 was pre-marked for color photography which was flown on August 4, 1971, and August 11, 1971. This photography was not used for bridging. The positions of the pre-marked control stations were transferred, using PUG methods, to color infrared photography which was flown on March 5, 1973, and March 18, 1973.

The following control station positions were transferred from photographs 71L(C)8370 through 71L(C)8382:

Irving 1971

Mangrove (USE) 1930 Sub Point A

Sands Cut RM2, 1849-1947 Sub station

The following control station positions were transferred from a roll of color photography which was not indexed (Spot No. 100-691A) LC-20:

Rubi, 1930-1948 Reset

Man, 1930

Angelfish Key RM3, 1853

Narrow Point, 1854

Long Sound 1961

Snipe Pt., 1934, substation

Knowlson, 1935, substation

Hull Key, 1852

Rock Harbor 2, 1961

Lower Sound Point, 1853 substation

Sub Station, Key Largo Cable Visions Inc., Taller Mast, 1961

Largo, 1962

Low 2, RM2, 1934

Planter 2, RM4

The following control station positions were transferred from photographs 72L(C)8691R thru 72L(C)8698R:

Tavernier 1935

Snake 1934 Sub. Sta.

Turkey Pt. 2, RM2 was transferred from photograph 71E(C)9595.

Cape Florida Old Tower Finial Sub Station A was transferred from photograph 71E(C)9201.

Lower Sound Point 1853 sbu. station was not used in the adjustment because the field party advised that it was questionable and should be used with caution. Sub. station Key Largo Visions, Inc., Taller Mast, 1961, could not be used because one of its azimuth stations (Key Largo Cable Visions, Inc. Shorter Mast) appears to have a bad published position. To date, this has not been resolved by the Geodesy Division. Turkey Point 2, RM2 was a very poor point to transfer, and, therefore, it was not used as control in the block adjustment in that area.

Part-way through the compilation phase of this project, it was determined that the published control positions in the area of this report were in error approximately - 4 feet in X and -10 ft. in Y. Therefore, Strip No. 1, No. 2, No. 3, No. 4, No. 5, No. 6, and No. 8 are adjusted to the old published control positions. This area includes T-sheets TP-00416 through TP-00420 and TP-00422 through TP-00432.

Strip No. 7, No. 9, No. 10, and No. 11 are adjusted to new preliminary control positions which were furnished by Geodesy on May 29, 1974. Geodesy Division stated this preliminary control will be within one (1) foot of the final adjustment. They also said to base non-main scheme stations on the nearest main scheme stations. This was approved by the Coastal Mapping Division.

Since stations established in 1971 and later have positions which were determined by a different adjustment than stations which were established before 1971, it was necessary that the corrections for non-main scheme stations of 1971 and later be based on the new preliminary control of the nearest main scheme stations of 1971 and later. In like manner, pre-1971 non-main scheme stations are based on the amount of change of the nearest pre-1971 main scheme station.

The compiler was advised to make a graphic adjustment on TP-00430 so it will junction well with TP-00433. Also, TP-00432 should be graphically adjusted so it will junction well with TP-00433, TP-00434, and TP-00435.

A listing of closures to control is included on an attached sheet of control stations. The station with the largest residual is Narrow Point 1854, with 1.808 feet in X and 1.267 feet in Y.

24. Supplemental Data

USGS Topographic Quadrangles and NOS Nautical Charts were used to obtain vertical control for bridging.

25. Photography

The following RC-8 color photography was used for bridging:

1:20,000 scale

Strip No. 4 71E(C)9201-9215  
Strip No. 8 73L(C)2871-2884R  
Strip No. 9 73L(C)2893-2924R

1:30,000 scale


Strip No. 1 71E(C)9120-9135  
Strip No. 2 71E(C)9562-9574  
Strip No. 3 71E(C)9576-9586  
Strip No. 5 71E(C)9536-9545  
Strip No. 6 71E(C)9588-9602

1:40,000 scale

Strip No. 7 73L(C)2935-2945R.  
Strip No. 10 73L(C)2952-2968R  
Strip No. 11 73L(C)2785-2797R


The quality and definition of the photography was adequate.

Respectfully submitted,



Victor McNeel

Approved and forwarded:



John D. Perrow, Jr.  
Chief, Aerotriangulation Section

CONTROL STATIONS

			<u>residuals</u>	
1.	(027100)	Turtle 1929	-0.706	-0.115
2.	(023102)	Pompano, 1928, subpoint B	1.488	-0.229
3.	(029100)	South Jetty, 1938	-1.134	0.176
4.	(034101)	Halland, 1928	0.317	-0.007
5.	(567101)	Causeway, 1934	0.027	-0.012
6.	(562101)	Point View, 1934	0.000	-0.181
7.	(207100)	Base, 1934	0.112	0.142
8.	(204100)	Key Biscayne North Base, 1849	-0.158	0.033
9.	(201101)	Cape Florida Old Tower Finial, subpoint A	-0.156	0.002
10.	(538102)	Pan American, 1935, Target 2	0.000	0.000
11.	(534101)	Naco 1934, subpoint A	0.000	0.000
12.	(544801)	Tie point from strip #5 used as control for strip #6	-0.157	0.025
13.	(591100)	Black Point 3	0.351	-0.066
14.	(595101)	Turkey Point No. 2, 1930, RM No. 2	-0.229	0.073
15.	(940100)			
	(602100)	Narrow Point 1854	-1.808	1.267
16.	(944100)	Man 1930.	0.222	-0.009
17.	(960100)	Long Sound, 1961	-0.168	-0.075
18.	(936101)	Snipe Point, 1934, sub- station	-0.215	-0.201
19.	(878101)	Irving, 1971, substation	0.687	-0.080
20.	(875102)	Mangrove (USE), 1930, subpoint B	-0.826	0.125
21.	(872101)	Sands Cut RM 2, 1849-1947 substation	0.296	-0.049
22.	(901100)	Rubi, 1930-1947, reset	-0.192	-0.134
23.	(905101)	Angelfish Key RM 3, 1853	-0.303	-0.242
24.	(914101)	Knowlson, 1935 substation	0.153	-0.155
25.	(919100)	Hull Key, 1852	-0.053	0.103
26.	(922100)	Rock Harbor 2, 1961	0.364	-0.284
27.	(022101)	Lower Sound Point, 1853 substation **		
28.	(923101)	Sub Station Key Largo Cable Visions Inc., Taller Mast, 1961 **		
29.	(924100)	Largo, 1962	-0.210	0.103


30.	(967101)	Low 2, RM 2, 1934	0.042	0.215
31.	(692100)	Tavernier, 1935	0.308	-1.325
32.	(793101)	Planter 2, RM 4	-1.476	1.087
33.	(695101)	Snake, 1934, subpoint	0.128	0.174

\*\* means not used in adjustments

JOB PH-7113  
AND  
JOB PH-7119


HILLSBORO INLET  
TO  
PLANTATION KEY,  
FLORIDA

CONTROL STATIONS  
USED IN THE  
ADJUSTMENTS



## INFRA-RED CONTACT PRINTS

1. 71K 5632R - 5660R MLW
2. 71K 5662R - 5672R MLW
3. 71K 5750R - 5766R MHW
4. 71K 5795R - 5806R MHW
5. 71K 5815R - 5829R MHW
6. 71L 8501R - 8509R MLW
7. 71L 8512R - 8520R MLW
8. 71L 8571R - 8580R MHW
9. 71L 8523R - 8530R MLW
10. 71L 8783R - 8791R MHW
11. 71L 8584R - 8593R MHW
12. 71L 8532R - 8537R MLW
13. 71L 9067R - 9080R MLW
14. 71L 8337R - 8341R MHW
15. 72K 6287R - 6298R MHW
16. 72K 6572R - 6584R MLW
17. 72K 6546R - 6563R MLW
18. 72K 6311R - 6330R MHW
19. 71L 8544R - 8559R MLW
20. 71L 8648R - 8662R MLW
21. 72K 6480R - 6499R MHW
22. 71L 8697R - 8705R MHW
23. 72K 6344R - 6350R MLW
24. 72K 6253R - 6255R MLW
25. 72K 6420R - 6423R MHW
26. 72K 6501R - 6515R MHW
27. 72K 6368R - 6382R MLW
28. 71K 5847R - 5856R MHW



JOB PH-7113  
AND  
JOB PH-7119

HILLSBORO INLET  
TO  
PLANTATION KEY,  
FLORIDA

INFRA-RED CONTACT  
PRINTS RATIOED FOR  
COMPILATION



## FLORIDA- NOAA Coastal Boundary Mapping Program

Horizontal Control

Map TP- 00448

Station	NOS Geodetic Data Reference for Description, Positions, Coordinates and Azimuths
KNOWLSON 1935 ✓	Book 424 P. 15, 28, 31, 33; GP 323, Fla. Vol 1; PC Fla. E. Zone P. 79
UPPER SOUND POINT 1853 ✓	Book 424 P. 16, 31, 38; GP 360 Fla Vol 1; PC Fla. E. Zone P. 90

Geodetic Bench Mark	Elevations (feet)	Condensed Description
	SLD 1929	
N 274 ✓		C&GS disk stamped N 274 1966; set vertically in the SW face of a 6X10 foot concrete block for water line.
R 274 ✕		C&GS disk stamped R 274 1966; set in top of the north corner of a 7 ft. concrete base with manhole for water line.
Z 316 ✓		C&GS disk stamped Z 316 1970; set in top of the east corner of the concrete base for a 10 ft. high concrete tank.
TIDAL STA 9 TIDAL BM 1		C&GS tidal disk stamped NO1 1935; set in a sidewalk, 26 ft. SW of center line of road leading NW.
E 275 ✕		C&GS disk stamped E 275 1966; set in top of the SW wall of a 5 ft. square concrete box with wooden cover, 25 ft. SE of center line of highway.
KNOWLSON ✕		C&GS tringulation disk stamped KNOWLSON 1935 1961; 53.5 ft. NE of power pole #219, 2.3 ft. SE of a metal witness post.
F 275 ✕		C&GS disk stamped F 275 1966; in top of the W corner of a 5.5 ft. square concrete box with wooden cover.

TP-00448  
Compilation Report  
April 1975

31. Delineation

The tidal datum lines were compiled graphically from office interpretation of the tide-coordinated, black-and-white infrared photography. This photography was controlled by common planimetric detail compiled from the color photography and map points determined by aerotriangulation.

The rectified color infrared photography was used as an aid for interpreting culture features and compiling and channel lines, shoal, shallow lines, and small scattered mangrove islets.

The rectified color photography was also used for the compilation of the interior details.

32. Control

See Photogrammetric Plot Report.

33. Supplemental Data - None.

34. Contours and Drainage

Contours are inapplicable. Drainage was compiled from a stereoscopic examination of the color printons and graphically compiling from the rectified color photography.

35. Shoreline and Alongshore Features

The photography was adequate for the interpretation of the shoreline and alongshore features.

36. Offshore Details

No unusual problems were encountered.

37. Landmarks and Aids

All landmarks and aids to navigation will be located or verified during field edit. Two landmarks and one light were located during bridging, and will be verified in field edit.

38. Control for Future Surveys - None.

39. Junctions

Refer to NOAA Form 76-36B for final junctions.

40. Horizontal and Vertical Accuracy.

- This map complies with the accuracy requirements for the Florida Coastal Zone Mapping Program.

41. thru 45. Inapplicable.

46. Comparison with Existing Maps

A comparison was made with the following U.S.G.S. quads:

Blackwater Sound, Florida 1947, P.R. 1969, 1:24,000.

Garden Cove, Florida, 1947, P.R. 1969, 1:24,000.

Significant differences were noted on the west side of Key Largo between 25°13'00" and 25°15'00".

47. Comparison with Nautical Charts:

A comparison was made with the following Nautical Charts:

11451, 1:80,000, 12th Edition, September 1974;

11463, 1:40,000, 7th Edition, August 1974;


1249, 1:80,000, 12th Edition, April 1973.

Significant differences were noted on the west shore of Key Largo where new channels along the shoreline have been constructed.

Respectfully submitted,

  
Peter N. Gibson

Approved & forwarded:

  
Jeter P. Battley, Jr.  
Chief, Coastal Mapping Section

## FIELD EDIT SHEET, MAP TP-00448, JOB PH 7119

51. METHOD

The shoreline was inspected from a small boat while cruising just off shore. Notes regarding apparent and fast shoreline and along shore details were made on the photographs and discrepancy print.

Two traingulation stations were recovered.

Seven bench marks were recovered and identified.

Three tide gages fall within the limits of this manuscript. Basin Hills tide gage is not in place at this time and no tidal bench marks were recovered. the area is under construction and has been filled. Barns Sound gage is also not in place, but one tidal gage was identified. Photo Party 65 installed a gage at Garden Cove at the time of field edit. this gage was identified on 73L2917R with a tidal bench mark.

Two Towers are recommended for landmarks.

All known aids were located or identified.

All field edit data will be found on the discrepancy print, field edit sheet and the photographs.

52. ADEQUACY OF COMPILATION

Adequate after application of field edit.

53. MAP ACCURACY

No test required.

54. RECOMMENDATION

None.

55. EXAMINATION OF PROOF COPY

Not required.


Submitted 7/22/75

  
Robert R. Wagner  
Chief, Photo Party 60

## ADDENDUM 1, TP-00448 PH 7119

Main Key, Barnes Sound Tide Gage was installed after field edit. It along with Tidal Bench Mark 1 was identified on photograph 73L2959R.

8/20/75 Submitted

  
Robert R. Wagner  
Chief, Photo Party 60

Review Report  
TP-00448

July 1976

61. General

The map manuscript for Coastal Zone Map TP-00448 was inspected as a Class III map (compilation, discrepancy print, and report) and reviewed as a Class I map by the Quality Control Group. The review consisted of an examination of the map manuscript, the field edit and its application, the reproduction negatives, and the Descriptive Report.

The proof copy of this map was edited by the Quality Control Group before making final copies. This edit comprised a thorough inspection of map details to verify the accuracy of reproduction with reference to the map manuscript and the quality of reproduction. In addition, the proof copy was examined by the following sections:

- Coastal Mapping - map details
- Staff Geographer - geographic names
- Coastal Surveys - horizontal and vertical control

The field reports dated February and March 1972 state that four (4) plane-table beach profiles were run. One (1) of these profiles is within the limits of TP-00448 and was used to verify the tidal datum lines.

62. Cartographic Comparison

Comparison was made with the following USGS quadrangle maps:

- Blackwater Sound, Florida, 1947, photorevised 1969,  
1:24,000 scale.

- Garden Cove, Florida, 1974, photorevised 1969,  
1:24,000 scale.

Comparison was made with the following nautical chart:

- 11463 (formerly C&GS 849), 7th Edition, dated August 3, 1974, 1:40,000  
scale:

Significant changes were noted on the quadrangle and chart between latitudes 25°13' and 25°15'. These changes are due to construction in the area.


Copies of the Field Editors' notes about a wreck and MLW area shown on the chart but not shown on TP-00448 are attached to the Chart Maintenance Print.

63. thru 65. Inapplicable.

66. Adequacy of Results and Future Surveys


Coastal Zone Map TP-00448 complies with the Instructions for NOS Cooperative Boundary Mapping, Job PH-7000, and the National Standards of Map Accuracy.

Submitted by:




Donald M. Brant

Approved and Forwarded:



Chief, Photogrammetric Branch AB



Chief, Coastal Mapping Division



27 Jan. 1975


## GEOGRAPHIC NAMES

PH-7119 (Card Sound to Plantation Key, Florida)

TP-00448

Atlantic Ocean ✓	Largo Point ✕
Barnes Sound ✕	Main Key ✕
Big Cove ✓	Manatee Bay ✕
Blackwater Sound ✕	Ocean Isle Estates ✕
Cormorant Rookeries ✓	Point Mary ✕
Cove Point ✕	Rattlesnake Key ✕
Cross Key ✕	Sexton Cove ✕
Everglades National Park ✕	Snake Point ✓
Garden Cove ✓	Thursday Cove ✕
Garden Cove (water body) ✕	Thursday Point ✕
Gulfstream Shores ✕	Upper Sound Point ✕
<del>Hawk Channel</del>	
Jewfish Creek ✕	
John Pennekamp Coral Reef State Park ✕	
Key Largo ✕	
Lake Simmons ✓	
Lake Surprise ✕	
Lake Surprise Estates ✕	

Approved by:

  
 Chas. E. Harrington

Staff Geographer-C51x2

\* SVY TP-00448 \* RPT UNIT CMD ROCKVILLE, MD. \* PAGE 1 OF 2  
\* JOB PH-7119 \* NONFLOATING AIDS FOR CHARTS \* STATE FLORIDA \*  
\* PRJ R \* LOCALITY RATTLESNAKE KEY \* ORIGINATING ACTIVITY \*  
\* DIM NA 1927 \* DATE 01/06/75 \* COMPILATION \*

\* THE FOLLOWING OBJECTS HAVE NOT BEEN INSPECTED FROM SEAWARD TO DETERMINE THEIR VALUE AS LANDMARKS \*

\* CHARTING\* RECORD REASON FOR DELETION \* POSITION CODES\* METHOD AND DATE \*  
\* NAME \* PUT TRIANGULATION NAMES IN \* LATITUDE DM C-G \* OF LOCATION \* CHARTS \*  
\* \* \* \* LONGITUDE DP SEQ \* OFFICE \* FIELD \* AFFECTED \*

\* \* BISCAYNE BAY \* \* \* \*  
\* \* LONG KEY \* \* \* \*

\* LIGHT \* JEW FISH CREEK \* 25 12 8.45 260.0 200 \* \* P-L-8-3 \* 1249 \*  
29 \* \* 80 22 58.19 1623.1 7 \* \* 07/16/75 \* 11451 \*

\* \* \* \* \*  
\* DYBN \* DITTO \* 25 11 58.02 1785.3 219 \* \* DITTO \* 11463 \*  
30 \* \* 80 23 5.10 142.8 1 \* \* \* \* DITTO \*

\* \* \* \* \*  
\* DYBN \* DITTO \* 25 11 54.48 1676.3 219 \* \* DITTO \* DITTO \*  
31 \* \* 80 23 4.97 139.1 2 \* \* \* \*

\* \* \* \* \*  
\* DYBN \* DITTO \* 25 11 36.43 1120.3 219 \* \* P-5 \* \*  
32 \* \* 80 23 13.85 367.8 3 \* \* 07/17/75 \* DITTO \*

\* \* \* \* \*  
\* DYBN \* DITTO \* 25 11 16.52 508.3 219 \* \* P-5 \* \*  
34 \* \* 80 23 14.95 418.6 4 \* \* 07/17/75 \* DITTO \*

\* \* \* \* \*  
\* DYBN \* BLACKWATER SOUND \* 25 11 45.12 1388.3 219 \* \* 73LC2917R \* \*  
36 \* \* 80 23 24.64 690.0 5 \* \* P-L-8-3 \* \*  
\* \* \* \* 07/17/75 \* DITTO \*

\* \* \* \* \*  
\* DYBN \* DITTO \* 25 11 45.24 1392.0 219 \* \* DITTO \* \*  
37 \* \* 80 23 22.29 624.2 6 \* \* \* \* DITTO \*

\* \* \* \* \*  
\* LIGHT \* DITTO \* 25 10 34.12 1049.9 200 \* \* DITTO \* \*  
38 \* \* 80 23 35.59 996.6 8 \* \* \* \* DITTO \*

\* \* \* \* \*  
\* \* \* \* \*  
\* \* \* \* \*

\* TYPE OF ACTION \* NAMES OF RESPONSIBLE PERSONNEL \* ORIGINATOR \*

\* POSITIONS DETERMINED \* \* \* \*  
\* AND/OR VERIFIED BY \* J. MCCLURE AND VERIFIED BY J. BATTLE \* FIELD REPRESENTATIVE \*  
\* FIELD AND OFFICE \* I. HAAS \* OFFICE COMPILER \*  
\* ACTIVITIES \* J. TAYLOR \* DATA PROCESSER \*



National Archives Data  
TP-00448

1 Discrepancy print (paper copy)  
1 Field edit sheet (stable base copy)  
1 NOAA Form 76-36 C (History of Field Operations)  
2 NOAA Forms 76-40 (Nonfloating Aids or Landmarks for Charts)  
2 Pages of sextant fixes

Photography:

72K6343, 6344, 6513  
73L2912R, thru 2917R, 2960R (two of 2912)