

ORIGINAL

TP-00845

TP-00845

NOAA FORM 76-35

U.S. DEPARTMENT OF COMMERCE
NATIONAL OCEANIC AND ATMOSPHERIC ADMINISTRATION
NATIONAL OCEAN SURVEY

DESCRIPTIVE REPORT

Type of Survey Shoreline
Job No. CM-7415 Map No. TP-00845
Classification No. Edition No. ... 1
Field Edited Map

LOCALITY

State Maryland
General Locality Baltimore Harbor
Locality Curtis Creek
.....

1974 TO 1975

REGISTRY IN ARCHIVES

DATE

NOAA FORM 76-36A (3-72)		U. S. DEPARTMENT OF COMMERCE NATIONAL OCEANIC AND ATMOSPHERIC ADMIN.					
DESCRIPTIVE REPORT - DATA RECORD		<table border="1" style="width:100%; border-collapse: collapse;"> <tr> <td style="width:50%;"> TYPE OF SURVEY ☒ ORIGINAL ☐ RESURVEY ☐ REVISED </td> <td style="width:50%;"> SURVEY TP. <u>00845</u> MAP EDITION NO. <u>(1)</u> MAP CLASS <u>Final</u> JOB <u>CM-7415</u> </td> </tr> </table>		TYPE OF SURVEY ☒ ORIGINAL ☐ RESURVEY ☐ REVISED	SURVEY TP. <u>00845</u> MAP EDITION NO. <u>(1)</u> MAP CLASS <u>Final</u> JOB <u>CM-7415</u>		
TYPE OF SURVEY ☒ ORIGINAL ☐ RESURVEY ☐ REVISED	SURVEY TP. <u>00845</u> MAP EDITION NO. <u>(1)</u> MAP CLASS <u>Final</u> JOB <u>CM-7415</u>						
PHOTOGRAMMETRIC OFFICE Coastal Mapping Division Atlantic Marine Center, Norfolk, VA		<table border="1" style="width:100%; border-collapse: collapse;"> <tr> <td colspan="2" style="text-align: center;"> LAST PRECEEDING MAP EDITION </td> </tr> <tr> <td style="width:50%;"> TYPE OF SURVEY ☐ ORIGINAL ☐ RESURVEY ☐ REVISED </td> <td style="width:50%;"> JOB PH. _____ MAP CLASS _____ SURVEY DATES: 19__ TO 19__ </td> </tr> </table>		LAST PRECEEDING MAP EDITION		TYPE OF SURVEY ☐ ORIGINAL ☐ RESURVEY ☐ REVISED	JOB PH. _____ MAP CLASS _____ SURVEY DATES: 19__ TO 19__
LAST PRECEEDING MAP EDITION							
TYPE OF SURVEY ☐ ORIGINAL ☐ RESURVEY ☐ REVISED	JOB PH. _____ MAP CLASS _____ SURVEY DATES: 19__ TO 19__						
OFFICER-IN-CHARGE Jeffrey G. Carlen, Cdr.							
I. INSTRUCTIONS DATED							
1. OFFICE		2. FIELD					
Aerotriangulation 2/07/75 Compilation 3/12/75		August 16, 1974					
II. DATUMS							
1. HORIZONTAL: ☒ 1927 NORTH AMERICAN		OTHER (Specify)					
2. VERTICAL: ☒ MEAN HIGH-WATER ☒ MEAN LOW-WATER ☐ MEAN LOWER LOW-WATER ☐ MEAN SEA LEVEL		OTHER (Specify)					
3. MAP PROJECTION Polyconic		4. GRID(S) <table border="1" style="width:100%; border-collapse: collapse;"> <tr> <td style="width:50%;">STATE Maryland</td> <td style="width:50%;">ZONE</td> </tr> </table>		STATE Maryland	ZONE		
STATE Maryland	ZONE						
5. SCALE 1:5,000		<table border="1" style="width:100%; border-collapse: collapse;"> <tr> <td style="width:50%;">STATE</td> <td style="width:50%;">ZONE</td> </tr> </table>		STATE	ZONE		
STATE	ZONE						
III. HISTORY OF OFFICE OPERATIONS							
OPERATIONS		NAME	DATE				
1. AEROTRIANGULATION BY METHOD: <u>Analytic</u> LANDMARKS AND AIDS BY		<u>I. Rayborn</u>	<u>4/75</u>				
2. CONTROL AND BRIDGE POINTS PLOTTED BY METHOD: <u>Calcomp</u> CHECKED BY		<u>R. Robertson</u> <u>R. Robertson</u>	<u>4/75</u> <u>4/75</u>				
3. STEREOSCOPIC INSTRUMENT (shoreline only) PLANIMETRY BY COMPILATION CHECKED BY INSTRUMENT: <u>Wild B-8</u> CONTOURS BY SCALE: <u>1:7,500</u> CHECKED BY		<u>L. O. Neterer, Jr.</u> <u>Not checked</u> <u>NA</u> <u>NA</u>	<u>9/75</u> 				
4. MANUSCRIPT DELINEATION PLANIMETRY BY CHECKED BY METHOD: <u>Smooth Drafted</u> CONTOURS BY CHECKED BY SCALE: <u>1:5,000</u> HYDRO SUPPORT DATA BY CHECKED BY		<u>D. P. Butler</u> <u>F. Margiotta & R. Minton</u> <u>NA</u> <u>NA</u> <u>NA</u> <u>NA</u>	<u>10/75</u> <u>11/75</u> 				
5. OFFICE INSPECTION PRIOR TO FIELD EDIT BY		<u>F. Margiotta & R. Minton</u>	<u>11/75</u>				
6. APPLICATION OF FIELD EDIT DATA BY		<u>Charles Parker</u>	<u>2/76</u>				
7. COMPILATION SECTION REVIEW BY		<u>A. L. Shands</u>	<u>2/76</u>				
8. FINAL REVIEW BY		<u>A. L. Shands</u>	<u>2/76</u>				
9. DATA FORWARDED TO PHOTOGRAMMETRIC BRANCH BY		<u>C. H. Bishop</u>	<u>5/77</u>				
10. DATA EXAMINED IN PHOTOGRAMMETRIC BRANCH BY		<u>J. B. Phillips</u>	<u>6/77</u>				
11. MAP REGISTERED - COASTAL SURVEY SECTION BY		<u>R. J. Cater</u>	<u>7/77</u>				

NOAA FORM 76-36B
(3-72)U. S. DEPARTMENT OF COMMERCE
NATIONAL OCEANIC AND ATMOSPHERIC ADMINISTRATION
NATIONAL OCEAN SURVEYTP-00845
COMPILATION SOURCES

1. COMPILATION PHOTOGRAPHY

CAMERA(S) Wild RC-8 "E" and RC-10 "C"		TYPES OF PHOTOGRAPHY LEGEND		TIME REFERENCE	
TIDE STAGE REFERENCE Baltimore		☒ (C) COLOR ☐ (P) PANCHROMATIC ☐ (I) INFRARED		ZONE	
☒ PREDICTED TIDES Fort McHenry ☐ REFERENCE STATION RECORDS ☐ TIDE CONTROLLED PHOTOGRAPHY				Eastern	
				MERIDIAN	
				75th	
				☒ STANDARD	
				☐ DAYLIGHT	
NUMBER AND TYPE	DATE	TIME	SCALE	STAGE OF TIDE	
*74E(C)7282 thru 7286	10/21/74	10:46	1:15,000	0.9 ft. above MLW	
*74E(C)7364 thru 7366	10/21/74	11:48	1:15,000	0.8 ft. above MLW	
**74C(C)803 and 804	10/05/74	10:37	1:30,000	0.9 ft. above MLW	

REMARKS

*Compilation photography
 **~~Bridge~~ photography

2. SOURCE OF MEAN HIGH-WATER LINE:

The MHWL was compiled from office interpretation of the above listed photographs.

3. SOURCE OF MEAN LOW-WATER OR MEAN LOWER LOW-WATER LINE:

None compiled.

4. CONTEMPORARY HYDROGRAPHIC SURVEYS (List only those surveys that are sources for photogrammetric survey information.)

SURVEY NUMBER	DATE(S)	SURVEY COPY USED	SURVEY NUMBER	DATE(S)	SURVEY COPY USED

5. FINAL JUNCTIONS

NORTH	TP-00841	EAST	TP-00846	SOUTH		WEST	
	TP-00842		TP-00849 (1:10,000)		TP-00849 (1:10,000)		TP-00848 (1:10,000)

REMARKS

This manuscript lies within the northwest corner of TP-00849 and laps into the east edge of TP-00848, both at scale of 1:10,000.

NOAA FORM 76-36C
(3-72)U. S. DEPARTMENT OF COMMERCE
NATIONAL OCEANIC AND ATMOSPHERIC ADMINISTRATION
NATIONAL OCEAN SURVEYTP-00845
HISTORY OF FIELD OPERATIONSI. ☒ FIELD INSPECTION OPERATION☐ FIELD EDIT OPERATION

OPERATION	NAME	DATE
1. CHIEF OF FIELD PARTY	R. S. Tibbetts	9/74
2. HORIZONTAL CONTROL	RECOVERED BY ESTABLISHED BY PRE-MARKED OR IDENTIFIED BY	None None None
3. VERTICAL CONTROL	RECOVERED BY ESTABLISHED BY PRE-MARKED OR IDENTIFIED BY	NA NA NA
4. LANDMARKS AND AIDS TO NAVIGATION	RECOVERED (Triangulation Stations) BY LOCATED (Field Methods) BY IDENTIFIED BY	None None None
5. GEOGRAPHIC NAMES INVESTIGATION	TYPE OF INVESTIGATION ☐ COMPLETE ☐ SPECIFIC NAMES ONLY ☒ NO INVESTIGATION	
6. PHOTO INSPECTION	CLARIFICATION OF DETAILS BY	
7. BOUNDARIES AND LIMITS	SURVEYED OR IDENTIFIED BY	NA

II. SOURCE DATA

1. HORIZONTAL CONTROL IDENTIFIED

None

2. VERTICAL CONTROL IDENTIFIED

NA

PHOTO NUMBER	STATION NAME	PHOTO NUMBER	STATION DESIGNATION

3. PHOTO NUMBERS (Clarification of details)

None

4. LANDMARKS AND AIDS TO NAVIGATION IDENTIFIED

None

PHOTO NUMBER	OBJECT NAME	PHOTO NUMBER	OBJECT NAME

5. GEOGRAPHIC NAMES: ☐ REPORT ☒ NONE6. BOUNDARY AND LIMITS: ☐ REPORT ☒ NONE

7. SUPPLEMENTAL MAPS AND PLANS

None

8. OTHER FIELD RECORDS (Sketch books, etc. DO NOT list data submitted to the Geodesy Division)

None

NOAA FORM 76-36C
(3-72)U. S. DEPARTMENT OF COMMERCE
NATIONAL OCEANIC AND ATMOSPHERIC ADMINISTRATION
NATIONAL OCEAN SURVEY

TP-00845

HISTORY OF FIELD OPERATIONS

I. ☐ FIELD INSPECTION OPERATION☒ FIELD EDIT OPERATION

OPERATION	NAME	DATE
1. CHIEF OF FIELD PARTY	G. W. Jamerson	9/18/75
2. HORIZONTAL CONTROL	G. W. Jamerson	9/75
RECOVERED BY	NA	
ESTABLISHED BY	NA	
PRE-MARKED OR IDENTIFIED BY	NA	
3. VERTICAL CONTROL	NA	
RECOVERED BY	NA	
ESTABLISHED BY	NA	
PRE-MARKED OR IDENTIFIED BY	NA	
4. LANDMARKS AND AIDS TO NAVIGATION	G. W. Jamerson	11/75
RECOVERED (Triangulation Stations) BY	NA	
LOCATED (Field Methods) BY	NA	
IDENTIFIED BY	NA	
5. GEOGRAPHIC NAMES INVESTIGATION		
TYPE OF INVESTIGATION		
☐ COMPLETE		
☐ SPECIFIC NAMES ONLY		
☒ NO INVESTIGATION		
6. PHOTO INSPECTION	G. W. Jamerson	11/75
CLARIFICATION OF DETAILS BY		
7. BOUNDARIES AND LIMITS	NA	
SURVEYED OR IDENTIFIED BY		

II. SOURCE DATA

1. HORIZONTAL CONTROL IDENTIFIED

None

2. VERTICAL CONTROL IDENTIFIED

None

PHOTO NUMBER

STATION NAME

PHOTO NUMBER

STATION DESIGNATION

3. PHOTO NUMBERS (Clarification of details)

NOS October 74E(C)7283, 7284, 7285, 7286 and from TP-00842, 74E(C)7282

4. LANDMARKS AND AIDS TO NAVIGATION IDENTIFIED

Data for objects verified in the field are listed under 8. below.

PHOTO NUMBER

OBJECT NAME

PHOTO NUMBER

OBJECT NAME

5. GEOGRAPHIC NAMES:

☐ REPORT☒ NONE

6. BOUNDARY AND LIMITS:

☐ REPORT☒ NONE

7. SUPPLEMENTAL MAPS AND PLANS

None

8. OTHER FIELD RECORDS (Sketch books, etc. DO NOT list data submitted to the Geodesy Division)

3 Form 76-40's
Field Edit Report
Field Edit OzalidNOAA FORM 76-36C
(3-72)

NOAA FORM 76-36D
(3-72)U. S. DEPARTMENT OF COMMERCE
NATIONAL OCEANIC AND ATMOSPHERIC ADMINISTRATIONTP-00845
RECORD OF SURVEY USE

I. MANUSCRIPT COPIES

COMPILATION STAGES			DATE MANUSCRIPT FORWARDED	
DATA COMPILED	DATE	REMARKS	MARINE CHARTS	HYDRO SUPPORT
Compilation complete, pending Field Edit.	10/75	Class III Manuscript Superseded	11/24/75	11/19/75
Field Edit applied.	2/76	Class I Manuscript Superseded	6/07/76	
Final Review	5/77		5/26/77	

II. LANDMARKS AND AIDS TO NAVIGATION

1. REPORTS TO MARINE CHART DIVISION, NAUTICAL DATA BRANCH

NUMBER	CHART LETTER NUMBER ASSIGNED	DATE FORWARDED	REMARKS
1		7/02/76	Landmarks for charts.
1		7/02/76	Landmarks for deletion.
1		7/02/76	Aids for charts.


2. ☐ REPORT TO MARINE CHART DIVISION, COAST PILOT BRANCH. DATE FORWARDED: July 2, 1976
3. ☐ REPORT TO AERONAUTICAL CHART DIVISION, AERONAUTICAL DATA SECTION. DATE FORWARDED: _____

III. FEDERAL RECORDS CENTER DATA

1. ☒ BRIDGING PHOTOGRAPHS; ☒ DUPLICATE BRIDGING REPORT; ☒ COMPUTER READOUTS.
2. ☐ CONTROL STATION IDENTIFICATION CARDS; ☒ FORM ~~76-40~~ ⁷⁶⁻⁴⁰ SUBMITTED BY FIELD PARTIES.
3. ☒ SOURCE DATA (except for Geographic Names Report) AS LISTED IN SECTION II, NOAA FORM 76-36C.
ACCOUNT FOR EXCEPTIONS:
4. ☐ DATA TO FEDERAL RECORDS CENTER. DATE FORWARDED: _____

IV. SURVEY EDITIONS (This section shall be completed each time a new map edition is registered)

SECOND EDITION	SURVEY NUMBER TP - _____ (2)	JOB NUMBER PH - _____	TYPE OF SURVEY ☐ REVISED ☐ RESURVEY MAP CLASS ☐ II. ☐ III. ☐ IV. ☐ V. ☐ FINAL
	DATE OF PHOTOGRAPHY	DATE OF FIELD EDIT	
THIRD EDITION	SURVEY NUMBER TP - _____ (3)	JOB NUMBER PH - _____	TYPE OF SURVEY ☐ REVISED ☐ RESURVEY MAP CLASS ☐ II. ☐ III. ☐ IV. ☐ V. ☐ FINAL
	DATE OF PHOTOGRAPHY	DATE OF FIELD EDIT	
FOURTH EDITION	SURVEY NUMBER TP - _____ (4)	JOB NUMBER PH - _____	TYPE OF SURVEY ☐ REVISED ☐ RESURVEY MAP CLASS ☐ II. ☐ III. ☐ IV. ☐ V. ☐ FINAL
	DATE OF PHOTOGRAPHY	DATE OF FIELD EDIT	



Official Mileage for Cost Accounts

Sheet No.	Sq. Miles
TP-00836	1
TP-00837	4
TP-00838	2
TP-00839	1
TP-00840	2
TP-00841	2
TP-00842	4
TP-00843	2
TP-00844	3
TP-00845	4
TP-00846	2
TP-00847	1
TP-00848	3
TP-00849	9
TP-00850	6
TP-00851	2
TP-00852	11

TOTAL 59

JOB CM-7415
BALTIMORE HARBOR
MARYLAND
SHORELINE MAPPING
SCALE 1:5,000
& 1:10,000

SUMMARY TO ACCOMPANY

DESCRIPTIVE REPORTS

TP-00836 through TP-00852

Project CM-7415 covers the Patapsco River and Baltimore Harbor from the mouth of the river at Long. $76^{\circ} 25'$ westward to and including the Inner Harbor. The part of Back River within the limits of Maps TP-00851 and TP-00852 is not included in the project and was not mapped. Seventeen maps - four at 1:10,000 scale and thirteen at 1:5,000 scale - are included in the project.

Field work prior to compilation consisted of recovery and pre-marking of horizontal control required for bridging. This work was done in September 1974.

Color photography was flown in October 1974. The entire area is covered by 1:30,000 scale photography, which was used for bridging and compilation of the 1:10,000 scale maps. Supplemental photography used for compilation of the 1:5,000 scale maps was flown at 1:15,000 scale. Black and white ratio prints at map scale were prepared from the color transparencies for office use and field edit operations.

Bridging was done by analytic methods in the Rockville Office in April 1975. See Photogrammetric Plot Report, which is Page 7 of this Descriptive Report.

Compilation was done by the Coastal Mapping Section at the Atlantic Marine Center from July to November 1975, using the Wild B-8 stereoplotter. The location of the mean high water line and other details were determined by office interpretation of the photographs.

Field edit was done by a photogrammetric field unit from September to November 1975 and applied to the manuscripts at the Atlantic Marine Center from December 1975 to February 1976.

All original manuscripts are stabilene sheets. The 1:5,000 scale maps are on a two and one-half minute format and the 1:10,000 scale maps are on a five minute format. The original manuscripts were forwarded to the Rockville Office for preparation of registration copies.

Photogrammetric Plot Report
Baltimore Harbor, Maryland
CM-7415
April 1975

21. Area Covered

The area covered by this report pertains to the shoreline of Baltimore Harbor, Baltimore, Maryland. This area is covered by thirteen 1:5,000 scale sheets, TP-00836 thru TP-00847, TP-00851, and four 1:10,000 scale sheets TP-00848 thru TP-00850 and TP-00852.

22. Method

Five strips of 1:30,000 scale color photography were bridged by analytic aerotriangulation methods. Sketch number 1 shows the layout of the sheets, compilation photographs, strips of bridging photographs, and the location of field identified control. Ties were made between all bridging strips. The strips were controlled by field identified control paneled in 1974 with the inclusion of one office identified station as a terminal for strip two. Office identified control was floated as checks. Common points were located between the bridging photography and the compilation photography to control the compilation and to determine the ratio scale. Points were located on the bridging photography to determine the ratio scale of the photographs that pertain to the 1:10,000 scale TP sheets. Data for ruling projection were furnished to the Calcomp to be plotted in the Maryland State plane coordinate system. 1:5,000 scale ratios were ordered for the 1:5,000 scale sheets and 1:10,000 scale ratios of the bridging photographs were ordered for the 1:10,000 scale sheets.

23. Adequacy of Control

The control was adequate with the inclusion of office identified control. Geodesy could not furnish a position for Curb 2, 1971, in order to compute a sub point for that station. An office identified control station was used as a terminal for strip number two, in place of Curb 2, 1971.

24. Supplemental Data

USGS Quadrangles were used to provide vertical control for the adjustment.

25. Photography

The photography was adequate as to coverage and overlap. Definition was poor due to haze at time of photography.


Approved and forwarded:

John D. Perrow, Jr.
John D. Perrow, Jr.

Chief, Aerotriangulation Section

Respectfully submitted,

Ivey O. Raborn
Ivey O. Raborn



DESCRIPTIVE REPORT CONTROL RECORD

MAP NO.	TP-00845	JOB NO.	CM-7415	GEODETTIC DATUM NA 1927		ORIGINATING ACTIVITY Coastal Mapping Div., Norfolk, VA	AMC	
STATION NAME		SOURCE OF INFORMATION (Index)	AEROTRI- ANGULATION POINT NUMBER	COORDINATES IN FEET STATE _____ ZONE _____		GEOGRAPHIC POSITION ϕ LATITUDE λ LONGITUDE		REMARKS FORWARD BACK
CREEK, 1915		G.P. Vol I P. 321		X=		ϕ	39 12 25.864	797.6 (1052.7)
				Y=		λ	76 34 45.124	1082.7 (356.9)
				X=		ϕ		
				Y=		λ		
				X=		ϕ		
				Y=		λ		
				X=		ϕ		
				Y=		λ		
				X=		ϕ		
				Y=		λ		
				X=		ϕ		
				Y=		λ		
				X=		ϕ		
				Y=		λ		
				X=		ϕ		
				Y=		λ		
				X=		ϕ		
				Y=		λ		
				X=		ϕ		
				Y=		λ		
COMPUTED BY	A. C. Rauck, Jr.		DATE	COMPUTATION CHECKED BY		F. Mauldin		DATE
LISTED BY			5/20/75	LISTING CHECKED BY				5/27/75
HAND PLOTTING BY			DATE	HAND PLOTTING CHECKED BY				DATE

COMPILATION REPORT

TP-00845

31. DELINEATION:

Delineation was by the Wild B-8 stereoplotter, using 1:15,000 scale color photography. Quality of the photographs was good.

32. CONTROL:

See the attached Photogrammetric Plot Report dated April 1975.

33. SUPPLEMENTAL DATA:

None.

34. CONTOURS AND DRAINAGE:

Contours are not applicable to the project. Drainage was delineated by the Wild B-8 stereoplotter and by office interpretation of the photographs.

35. SHORELINE AND ALONGSHORE DETAILS:

Alongshore details were delineated by the Wild B-8 stereoplotter and by office interpretation of the photographs.

The mean high water line was delineated from office interpretation of the photographs.

36. OFFSHORE DETAILS:

No unusual problems, except for the construction of two bridges at the north end of Curtis Creek.

37. LANDMARKS AND AIDS:

Preliminary Forms 76-40 for Landmarks and/or Nonfloating Aids were prepared by the Compilation Office and forwarded to the Field Editor and/or Hydrographer for verification, location, or deletion in November 1975 and the final field edited forms were forwarded to the Rockville, Maryland Office on June 28, 1976.

38. CONTROL FOR FUTURE SURVEYS:

None.

39. JUNCTIONS:

See the attached Form 76-36B, Item #5 of the Descriptive Report concerning junctions.

40. HORIZONTAL AND VERTICAL ACCURACY:

No statement.

46. COMPARISON WITH EXISTING MAPS:

A comparison has been made with the following USGS Quadrangle: CURTIS BAY, MD., scale 1:24,000, dated 1969.

47. COMPARISON WITH NAUTICAL CHARTS:

A comparison has been made with the following National Ocean Survey Charts:

No. 12279, scale 1:40,000, 12th Edition, dated November 9, 1974
No. 12281, scale 1:15,000, 29th Edition, dated August 17, 1974

ITEMS TO BE APPLIED TO NAUTICAL CHARTS IMMEDIATELY:

None.

ITEMS TO BE CARRIED FORWARD:

None.

Submitted by:

David P. Butler

David P. Butler
Cartographic Aid
October 19, 1975

Approved:

Albert C. Rauck, Jr.

Albert C. Rauck, Jr.
Chief, Coastal Mapping Section, AMC

ADDENDUM TO THE COMPILATION REPORT

TP-00845

FIELD EDIT

Field edit has been applied and all corrections, deletions, and additions have been made.

Submitted by:

Albert C. Ranch. Jr. FOR

Charles Parker
February 18, 1976

February 28, 1977

GEOGRAPHIC NAMES

FINAL NAME SHEET

CM-7415 (Baltimore, Md.)

TP-00845

Arundel Cove

Back Creek

Baltimore & Ohio (RR)

Curtis Creek

Furnace Creek

Margate

Marley Creek

Marley Neck

Point Pleasant

Solleys Cove


Stahl Point

Tanyard Cove

Thomas Point

Walnut Point

Approved by:


Charles E. Harrington
Staff Geographer - C51x2

NOAA FORM 75-74 (7-75)		U.S. DEPARTMENT OF COMMERCE NOAA NATIONAL OCEAN SURVEY	
PHOTOGRAMMETRIC OFFICE REVIEW			
TP - 00845			
1. PROJECTION AND GRIDS FPM	2. TITLE FPM	3. MANUSCRIPT NUMBERS ALS	4. MANUSCRIPT SIZE JRM
CONTROL STATIONS			
5. HORIZONTAL CONTROL STATIONS OF THIRD-ORDER OR HIGHER ACCURACY ALS	6. RECOVERABLE HORIZONTAL STATIONS OF LESS THAN THIRD-ORDER ACCURACY (Topographic stations) NA	7. PHOTO HYDRO STATIONS NA	
8. BENCH MARKS NA	9. PLOTTING OF SEXTANT FIXES NA	10. PHOTOGRAMMETRIC PLOT REPORT FPM	11. DETAIL POINTS FPM
ALONGSHORE AREAS (Nautical Chart Data)			
12. SHORELINE FPM	13. LOW-WATER LINE FPM	14. ROCKS, SHOALS, ETC. FPM	15. BRIDGES FPM
16. AIDS TO NAVIGATION FPM	17. LANDMARKS FPM	18. OTHER ALONGSHORE PHYSICAL FEATURES JRM	19. OTHER ALONGSHORE CULTURAL FEATURES JRM
PHYSICAL FEATURES			
20. WATER FEATURES JRM	21. NATURAL GROUND COVER NA	22. PLANETABLE CONTOURS NA	
23. STEREOSCOPIC INSTRUMENT CONTOURS NA	24. CONTOURS IN GENERAL NA	25. SPOT ELEVATIONS NA	26. OTHER PHYSICAL FEATURES JRM
CULTURAL FEATURES			
27. ROADS JRM	28. BUILDINGS JRM	29. RAILROADS JRM	30. OTHER CULTURAL FEATURES JRM
BOUNDARIES			
31. BOUNDARY LINES NA	32. PUBLIC LAND LINES NA		
MISCELLANEOUS			
33. GEOGRAPHIC NAMES JRM	34. JUNCTIONS JRM	35. LEGIBILITY OF THE MANUSCRIPT JRM	
36. DISCREPANCY OVERLAY JRM	37. DESCRIPTIVE REPORT JRM	38. FIELD INSPECTION PHOTOGRAPHS NA	39. FORMS JRM
40. REVIEWER <i>Frank Margiotta</i> Frank Margiotta R. Minton <i>J.R. Minton</i> 11/75		SUPERVISOR, REVIEW SECTION OR UNIT <i>Albert C. Rauck, Jr.</i> Albert C. Rauck, Jr.	
41. REMARKS (See attached sheet)			
FIELD COMPLETION ADDITIONS AND CORRECTIONS TO THE MANUSCRIPT			
42. Additions and corrections furnished by the field completion survey have been applied to the manuscript. The manuscript is now complete except as noted under item 43.			
COMPILER Charles Parker <i>Albert C. Rauck, Jr. For</i>		2/18/76	SUPERVISOR <i>Albert C. Rauck, Jr.</i>
REVIEWER A. L. Shands		2/27/76	Albert C. Rauck, Jr.
43. REMARKS <i>A. L. Shands</i>			
See Form 76-36C, HISTORY OF FIELD OPERATIONS, Field Edit, Item 8.			



U.S. DEPARTMENT OF COMMERCE
National Oceanic and Atmospheric Administration
NATIONAL OCEAN SURVEY

FIELD EDIT REPORT

TP-00845

Baltimore Harbor, Md.

51. METHODS

An inspection of all shoreline and alongshore features was made, and all deletions, additions, and corrections are either shown or referred to on the field edit ozalid. All field edit notes are in purple ink for additions and corrections and in green ink for deletions.

Searches by boat for reported features below mean high water were made; because of the limited visibility into the water and lack of wire drag equipment or personnel in quantity to operate such equipment, any negative findings noted in the field edit data should not be considered conclusive, unless otherwise stated. The latest hydrographic survey of the area should be consulted for more complete information.

Most of the field edit inspection was accomplished by boat. Features were located by either sextant fixes or photo identification.

52. ADEQUACY OF COMPILATION

Compilation was adequate. There were no areas of change on this sheet. Compilation will be complete with the application of field notes.

56. GEOGRAPHIC NAMES

No discrepancies were found while editing this sheet.

57. LANDMARKS AND AIDS TO NAVIGATION

There are five landmarks on this sheet recommended for charting and one recommended for deletion.

There are three non-floating aids to navigation on this sheet recommended for charting.

58. FIELD EDITOR

Field edit was performed by Lt. George Jamerson and Mr. Howard Hart in November, 1975.



U.S. DEPARTMENT OF COMMERCE
National Oceanic and Atmospheric Administration
NATIONAL OCEAN SURVEY

Respectfully submitted,

George W. Jamerson

George W. Jamerson
Lt. NOAA
November 26, 1975

NOAA FORM 76-40
(8-74)

Replaces C&GS Form 567.

☒ TO BE CHARTED
☐ TO BE REVISED
☐ TO BE DELETED

REPORTING UNIT
(If field party, ship or office)
Coastal Mapping Div.
A.M.C. Norfolk, Va.

STATE
Maryland

LOCALITY
Baltimore Harbor

DATE
Feb. 1976

U.S. DEPARTMENT OF COMMERCE
NATIONAL OCEANIC AND ATMOSPHERIC ADMINISTRATION

NON-ENGINEERING AIDS OR LANDMARKS FOR CHARTS

ORIGINATING ACTIVITY

☐ HYDROGRAPHIC PARTY
☐ GEODETIC PARTY
☐ PHOTO FIELD PARTY
☒ COMPILATION ACTIVITY
☐ FINAL REVIEWER
☐ QUALITY CONTROL & REVIEW GRP.
☐ COAST PILOT BRANCH

(See reverse for responsible personnel)

DATUM
N.A. 1927

DATUM

SURVEY NUMBER
TP-00845

JOB NUMBER
CM-7415

OPR PROJECT NO.
514

The following objects HAVE ☒ BEEN INSPECTED FROM SEAWARD TO DETERMINE THEIR VALUE AS LANDMARKS.

CHARTING NAME	DESCRIPTION (Record reason for deletion of landmark or aid to navigation. Show triangulation station names, where applicable, in parentheses)	POSITION				METHOD AND DATE OF LOCATION (See instructions on reverse side)		CHARTS AFFECTED
		LATITUDE		LONGITUDE		OFFICE	FIELD	
		° /	D.M. Meters	° /	D.P. Meters			
TANK	Ht.=127(167)	39 12	02.01 62	76 32	30.84 710	74E(C)7365 Oct.21,1974	F-V-Vis. Nov.1975	12273 12279
TOWER	Coast Guard Base, Curtis Bay Ht.=380(100)	39 12	15.38 474	76 34	06.78 163	74E(C)7282 Oct.21,1974	" "	" "
TOWER	Overhead Power Cable Tower Ht.=120(130)	39 10	16.71 515	76 35	02.03 49	74E(C)7285 Oct.21,1974	" "	" "
TOWER	Overhead Power Cable Tower Ht.=120(135)	39 10	20.59 635	76 35	12.29 295	" "	" "	" "
TOWER	Overhead Power Cable Tower Ht.=120(145)	39 10	22.28 687	76 35	17.43 418	" "	" "	" "

V F T M

Replaces C&GS Form 567.

LANDMARKS FOR CHARTS

U.S. DEPARTMENT OF COMMERCE
ATMOSPHERIC ADMINISTRATION

LANDMARKS FOR CHARTS

[illegible]

Replaces C&GS Form 567.

NONFLOATING AIDS ~~ON LAND~~ FOR CHARTSU.S. DEPARTMENT OF COMMERCE
NATIONAL OCEANIC AND ATMOSPHERIC ADMINISTRATION

ORIGINATING ACTIVITY

- ☐ HYDROGRAPHIC PARTY
☐ GEODETIC PARTY
☐ PHOTO FIELD PARTY
☒ COMPILATION ACTIVITY
☐ FINAL REVIEWER
☐ QUALITY CONTROL & REVIEW GRP.
☐ COAST PILOT BRANCH

(See reverse for responsible personnel)

DATE
Feb. 1976LOCALITY
Baltimore HarborSTATE
MarylandREPORTING UNIT
(If field party, ship or office)
Coastal Mapping Div,
A.N.C. Norfolk, Va.The following objects HAVE ☒ HAVE NOT ☐ been inspected from seaward to determine their value as landmarks.

OPR PROJECT NO.

514

JOB NUMBER

CM-7415

SURVEY NUMBER

DATUM

N.A. 1927

POSITION

METHOD AND DATE OF LOCATION
(See instructions on reverse side)

OFFICE

FIELD

CHARTS
AFFECTEDCHARTING
NAME

DESCRIPTION

(Record reason for deletion of landmark or aid to navigation.
Show triangulation station names, where applicable, in parentheses)

LATITUDE

D.M. Meters

°

LONGITUDE

D.P. Meters

"

DAYBEACON

Marley Creek Daybeacon 1

39 11

11.35

76 34

32.63

783

74E(C)7284

F-V-Vis.
Nov. 1975

12279

DAYBEACON

Marley Creek Daybeacon 3

39 11

00.91

76 34

41.46

995

"

"

"

DAYBEACON

Marley Creek Daybeacon 5

39 10

52.37

76 34

50.62

1215

"

"

"

v ETC

REVIEW REPORT

TP-00845

SHORELINE

May 6, 1977

61. GENERAL STATEMENT:

See Summary, which is Page 6 of this Descriptive Report.

No comparison print was made for this map.

62. COMPARISON WITH REGISTERED TOPOGRAPHIC SURVEYS:

A visual comparison was made with copies of Surveys T-5342 and T-5436, both 1:10,000 scale and both mapped from photographs taken in April and May 1934. There is new bridge construction at Walnut Point, a Coast Guard Base has been added on the east side of Curtis Creek at Arundel Cove, and numerous piers have been added. Otherwise, no significant differences were noted.

In the area compared, TP-00845 supersedes T-5342 and T-5436 for nautical chart construction purposes. T-5342 and T-5436 are the latest registered topographic surveys of the area.

63. COMPARISON WITH MAPS OF OTHER AGENCIES:

A visual comparison was made with USGS Quadrangle CURTIS BAY, MD., 1:24,000 scale, dated 1969. No significant differences were noted.

64. COMPARISON WITH CONTEMPORARY HYDROGRAPHIC SURVEYS:

A comparison was made with the boatsheet for Survey H-9581 (AHP 5-11-75).

At Lat. $39^{\circ} 11' 21''$, Long. $76^{\circ} 34' 25''$, a submerged wreck located by the hydrographer is not visible on the photographs and is not shown on TP-00845.

At Lat. $39^{\circ} 11' 11''$, Long. $76^{\circ} 34' 23''$, a pipe located by the hydrographer is not visible on the photographs and is not shown on TP-00845.

65. COMPARISON WITH NAUTICAL CHARTS:

North of Lat. $39^{\circ} 11' 25''$, a visual comparison was made with Chart 12281 (545), 1:15,000 scale, 31st Edition, dated November 13, 1976.

A tank charted at Lat. $39^{\circ} 12.3'$, Long. $76^{\circ} 35.1'$ has been destroyed and is recommended for deletion.

Dolphins charted at the head of Arundel Cove are not visible on the photographs and were not observed by the field editor or hydrographer, and therefore, they are not shown on TP-00845.

An obstruction charted at Lat. $39^{\circ} 11' 20''$, Long. $76^{\circ} 34' 05''$ is not visible on the photographs, is not on the boatsheet, was not observed by the field editor, and therefore, is not shown on TP-00845.

South of Lat. $39^{\circ} 11' 25''$, a visual comparison was made with Chart 12278 (549), 1:40,000 scale, 43rd Edition, dated April 3, 1976. No significant differences were noted.

66. ADEQUACY OF RESULTS AND FUTURE SURVEYS:

This map complies with Project Instructions and meets requirements for Bureau Standards and National Standards of Map Accuracy.

Submitted:

Charles H. Bishop

Charles H. Bishop
Cartographer
May 6, 1977

Approved for forwarding:

Joseph W. Vonasek

Joseph W. Vonasek
Chief, Photogrammetric Branch, AMC

Approved:

W. K. Hargrove

Chief, Photogrammetric Branch

James C. Hargrove

Chief, Coastal Mapping Division

