

9896-7&9 9900-2
11292

Diag. Cht. No. 8252-2

Form 504

U. S. COAST AND GEODETIC SURVEY

DEPARTMENT OF COMMERCE

DESCRIPTIVE REPORT

Type of Survey Shoreline (Photogrammet-
ric)

Field No. Ph-49 (119) Office No. T-9896-9897
T-9899-9902
T-11292

LOCALITY

State Territory of Alaska

General locality Peril Strait

Locality Kakul Narrows to Ushk Bay

1942-52

CHIEF OF PARTY

L. C. Johnson, 1950

J. P. Lushene, 1952

F.A. Riddell, Portland Photo. Office
LIBRARY & ARCHIVES

DATE March 6, 1957

9896-7&9 9900-2
11292

DATA RECORD

Page 2

T- 9896 thru T-9902

Project No. (II): Ph-49(49)

Quadrangle Name (IV):

Field Office (II): Ship "PATTON"

L. C. Johnson, 1950

Chief of Party: Joseph P. Lushene, 1952

Photogrammetric Office (III): Portland, Oregon

Officer-in-Charge: Fred A. Riddell

Instructions dated (II) (III):
5 August 1947 (field)
14 March 1950 (field)
17 August 1951 (office)
14 April 1947 (suppl.)Copy filed in Division of
Photogrammetry (IV)

Method of Compilation (III): Graphic

Manuscript Scale (III): 1:10,000

Stereoscopic Plotting Instrument Scale (III):

Scale Factor (III): None

OCT 27 1953

Date received in Washington Office (IV):

Date reported to Nautical Chart Branch (IV):

DEC 7 1953

Applied to Chart No.

Date:

Date registered (IV):

Publication Scale (IV):

Publication date (IV):

Geographic Datum (III): N.A. 1927

Vertical Datum (III): X

Mean sea level except as follows:

Elevations shown as (25) refer to mean high water

Elevations shown as (5) refer to sounding datum

i.e., mean low water or mean lower low water

Reference Station (III): See reverse side of this page

Lat.:

Long.:

Adjusted

Unadjusted

Plane Coordinates (IV):

State:

Zone:

Y=

X=

Roman numerals indicate whether the item is to be entered by (II) Field Party, (III) Photogrammetric Office,
or (IV) Washington Office.

When entering names of personnel on this record give the surname and initials, not initials only.

T-9896 - RANCE, 1952 Lat. $57^{\circ} 33'$ $57.467''$ 1777.8m (78.4m) (Field
Long. $135^{\circ} 36'$ $37.715''$ 627.0m (370.5m) Comp.)

T-9897 - Same as above

T-9898 - CHIEF², 1952 Lat. $57^{\circ} 31'$ $46.235''$ 1430.3m (425.9m) (Field
Long. $135^{\circ} 29'$ $30.119''$ 501.2m (497.3m) Comp.)

T-9899 - OPASNI, 1952 Lat. $57^{\circ} 27'$ $35.408''$ 1095.4m (760.8m) (Field
Long. $135^{\circ} 32'$ $32.171''$ 536.3m (464.0m) Comp.)

T-9900 - SHOAL 2, 1950 Lat. $57^{\circ} 24'$ $35.841''$ 1108.8m (747.4m) (Field
Long. $135^{\circ} 37'$ $22.432''$ 374.5m (627.3m) Comp.)

T-9901 - GALLEY, 1950 Lat. $57^{\circ} 22'$ $40.310''$ 1247.0m (609.1m) (Field
Long. $135^{\circ} 32'$ $50.831''$ 849.4m (153.2m) Comp.)

T-9902 - EDUCE, 1950 Lat. $57^{\circ} 21'$ $50.700''$ 1568.4m (287.7m) (Field
Long. $135^{\circ} 31'$ $55.044''$ 920.1m (82.8m) Comp.)

Areas contoured by various personnel
(Show name within area)
(II) (III)

DATA RECORD

Field Inspection by (II): William C. Russell (*Salisbury Id. to Pt. Siroi*) Date: Season 1950
 Edmund L. Jones (*Pt. Siroi, N.E. to Nismeni Cove (proj. limit)*) 21 May -
T-9902 T-11292 10 Sept. 1952

M.H.W.L.
 Planetable ~~contouring~~ by (II): William D. Barbee Date: 16 June -
H-7985 Deadman Reach thru Nismeni Cove 10 Oct. 1952

Completion Surveys by (II):

Date:

Mean High Water Location (III) (State date and method of location): Field inspection 1950 and 1952.

Projection and Grids ruled by (IV):

Date:

Projection and Grids checked by (IV):

Date:

Control plotted by (III): J. L. Harris & Roy A. Davidson

Date: December 1951
 March 1952

Control checked by (III): J. L. Harris & Roy A. Davidson

Date: December 1951
 March 1952

Radial Plot or Stereoscopic J. L. Harris & Roy A. Davidson
 Control extension by (III):

Date: December 1951
 March 1952

Planimetry

Date:

Stereoscopic Instrument compilation (III):

Contours

Date:

Manuscript delineated by (III):

T-9896 - L.L. Graves
 T-9897 - V.E. Serena
 T-9898 - V.E. Serena
 T-9899 - C.C. Wiebe
 T-9900 - L.L. Graves
 T-9901 - V.E. Serena
 T-9902 - L.L. Graves

Date: Feb. 1953
 Mar. 1953
 Mar. 1953
 Feb. 1953
 Feb. 1953
 Feb. 1953
 Feb. 1953

Photogrammetric Office Review by (III):

J. E. Deal (T-9897, T-9899)
 C. C. Wiebe (All others)

Date: August 1953
 October, 1953

Elevations on Manuscript None
 checked by (II) (III):

Date:

Camera (kind or source) (III): U.S.C. & G.S., 9 lens, focal length 8.25 inches

Number	Date	Time	Scale	Stage of Tide
9471 to 9476 Incl.	7/8/42	10:38	1:10,000	6.6 ft. above M.L.L.W.
9533 to 9537 "	7/8/42	11:10	1:10,000	6.5 ft. above M.L.L.W.
10580 to 10606 "	7/31/42	3:10	1:10,000	10.5 ft. above M.L.L.W. <i>ok</i>
10618 to 10641 "	7/31/42 ✓	3:50	1:10,000	11.6 ft. above M.L.L.W. <i>ok</i>

Single lens

SEA 140 031 to 034	8/25/48	unknown	1:10,000(ratio)	low-water
SEA 124 100 to 102	8/14/48	"	1:10,000(ratio)	low-water

Tide (III) *

Reference Station: SITKA, ALASKA
 Subordinate Station: BEAR BAY (T-9899) (T-9900)
 Subordinate Station: KAKUL NARROWS (T-9900)
 Ret Sta Juneau
 Sub " Pogi bshi Anchorage (T-9896-T-11292)

Washington Office Review by (IV):

Robinson, A.T. 9901 Robinson A.T. 9902 9-8-54
 Robinson, A.T. 9897 Robinson A.T. 11292 9-13-54
 Final Drafting by (IV) Robinson, A.T. 9896
 Robinson, A.T. 9900
 Robinson, A.T. 9899

Drafting verified for reproduction by (IV): T-9896 W.O. Halluin
 T-9897 W.O. Halluin
 T-9900 W.O. Halluin
 T-9899 W.O. Halluin
 T-9901 W.O. Halluin
 T-11292 W.O. Halluin
 Proof Edit by (IV):

Land Area (Sq. Statute Miles) (III): Shoreline only

Shoreline (More than 200 meters to opposite shore) (III): 149

Shoreline (Less than 200 meters to opposite shore) (III): 11

Control Leveling - Miles (II):

Number of Triangulation Stations searched for (II):

Recovered: 119

Identified: 49

Number of BMs searched for (II):

Recovered:

Identified:

Number of Recoverable Photo Stations established (III): None

Number of Temporary Photo Hydro Stations established (III): 2

Remarks: Values resulting from study of 1952 field data. (compare 1952 values w. 1953 values)

		Diurnal			Time
MHW	Ratio of Ranges	Mean Range	Spring Range		
		7.7	9.9		
11.5	1.4	11.2	13.6	+0:30	
	1.0	7.8	10.0	+0:10	
14.00	0.9	14.0	16.6	+0:05	
		12.4	15.0		

Date: 2-2 Jan. 1954
 7-2-54
 7/18/54

Date: 7/18/54
 7/25/54
 8/20/54

Date: 7-30-54
 7-27-54
 8-31-54

Date: 9-7-54
 7-23-54

Summary to Accompany T-9896, T-9897,
T-9899, T-9900, T-9901, T-9902, T-11292

These seven surveys cover the northern part of project Ph-49(49) and include that part of Peril Strait between Kalkul Narrows and Rodgers Point.

Project Ph-49(49) is a graphic compilation project. Field work in advance of compilation included the establishment of horizontal control and the inspection of shoreline. This work was done in conjunction with hydrographic surveys in 1950, 1951, and 1952, Project CS-247.


The surveys in this group were compiled at a scale of 1:10,000 using nine-lens photographs taken in 1942, except in the most northeastern section (T-9897 and T-11292) where single-lens Army photographs taken in 1948 were used.

Items registered under these T-numbers will include a cloth-mounted lithographic print of each map manuscript and the combined descriptive report for the group.

SHORELINE MAPPING PROJECT PH-49 (49)

ALASKA, Vicinity of Sitka Sound

Compilation scale 1:10,000



FIELD INSPECTION REPORT

Map Manuscripts T-9896 thru T-9902

Project Ph-49(49)

*T-11292 replaces
T-9898*

Refer to Field Reports titled:

Photogrammetric

RS-385

S. E. Alaska

Salisbury Sound and Peril Strait

Eastern part of Salisbury Sound, Kakul

Narrows, Suloia Bay and Serguis Narrows

1950

L. C. Johnson, Chief of Party

and

Shoreline

CS-247

Alaska

Peril Strait

Pogibshi Point

1952

Joseph P. Lushene, Chief of Party

PHOTOGRAMMETRIC PLOT REPORT

Map Manuscripts T-9896 thru T-9902

T-11292 replaces
T-9898

Project Ph - 49(49)

21. AREA COVERED:

This radial plot covers the shorelines of Peril Strait, Fish Bay, Deep Bay, and Ushk Bay in southeast Alaska. It comprises Map Manuscripts No's. T-9896 thru T-9902.

22. METHOD:

Methods used were the same as those described in sub-heading 22 of the Photogrammetric Plot Report for T-8475 and T-8819 thru T-8821. This report is included in the Descriptive Report for T-8475, Project Ph-49(49) (1948 and 1949).

The following exception is noted:

The area was adequately covered by 9 lens photographs except for the west shoreline north of Ushk Bay on T-9897 and all ~~of T-9898~~. For these places single lens 4:1 ratio prints of 1948 photography were available. The detail on these prints is vague, radials are uncertain because of lens and paper distortion, and the pricking of horizontal control stations is questionable.

23. ADEQUACY OF CONTROL:

The field identification of stations was satisfactory and an adequate number of horizontal control stations were available. Along the west shoreline north of Ushk Bay in T-9897 the horizontal control stations were supplemented by sextant fix locations which are entered in H-7988, Volume 5 pages 27 and 53. These sextant fix locations were identified at the Photogrammetric Office.

Sub-station MENTO, 1951 could not be held. There is a disagreement in data on pricking card as to whether a right of left angle was measured. Neither will hold and the difficulty could not be resolved.

24. SUPPLEMENTAL DATA:

Graphic control surveys in the area of this radial plot are

Letter 17 Oct. 1952: Number dropped, shoreline compilation unnecessary (except in SW corner) because a planetable shoreline was made for H-7985 which covers the greater part of T-9898. Preliminary RS-387 had proved to be too generalized for use. T-11292 furnishes photogrammetric shoreline in the gap between T-9897 and H-11292. LTS. Jan. 1953

assfollows:

PA-A-51	Scale 1:5000
PA-A-52	Scale 1:5000
PA-B-52	Scale 1:5000
PA-C-52	Scale 1:10,000

For supplementary control stations used to control the radial plot refer to sub-heading 3, "Horizontal Control" of the 1952 Field Report.

25. PHOTOGRAPHY:

Except as previously stated under sub-heading 22 "Method" the photography was adequate for coverage.

There were no fiducial marks on the photographs for use in correcting transforming errors and paper distortion.

A period of 10 years had elapsed between the time of photography and the running of the radial plot.

Approved and forwarded;




Fred A. Riddell
Officer-in-Charge

Respectfully submitted;



J. Edward Deal, Jr.
Cartographer



LEGEND

- ▲ TRIANGULATION STATIONS
- TOPOGRAPHIC STATIONS USED IN RADIAL PLOT
- 1942 NINE LENS PHOTOGRAPHS
- 1948 SINGLE LENS PHOTOGRAPHS

SKETCH SHOWING AREA OF RADIAL
PLOT T-9896 TO T-9902 INCLUSIVE
PROJECT PH-49 (49)

MAP T-9897

PROJECT NO. Ph-49(49)

SCALE OF MAP 1:10,000

SCALE FACTOR None

STATION	SOURCE OF INFORMATION (INDEX)	DATUM	LATITUDE OR ψ -COORDINATE LONGITUDE OR α -COORDINATE	DISTANCE FROM GRID IN FEET. OR PROJECTION LINE IN METERS		DATUM CORRECTION	N.A. 1927 - DATUM DISTANCE FROM GRID OR PROJECTION LINE IN METERS		FACTOR DISTANCE FROM GRID OR PROJECTION LINE IN METERS
				FORWARD	(BACK)		FORWARD	(BACK)	
✓ OAR 2, 1952	Field Comp.	N.A. 1927	57° 30' 42.685				1320.5	(535.7)	
OAR 2, Sub. Sta. "a"	G9743 "	"	135° 33' 04.108				68.4	(930.5)	
✓ KIL 2, 1952	"	"	57° 30'				1344.7	(511.5)	
	"	"	135° 33'				32.1	(966.8)	
✓ NUN 2, 1952	"	"	57° 30' 39.465				1220.9	(635.3)	
NUN 2 Sub. Sta.	"	"	135° 34' 00.119				02.0	(997.0)	
✓ GIRL 2, 1952	"	"	57° 31' 25.344				784.0	(1072.2)	
GIRL 2 Sub. Sta. x	"	"	135° 34' 21.093				351.1	(647.6)	
✓ BER (USGS) 1952	"	"	57° 31'				767.4	(1088.8)	
	"	"	135° 34'				392.7	(606.0)	
✓ JOG 2, 1952	"	"	57° 32' 24.626				761.8	(1094.4)	
	"	"	135° 33' 47.186				785.0	(213.2)	
✓ HOGAT 1952	"	"	57° 32'				489.8	(1366.4)	
	"	"	135° 33'				887.1	(111.1)	
✓ HOGAT Sub. Sta. "b"	"	"	57° 32' 24.848				768.7	(1087.5)	
	"	"	135° 33' 47.174				784.8	(213.4)	
✓ N.E. BASE 1895 PGIBISHI ANCHORAGE	"	"	57° 35' 44.233				1368.4	(487.8)	
	"	"	135° 30' 31.990				531.4	(465.2)	
	"	"	57° 33' 04.632				143.3	(1712.9)	
	"	"	135° 30' 30.220				502.6	(495.3)	
	"	"	57° 33'				206.3	(1649.9)	
	"	"	135° 30'				418.7	(579.2)	
	"	"	57° 30' 41.462				1282.7	(573.5)	
	"	"	135° 30' 59.631				992.8	(6.1)	

Page 11

1 FT. = 3048006 METER
COMPUTED BY: FAR

DATE NOV. 1952

CHECKED BY: VES

DATE 12/10/52

M-2388-12

MAP T. 9897

PROJECT NO. Ph-49(49)

SCALE OF MAP 1:10,000

SCALE FACTOR

None

STATION	SOURCE OF INFORMATION (INDEX)	DATUM	LATITUDE OR y -COORDINATE LONGITUDE OR x -COORDINATE	DISTANCE FROM GRID IN FEET, OR PROJECTION LINE IN METERS		DATUM CORRECTION	N.A. 1927 - DATUM DISTANCE FROM GRID OR PROJECTION LINE IN METERS		FACTOR DISTANCE FROM GRID OR PROJECTION LINE IN METERS
				FORWARD	(BACK)		FORWARD	(BACK)	
N.E. BASE 1895	Field	N.A.	57 30				1273.9	(582.3)	
Sub. Sta. "e" $\times$	Comp.	1927	135 31				22.8	(976.1)	
S.W. BASE 1895	"	"	57 30	24.403			754.9	(1101.3)	
POGIBSHI ANCHORAGE	"	"	135 32	14.263			237.5	(761.6)	
S.W. BASE 1895	"	"	57 30				851.0	(1005.2)	
Sub. Sta. "a"	"	"	135 32				245.7	(753.4)	
$\checkmark$ SIDE 1952	"	"	57 33	13.249			409.9	(1446.3)	
	"	"	135 34	46.781			778.0	(219.8)	
SIDE	"	"	57 33				310.1	(1546.1)	
Sub. Sta. "a"	"	"	135 34				760.9	(236.9)	
$\checkmark$ USHK 1952	"	"	57 34	12.309			380.8	(1475.1)	
	"	"	135 35	12.485			207.5	(789.9)	
$\times$ USHK	"	"	57 34				430.1	(1426.1)	
Sub. Sta. "a"	"	"	135 35				300.5	(696.9)	
$\checkmark$ RANCE 1952	"	"	57 33	57.467			1777.8	(78.4)	
	"	"	135 36	37.715			627.0	(370.5)	
RANCE	"	"	57 33				1748.6	(107.6)	
Sub. Sta. "a"	"	"	135 36				562.6	(434.9)	
$\checkmark$ POVEROTNI	"	"	57 30	52.629			1628.1	(228.1)	
ISLAND LIGHT	"	"	135 33	12.371			206.0	(792.8)	
GEM 1952	"	"	57 34	38.406			1188.2	(668.0)	
	"	"	1 35 37	45.242			751.9	(245.3)	
$\checkmark$ FOR 1952	"	"	57 33	55.220			1708.3	(147.9)	
	"	"	135 30	54.834			911.6	(85.9)	

Page 12

1 FT. = 3048006 METER

COMPUTED BY: FAR

DATE NOV. 1952

CHECKED BY: VBS

DATE 12/10/52

MAP T. 9897.

PROJECT NO. Ph-79(49)

SCALE OF MAP 1:10,000

SCALE FACTOR None

[illegible]

MAP T-9898 11292 PROJECT NO. Ph-49(49) SCALE OF MAP 1:10,000 SCALE FACTOR None

STATION	SOURCE OF INFORMATION (INDEX)	DATUM	LATITUDE OR Y-COORDINATE LONGITUDE OR X-COORDINATE		DISTANCE FROM GRID IN FEET, OR PROJECTION LINE IN METERS		DATUM CORRECTION	N.A. 1927 - DATUM DISTANCE FROM GRID OR PROJECTION LINE IN METERS		FACTOR DISTANCE FROM GRID OR PROJECTION LINE IN METERS
✓ CHIEF 2, 1952	Field Comp.	N.A. 1927	57 31	46.235				1430.3	(425.9)	
			135 29	30.119				501.2	(497.3)	
CHIEF 2, 1952 X	"	"	57 31					1494.5	(361.7)	
Sub. Sta. "i"			135 29					440.5	(558.0)	
✓ ELOVOI 1952	"	"	57 33	55.043				1702.9	(153.3)	
			135 27	59.533				989.7	(7.8)	
✓ BROAD 1952	"	"	57 35	09.304				287.8	(1568.4)	
			135 23	28.668				476.4	(520.5)	
✓ COVE 1952	"	"	57 33	48.816				1510.2	(346.0)	
			135 24	35.979				598.2	(399.4)	
COVE 1952	"	"	57 33					1493.2	(363.0)	
Sub. Sta. "a" X			135 24					557.8	(439.8)	
✓ CROSS 1928	"	"	57 31	22.711				703.5	(1152.7)	
			135 27	35.443				589.9	(408.8)	
✓ CRO (TOPO STATION)	"	"	57 32	40.424				1250.6	(605.6)	
			135 27	56.321				936.8	(61.2)	
CRO 1952	"	"	57 32					1256.3	(599.9)	
Sub. Sta. "a"			135 27					956.1	(41.9)	
✓ MAN (TOPO STATION)	"	"	57 33	27.612				854.2	(1002.0)	Page 14
			135 26	38.392				638.4	(359.3)	
MAN	"	"	57 33					877.2	(979.0)	
Sub. Sta. "a"			135 26					578.7	(419.0)	
✓ OTSTOLA	"	"	57 33	42.405				1311.8	(544.4)	
ISLAND LIGHT	"	"	135 26	54.144				900.2	(97.4)	

1 FT. = 3048006 METER

COMPUTED BY: FAR

DATE NOV. 1952

CHECKED BY: VES

DATE 12/11/52

MAP T- 9898	PROJECT NO. Ph-49 (49)	SCALE OF MAP 1:10,000	SCALE FACTOR None
MAP T- 9898	PROJECT NO. Ph-49 (49)	SCALE OF MAP 1:10,000	SCALE FACTOR None

[illegible]

MAP T. 9899

PROJECT NO. Ph-19(49)

SCALE OF MAP

1:10,000

SCALE FACTOR

None

STATION	SOURCE OF INFORMATION (INDEX)	DATUM	LATITUDE OR ψ -COORDINATE LONGITUDE OR x -COORDINATE		DISTANCE FROM GRID IN FEET, OR PROJECTION LINE IN METERS		DATUM CORRECTION		N.A. 1927 - DATUM DISTANCE FROM GRID OR PROJECTION LINE IN METERS		FACTOR DISTANCE FROM GRID OR PROJECTION LINE IN METERS	
ROSE 1952 ✓	Field Comp.	N.A. 1927	57 27	15.622					483.3	(1372.9)		
			135 32	33.653					561.2	(439.3)		
✓ FAY 2, 1952	"	"	57 27	12.092					374.1	(1482.1)		
			135 31	48.790					813.6	(186.9)		
✓ GIST 2, 1952	"	"	57 27	29.292					906.2	(950.0)		
			135 31	48.557					809.6	(190.8)		
✓ OPASNI 1952	"	"	57 27	35.408					1095.4	(760.8)		
			135 32	32.171					536.3	(464.0)		
✓ LING 2, 1952	"	"	57 28	10.440					323.0	(1533.2)		
			135 31	52.208					870.2	(129.9)		
✓ HUNCH 2, 1952	"	"	57 28	47.732					1476.6	(379.6)		
			135 32	46.818					780.2	(219.6)		
✓ INN 2, 1952	"	"	57 28	46.957					1452.7	(403.5)		
			135 31	51.430					857.0	(142.8)		
INN 2, 1952	"	"	57 28						1478.9	(377.3)		
Sub. Sta. "a"	"	"	135 31						852.2	(147.5)		
			57 28						311.5	(1544.7)		
LING 2, 1952	"	"	135 31						860.5	(139.6)		
Sub. Sta. "a"	"	"	57 29	32.105					992.2	(863.0)		
✓ MAT 2, 1952	"	"	135 32	22.673					377.7	(621.8)		
			57 29						951.3	(904.9)		
MAT 2, 1952	"	"	135 32						357.9	(641.6)		
Sub. Sta. "a"	"	"	57 29	34.817					1077.1	(779.1)		
✓ GOAL 2, 1952	"	"	135 33	07.575					126.2	(873.3)		

Page 16

1 FT. = 3048006 METER

COMPUTED BY: FAR

DATE NOV. 1952

CHECKED BY: YES

DATE 10/30/52

M. 2388-12

MAP T. 9899		PROJECT NO. Ph-49(49)		SCALE OF MAP 1:10,000		SCALE FACTOR None	
STATION	SOURCE OF INFORMATION (INDEX)	DATUM	LATITUDE OR ψ -COORDINATE LONGITUDE OR χ -COORDINATE	DISTANCE FROM GRID IN FEET. OR PROJECTION LINE IN METERS FORWARD (BACK)	DATUM CORRECTION	N.A. 1927 - DATUM DISTANCE FROM GRID OR PROJECTION LINE IN METERS FORWARD (BACK)	FACTOR DISTANCE FROM GRID OR PROJECTION LINE IN METERS FORWARD (BACK)
YELLOW PT. ROCK	G-9244	N.A.	57 26	57.149		1777.2 (78.9)	
DAY BEACON, 1951	P-3	1927	135 33	05.872		98.0 (902.6)	
ROSE ISLAND	Field	"	57 27	17.086		528.5 (1327.6)	
ROCK LIGHT, 1952	Comp.	"	135 32	17.000		283.5 (717.0)	
ROSE CHANNEL ROCK	"	"	57 27	41.598		1286.9 (569.3)	
DAY BEACON, 1952	"	"	135 32	51.520		858.9 (141.4)	
MULE, 1895	"	"	57 28	01.583		49.0 (1807.2)	
	"	"	135 32	59.634		994.1 (6.1)	
FEAT, 1895	G-549	"	57 26	55.228		1708.5 (147.7)	
	P-584	"	135 31	57.455		958.2 (42.4)	
FOWL, 1951	G-9244	"	57 27	10.944		338.6 (1517.6)	
	P-2	"	135 33	19.280		321.5 (679.0)	
FOWL, 1951		"	57 27			341.9 (1514.3)	
Sub. Sta. "a"		"	135 33			341.6 (658.9)	
FETCH, 1895	G-9244		57 26	54.951		1700.0 (156.2)	
	P-2		135 32	58.324		972.7 (27.9)	
ROB 2, 1951	"	"	57 26	00.130		4.0 (1852.1)	
	P-1	"	135 34	56.306		939.4 (61.6)	
MIDDLE 2, 1951	"	"	57 26	20.200		624.9 (1231.3)	Page
	"	"	135 34	07.923		132.1 (868.9)	17
ARTHUR 2, 1951	"	"	57 26	54.650		1690.7 (165.5)	
	"	"	135 34	38.593		643.7 (357.0)	
YELLOW 2, 1951	"	"	57 26	53.006		1639.8 (216.4)	
	P-2	"	135 33	35.237		589.4 (411.3)	

1 FT. = 3048006 METER

COMPUTED BY: FAR

DATE: NOV. 1952

CHECKED BY: VES

DATE: 10/30/52

MAP T. 9899

PROJECT NO. Ph-49(49)

SCALE OF MAP 1:10,000

SCALE FACTOR None

STATION	SOURCE OF INFORMATION (INDEX)	DATUM	LATITUDE OR Y-COORDINATE LONGITUDE OR X-COORDINATE		DISTANCE FROM GRID IN FEET. OR PROJECTION LINE IN METERS		DATUM CORRECTION	N.A. 1927 - DATUM DISTANCE FROM GRID OR PROJECTION LINE IN METERS		FACTOR DISTANCE FROM GRID OR PROJECTION LINE IN METERS	
					FORWARD	(BACK)		FORWARD	(BACK)	FORWARD	(BACK)
✓ JAN 2, 1951	G-9244 P-2	N.A. 1927	57 27	12.973				401.3	(1454.8)		
✓ MIDDLE POINT	"	"	135 33	55.045				917.9	(2.6)		
✓ LIGHT, 1951	P-3	"	57 26	21.840				675.6	(1180.5)		
✓ HEART, 1951	"	"	135 34	21.534				359.2	(641.7)		
	P-4	"	57 26	11.429				353.6	(1502.6)		
	"	"	135 35	36.157				603.2	(397.8)		
✓ DRINK, 1951	"	"	57 26	13.737				425.0	(1431.2)		
	P-4	"	135 36	48.204				804.1	(196.8)		
✓ KAPOK, 1951	"	"	57 26	27.368				846.7	(1009.5)		
	"	"	135 36	18.468				308.1	(692.8)		
✓ MASON, 1951	"	"	57 26	45.512				1408.0	(448.2)		
	"	"	135 37	04.652				77.6	(923.1)		
✓ LANCE, 1951	"	"	57 26	31.397				971.3	(884.9)		
	"	"	135 37	45.856				764.8	(235.9)		
✓ GREEN, 1951	"	"	57 27	03.939				121.8	(1734.3)		
	"	"	135 38	15.354				256.1	(744.6)		
✓ MENTO, 1951	"	"	57 26	06.584				203.7	(1652.5)		
	"	"	135 33	02.868				47.8	(953.2)		
✓ MOO, 1951	Field Comp.		57 26	07.28				225.2	(1630.9)		
			135 35	17.27				288.1	(713.0)		
✓ CAB, 1951	"	"	57 26	14.81				458.2	(1398.0)		
	"	"	135 34	02.24				37.4	(963.6)		
✓ SET, 1951	"	"	57 26	08.03				248.4	(1607.7)		
	"	"	135 36	14.52				242.2	(758.8)		

1 FT. = 3048006 METER

COMPUTED BY: FAR

DATE NOV. 1952

CHECKED BY: VES

DATE 10/30/52

M-2388-12

SCALE FACTORNone

STATION	SOURCE OF INFORMATION (INDEX)	DATUM	LATITUDE OR y-COORDINATE LONGITUDE OR x-COORDINATE	DISTANCE FROM GRID IN FEET. OR PROJECTION LINE IN METERS		DATUM CORRECTION	N.A. 1927 - DATUM DISTANCE FROM GRID OR PROJECTION LINE IN METERS		FACTOR DISTANCE FROM GRID OR PROJECTION LINE IN METERS	
				FORWARD	(BACK)		FORWARD	(BACK)	FORWARD	(BACK)
✓ TOM, 1951	Field Comp.	N.A. 1927	57 26 05.81 135 36 07.86				179.7 (1676.4) 131.1 (869.9)			
✓ NIT, 1951	" <i>216 945</i> <i>10 003</i>	"	57 26 36.88	<i>Position does not agree with Angles in 6-9244 R.E.E. 5-16-55</i>			1140.9 (715.2)			
			135 36 38.41			640.8 (360.1)				
✓ YES, 1951	"	"	57 26 23.40 135 36 02.16				723.9 (1132.3) 36.0 (964.9)			
✓ HER, 1951 (1)	"	"	57 26 57.00 135 38 50.17				1763.4 (92.8) 836.7 (163.9)			
✓ VIM, 1951	"	"	57 26 58.75 135 37 33.44				1817.5 (38.7) 557.6 (443.2)			
✓ ODD, 1951	"	"	57 26 42.83 135 38 14.26				1325.0 (531.2) 237.8 (762.8)			
✓ WHO, 1951	"	"	57 26 18.94 135 35 48.68				585.9 (1270.2) 812.1 (188.9)			
✓ PIE, 1951	"	"	57 26 21.40 135 37 21.42				662.0 (1194.1) 357.3 (643.6)			
✓ DAW, 1951	"	"	57 26 11.51 135 33 41.52				356.1 (1500.1) 692.7 (308.3)			
✓ TAX, 1951	"	"	57 26 54.56 135 34 46.56				1687.9 (168.3) 776.5 (224.3)			Page 19
✓ ZAG, 1951	"	"	57 26 31.95 135 35 56.26				988.4 (867.8) 938.5 (62.4)			
✓ PIN, 1951	"	"	57 26 12.03 135 34 59.25				372.2 (1484.0) 988.5 (123)			

1 FT. = 3048006 METER

COMPUTED BY.

DATE NOV. 1952

CHECKED BY: VES

DATE.....10/30/52.....

M-2388-12

MAP T- 9899

PROJECT NO.

Ph-49(49)

SCALE OF MAP 1:10,000

SCALE FACTOR

None

[illegible]

MAP T. 9900

PROJECT NO. Ph-49(49)

SCALE OF MAP 1:10,000

SCALE FACTOR None

STATION	SOURCE OF INFORMATION (INDEX)	DATUM	LATITUDE OR ψ -COORDINATE LONGITUDE OR λ -COORDINATE		DISTANCE FROM GRID IN FEET, OR PROJECTION LINE IN METERS		DATUM CORRECTION	N.A. 1927 - DATUM DISTANCE FROM GRID OR PROJECTION LINE IN METERS		FACTOR DISTANCE FROM GRID OR PROJECTION LINE IN METERS	
✓ FINAL, 1950	G-8876 pg 6.	N.A. 1927	57 24	17.879				553.1	(1303.1)		
✓ GRAG, 1895 - 1950	" pg 7	"	135 36	11.101				185.4	(816.5)		
✓ ILAND, 1950	"	"	57 24	03.344				103.4	(1752.8)		
✓ BOON 2, 1950	"	"	135 37	53.378				891.4	(110.6)		
✓ SERGIUS 2, 1950	"	"	57 23	53.275				1648.1	(208.0)		
✓ SHE 2, 1950	"	"	135 39	26.012				434.4	(567.7)		
✓ TODDY, 1950	"	"	57 24	20.763				642.3	(1213.9)		
✓ UNDER, 1950	"	"	135 39	02.271				37.9	(964.0)		
✓ STROP, 1950	"	"	57 24	27.716				857.4	(998.8)		
✓ MOUNTAIN 2, 1950	"	"	135 37	57.262				956.1	(45.7)		
✓ SHOAL 2, 1950	"	"	57 24	13.633				421.8	(1434.4)		
✓ SERGIUS NARROWS LIGHT, 1950	"	"	135 36	49.554				827.5	(174.4)		
	"	"	57 23	50.641				1566.6	(289.5)		
	"	"	135 40	17.976				300.2	(701.9)		
	"	"	57 24	23.560				728.9	(1127.2)		
	"	"	135 40	31.072				518.8	(483.0)		
	"	"	57 24	28.786				890.5	(965.7)		
	"	"	135 37	45.206				754.8	(247.0)		
	"	"	57 24	33.051				1022.5	(833.7)		
	"	"	135 36	17.895				298.8	(703.0)		
	"	"	57 24	35.841				1108.8	(747.4)		
	"	"	135 37	22.432				374.5	(627.3)		
	"	"	57 24	28.85				892.5	(963.7)		
	"	"	135 37	45.12				753.4	(248.4)		

Page 21

1 FT. = 3048006 METER

COMPUTED BY: RAD

DATE DEC. 1951

CHECKED BY: HJA

DATE 12/25/51

M-2368-12

MAP T. 9900

PROJECT NO. Ph-49(49)

SCALE OF MAP 1:10,000

SCALE FACTOR None

STATION	SOURCE OF INFORMATION (INDEX)	DATUM	LATITUDE OR ν -COORDINATE LONGITUDE OR x -COORDINATE		DISTANCE FROM GRID IN FEET. OR PROJECTION LINE IN METERS		DATUM CORRECTION		N.A. 1927 - DATUM DISTANCE FROM GRID OR PROJECTION LINE IN METERS		FACTOR DISTANCE FROM GRID OR PROJECTION LINE IN METERS	
					FORWARD	(BACK)			FORWARD	(BACK)	FORWARD	(BACK)
✓ WINDS, 1950	G-8876 pg 4	N.A. 1927	57	22	01.272				39.4	(1816.7)		
			135	43	18.184				303.9	(699.0)		
✓ GRIP, 1896 - 1950	"	"	57	22	09.830				304.1	(1552.0)		
			135	42	09.643				161.2	(841.6)		
✓ BORE 2, 1950	"	"	57	22	16.849				521.2	(1334.9)		
			135	41	08.695				145.3	(857.5)		
✓ CLOCK 2, 1950	"	"	57	22	25.958				803.0	(1053.1)		
			135	41	33.625				561.9	(440.8)		
✓ ACHE 2, 1950	"	"	57	22	35.870				1109.7	(746.4)		
			135	41	10.827				180.9	(821.8)		
✓ GEMOT, 1950	"	"	57	22	24.779				766.6	(1089.5)		
			135	40	55.313				924.4	(78.3)		
✓ FRESH, 1950	"	"	57	23	05.420				167.7	(1688.4)		
			135	40	43.654				729.3	(273.2)		
✓ STRUYA, 1950	" pg 5	"	57	22	52.275				1617.2	(238.9)		
			135	40	04.060				67.8	(934.8)		
✓ STRONG, 1950	"	"	57	22	28.132				870.3	(985.8)		
			135	39	34.570				577.7	(425.0)		
✓ COVEY, 1950	"	"	57	23	06.668				206.3	(1649.8)	Page	
			135	39	57.054				953.2	(49.2)	22	
✓ ACTIVE, 1950	"	"	57	22	03.308				102.3	(1753.8)		
			135	39	58.061				970.5	(32.4)		
✓ CLOUD, 1950	"	"	57	22	52.578				1626.5	(229.6)		
			135	39	48.767				814.8	(1871.7)		

1 FT. = 3048006 METER

COMPUTED BY RAD

DATE DEC. 1951

CHECKED BY HJA

DATE 12/29/51

MAP T- 9900

PROJECT NO Ph-49(49)

SCALE OF MAP 1:10,000

SCALE FACTOR None

STATION	SOURCE OF INFORMATION (INDEX)	DATUM	LATITUDE OR Y-COORDINATE LONGITUDE OR X-COORDINATE		DISTANCE FROM GRID IN FEET. OR PROJECTION LINE IN METERS		DATUM CORRECTION	N.A. 1927 - DATUM FROM GRID OR PROJECTION LINE IN METERS		FACTOR DISTANCE FROM GRID OR PROJECTION LINE IN METERS	
					FORWARD	(BACK)		FORWARD	(BACK)	FORWARD	(BACK)
✓ KAKUL NARROWS LIGHT, 1950	Q-8876 pg 5	N.A. 1927	57 22	27.109				838.6	(1017.5)		
RANGE, 2, 1950 ✓	"	"	135 40	54.449				910.0	(92.7)	4	55
CLIP 2, 1950 ✓	"	"	57 22	30.831				953.8	(902.3)		
	"	"	135 39	18.670				312.0	(690.7)		
	"	"	57 22	25.135				777.6	(1078.5)		
	"	"	135 37	31.221				521.8	(480.9)		
CABAL, 1950 ✓	"	"	57 23	35.278				1094.5	(761.7)		
	"	"	135 37	46.213				771.9	(230.3)		
ABYSS, 1950 ✓	"	"	57 23	17.257				533.9	(1322.2)		
	"	"	135 37	03.408				56.9	(945.5)		
SULOIA 2, 1950 ✓	pg 6	"	57 23	25.647				793.4	(1062.7)		
	"	"	135 38	52.615				878.9	(1231.4)		
BLUFF, 1950 ✓	"	"	57 23	10.582				327.4	(1528.7)		
	"	"	135 36	44.959				751.1	(251.3)		
HALEY, 1950 ✓	"	"	57 22	20.190				624.6	(1231.5)		
	"	"	135 36	13.429				224.4	(778.3)		
SCHULZE, 1950 ✓	"	"	57 23	18.427				570.1	(1286.0)		
	"	"	135 36	16.323				272.7	(729.7)		
PIPER, 1950 ✓	"	"	57 23	25.977				803.6	(1052.5)		
	"	"	135 35	45.094				753.3	(249.0)		
EATER, 1950 ✓	"	"	57 23	43.768				1354.0	(502.2)		
	"	"	135 36	13.125				219.2	(782.9)		
DEBUT, 1950 ✓	"	"	57 24	00.570				17.6	(1828.0)		
	"	"	135 35	44.290				739.6	(262.4)		

Page 23

1 FT. = 3048006 METER

COMPUTED BY: RAD

DATE DEC, 1951

CHECKED BY: HJA

DATE 12/28/51

M-2388-12

MAP T. 9900

PROJECT NO. Ph-49(49)

SCALE OF MAP 1:10,000

SCALE FACTOR None

STATION	SOURCE OF INFORMATION (INDEX)	DATUM	LATITUDE OR ψ -COORDINATE LONGITUDE OR λ -COORDINATE		DISTANCE FROM GRID IN FEET, OR PROJECTION LINE IN METERS		DATUM CORRECTION		N.A. 1927 - DATUM DISTANCE FROM GRID OR PROJECTION LINE IN METERS		FACTOR DISTANCE FROM GRID OR PROJECTION LINE IN METERS	
BAR, 1896 ✓	G-549 583	N.A. 1927	57 22	54.299					1679.6	(176.3)		
✓ CHANNEL, 1896-1928	"	"	135 39	37.763					631.0	(371.5)		
GRIP, 1896, 1925, 1928 ✓	"	"	57 22	21.809					674.7	(1181.4)		
ACE, 1896 ✓	"	"	135 40	56.529					944.7	(58.1)		
	"	"	57 22	09.823					303.9	(1552.2)		
	"	"	135 42	09.646					161.2	(841.6)		
	"	"	57 23	23.383					723.4	(1132.7)		
	584	"	135 37	38.588					644.6	(357.7)		
CORN, 1895 ✓	G-549 582	"	57 24	04.107					127.1	(1729.1)		
✓ FISH, 1895, 1896	"	"	135 37	25.164					420.2	(581.8)		
	"	"	57 23	40.452					1251.4	(604.8)		
	"	"	135 37	47.438					792.4	(209.8)		
✓ LIESNOI 2, 1951	G-9244 P 1	"	57 25	08.321					257.4	(1598.6)		
	"	"	135 36	16.827					280.9	(720.7)		
✓ SIROI 2, 1951	"	"	57 25	09.508					294.1	(1561.9)		
	"	"	135 35	13.389					223.5	(778.1)		
✓ LITTLE, 1895, 1951	"	"	57 25	40.987					1268.0	(588.2)		
	"	"	135 35	30.264					505.0	(496.2)		
DEEP BAY ENTRANCE	"	"	57 25	59.106					1828.5	(27.6)		
DAYBEACON, 1951	P 3	"	135 35	29.719					495.9	(505.2)		
✓ ELOPE, 1951	"	"	57 25	59.958					1854.9	(01.3)		
	P 4	"	135 36	07.612					127.0	(874.1)		
✓ BOX, 1951	Field	"	57 25	03.26					100.9	(1755.3)		
	Contd.	"	135 37	16.70					278.7	(722.7)		

1 FT. = 3048006 METER

COMPUTED BY: RAD & JIH

DATE DEC. 1951 JAN. 1952

CHECKED BY: JHA

DATE 12/29/51

M-2388-12

MAP T. 9900

PROJECT NO. Ph-49(49)

SCALE OF MAP 1:10,000

SCALE FACTOR None

STATION	SOURCE OF INFORMATION (INDEX)	DATUM	LATITUDE OR μ -COORDINATE LONGITUDE OR x -COORDINATE		DISTANCE FROM GRID IN FEET, OR PROJECTION LINE IN METERS		DATUM CORRECTION	N.A. 1927 - DATUM DISTANCE FROM GRID OR PROJECTION LINE IN METERS		FACTOR DISTANCE FROM GRID OR PROJECTION LINE IN METERS	
					FORWARD	(BACK)		FORWARD	(BACK)	FORWARD	(BACK)
CUT, 1951	Field	N.A.	57	25	17.48			540.8	(1315.4)		
	COMP.	1927	135	36	37.63			628.3	(373.2)		
GAD, 1951	"	"	57	24	54.17			1675.8	(180.4)		
			135	35	11.86			198.0	(803.6)		
(1) 200, 1951 ✓	"	"	57	24	46.34			1433.6	(422.6)		
			135	35	22.84			381.3	(620.4)		
PEP, 1951 ✓	"	"	57	25	08.06			249.3	(1606.7)		
			135	35	01.14			19.0	(982.6)		
FEZ, 1951 ✓	"	"	57	25	50.38			1558.6	(297.6)		
			135	35	37.04			618.0	(383.1)		
GAS, 1951 ✓	"	"	57	25	56.31			1742.0	(114.2)		
			135	35	52.45			875.2	(125.9)		
BOB, 1951	"	"	57	25	52.10			1611.8	(244.4)		
			135	36	09.83			164.0	(837.0)		
DEN, 1950 ✓	"	"	57	24	02.53			78.3	(1777.9)		
			135	37	17.66			294.9	(707.1)		
ERA, 1951	"	"	57	25	56.25			1740.2	(116.0)		
			135	36	18.52			309.0	(692.1)		
HUB, 1950 ✓	"	"	57	24	02.36			73.0	(1783.2)		
			135	37	42.29			706.2	(295.8)		
IDA, 1951	"	"	57	24	29.79			921.6	(934.6)		
			135	36	22.24			371.4	(630.4)		
KIM, 1950 ✓	"	"	57	23	52.77			1632.5	(223.7)		
			135	37	47.33			790.1	(211.6)		

1 FT. = 3048006 METER

COMPUTED BY: FAR

DATE OCT. 1952

CHECKED BY: VES

DATE NOV. 1952

MAP T- 9900

PROJECT NO. Ph-49(49)

SCALE OF MAP 1:10,000

SCALE FACTOR None

STATION	SOURCE OF INFORMATION (INDEX)	DATUM	LATITUDE OR ψ -COORDINATE LONGITUDE OR χ -COORDINATE	DISTANCE FROM GRID IN FEET. OR PROJECTION LINE IN METERS FORWARD (BACK)	DATUM CORRECTION	N.A. 1927 - DATUM DISTANCE FROM GRID OR PROJECTION LINE IN METERS FORWARD (BACK)	FACTOR DISTANCE FROM GRID OR PROJECTION LINE IN METERS FORWARD (BACK)
LEG, 1951 ✓	Field	N.A.	57 24 12.36			382.4 (1473.8)	
	Comp.	1927	135 37 38.22			638.2 (363.7)	
✓ (1) LEO, 1951	"	"	57 24 04.37			135.2 (1720.9)	
	"	"	135 37 25.29			422.3 (579.6)	
NAT, 1951 ✓	"	"	57 24 14.03			434.0 (1422.1)	
	"	"	135 37 52.70			880.0 (121.9)	
PIX, 1950 ✓	"	"	57 24 01.22			37.8 (1818.4)	
	"	"	135 36 55.78			931.5 (70.5)	
POT, 1951 ✓	"	"	57 24 15.07			466.2 (1390.0)	
	"	"	135 37 48.34			806.8 (194.9)	
RIG, 1950 ✓	"	"	57 24 19.20			594.0 (1262.2)	
	"	"	135 36 28.22			471.4 (530.5)	
✓ SIP, 1951	"	"	57 24 33.34			1031.4 (824.8)	
	"	"	135 37 34.99			584.2 (417.5)	
✓ SOW, 1951	"	"	57 24 32.20			996.1 (860.0)	
	"	"	135 38 34.03			568.2 (433.6)	
✓ TAN, 1951	"	"	57 24 32.61			1008.8 (847.3)	
	"	"	135 38 11.74			196.0 (805.7)	
✓ TAP, 1950	"	"	57 24 11.49			355.5 (1500.7)	26
	"	"	135 36 36.84			615.2 (386.7)	
✓ WAX, 1950	"	"	57 24 24.90			770.3 (1085.9)	
	"	"	135 38 41.63			695.1 (306.7)	
FAR, 1951	"	"	57 24 44.64			1384.1 (472.1)	
	"	"	135 35 43.27			722.4 (279.3)	

1 FT. = 3048006 METER

COMPUTED BY: FAR

DATE OCT, 1952

CHECKED BY: YES

DATE NOV, 1952

SCALE FACTOR None

[illegible]

MAP T. 9901

PROJECT NO. Ph-49(49)

SCALE OF MAP 1:10,000

SCALE FACTOR None

STATION	SOURCE OF INFORMATION (INDEX)	DATUM	LATITUDE OR ψ -COORDINATE LONGITUDE OR λ -COORDINATE	DISTANCE FROM GRID IN FEET. OR PROJECTION LINE IN METERS FORWARD (BACK)	DATUM CORRECTION	N.A. 1927 - DATUM DISTANCE FROM GRID OR PROJECTION LINE IN METERS FORWARD (BACK)	FACTOR DISTANCE FROM GRID OR PROJECTION LINE IN METERS FORWARD (BACK)
GALLEY, 1950 ✓	G-8876 P 6.	N.A. 1927	57 22 40.310 135 32 50.831			1247.0 (609.1) 849.4 (153.2)	
KARAT, 1950 ✓	" P 7	"	57 22 10.079 135 30 33.771			311.8 (1544.3) 564.4 (438.4)	
FOX 2, 1951 ✓	G-9244 P 1	"	57 25 37.187 135 34 27.983			1150.4 (705.7) 467.0 (534.3)	
REX 2, 1951 ✓	"	"	57 25 58.233 135 33 53.361			1801.5 (54.7) 890.3 (110.8)	
CABLE, 1951 ✓	" P 4	"	57 25 41.598 135 34 02.077			1286.9 (569.3) 34.7 (966.4)	
ABORT, 1951 ✓	" P 5	"	57 25 20.130 135 34 28.538			622.8 (1233.4) 476.3 (525.1)	
DEBIT, 1951 ✓	"	"	57 25 07.581 135 33 55.666			234.5 (1621.6) 929.2 (72.4)	
(1) VAL, 1951 ✓ (Hydro)	Field Comp.	N.A. 1927	57 25 22.22 135 33 38.41			687.4 (1168.8) 641.1 (360.3)	
(1) USE, 1951 ✓ (Hydro)	"	"	57 25 20.23 135 34 03.46			625.8 (1230.3) 57.7 (943.7)	
WAG, 1951 ✓ (Hydro)	"	"	57 25 05.77 135 34 18.66			178.5 (1677.7) 311.5 (690.1)	Page 28
RIM, 1951 ✓ (Hydro)	"	"	57 25 01.54 135 34 53.55			47.6 (1808.5) 893.9 (107.7)	
TOY, 1951 ✓ (Hydro)	"	"	57 25 07.81 135 34 40.90			241.6 (1614.4) 682.7 (318.8)	

1 FT. = .3048006 METER

COMPUTED BY: J.L.H.

DATE 2/26/52

CHECKED BY: JED

DATE 2/26/ 52

MAP T-9901...

PROJECT NO. Ph-49(49)

SCALE OF MAP 1:10,000

SCALE FACTOR

[illegible]

1 FT = 3048006 METER

COMPUTED BY: FAR

DATE NOV. 1952

CHECKED BY: VES

DATE 10/31/52

M-2388-12

SCALE FACTOR

Page 30

COMPILATION REPORT

Map Manuscripts No's. T-9896 thru T-9902

Project Ph - 49(49)

Sub-headings 31, 32, 34, and 36 of the Descriptive Report for Map Manuscript No. T-8475, Project Ph-49(49), (1948 and 1949) are in general applicable.

33. SUPPLEMENTAL DATA:

Graphic control surveys used to supplement the photographs are as follows:

PA-A-51	Scale, 1:5000
PA-A-52	Scale, 1:5000
PA-B-52	Scale, 1:5000
PA-C-52	Scale, 1:10,000

A rock which bares 5 ft. at M.L.L.W. was transferred from PA-A-51, Scale 1:5000 to T-9901, Scale, 1:10,000 by graphic intersection. Data of Field Print No. 10596 was disregarded at this place.

The shoreline northeast from station CRO, 1952 on T-9898 had been delineated on graphic control sheet PA-A-52 at a scale of 1:5000. A junction was made with this planimetry.

Shoreline shown on PA-B-52, Scale 1:5000 was reduced to Scale 1:10,000 by use of the vertical projector and then traced on T-9899.

Shoreline of Hogatt Island was traced from PA-C-52, Scale 1:10,000 on T-9897.

A photostat print of boat sheet PA-1151 (Reg. No. H-7931), Ship "PATTON", CS-247 was used to supplement the field inspection data.

35. SHORELINE AND ALONGSHORE DETAILS:

The field inspection of shoreline during the 1952 field season was done very meticulously. Additional data found in the descriptions of horizontal control stations were applied when locating the mean high-water line. Planetable locations of the mean high-water line and various rocks were transferred to the map manuscripts.

No attempt was made to delineate rocks not field inspected or not shown on the graphic control sheets because it was believed that these have been covered during the hydrographic survey which was completed prior to shoreline compilation.

Data from boat sheets was not furnished the compilation office north of Latitude $57^{\circ} 27' 20''$ which includes most of the area of T-9899 and all of T-9896 thru T-9898.

Refer to remarks contained in "Notes to the Reviewer" included in this descriptive report.

37. LANDMARKS AND AIDS:

Refer to sub-heading 9 "Landmarks and Aids" of the 1952 field inspection report.

38. CONTROL FOR FUTURE SURVEYS:

Forms 524 are submitted for Recoverable Topographic Stations VET, 1952 and NOT, 1952 which fall within the limits of T-9896.

Refer to sub-heading 11 of the 1952 field inspection report for additional information. The Form 524 listed for station FOX was not furnished the compilation office.

39. JUNCTION S:

Satisfactory junctions have been made between all map manuscripts covered by this report and with T-8485. A junction also was made with planimetry on T-9898 and that shown on graphic control sheet PA-A-52.

40. HORIZONTAL AND VERTICAL ACCURACY:

There are no shoreline areas of this map manuscript believed to be of sub-normal horizontal accuracy.

Disagreements in the location of the west shoreline of Peril Strait north from Ushk Bay were satisfactorily resolved when the photogrammetric office was furnished, by the Seattle Processing Office, several sextant fix locations contained in the hydrographic survey data.

Interior horizontal accuracy and vertical accuracy are not applicable.

46. COMPARISON WITH EXISTING MAP:

Comparison was made with all graphic control surveys listed under sub-heading 33 of this report.

Comparison was made between shoreline manuscript RS-427, Scale 1:10,000 and T-9897. The shoreline details of T-9897 supercede RS-427.

47. COMPARISON WITH NAUTICAL CHARTS:

A comparison was made with Nautical Chart No. 8248, Scale, 1:40,000, Published Feb. 1931 (2nd Edition) last corrected 1/22/51.

At Latitude $57^{\circ} 24' 50''$ and Longitude $135^{\circ} 37' 10''$ there is a small island on the chart which has been designated by field inspection as not being detached from the mainland. Office examination of the photographs does not clarify this disagreement. T-9900 (APPENINSULA, at OABE 1951)

Other features are in good general agreement between the chart and map manuscript.

Numerous disagreements in the locations of rocks between the chart and map manuscripts have not been listed because it is believed that satisfactory locations and data have now been submitted by field inspection and hydrographic survey for all rocks to be charted in this area.

Approved and forwarded;

Fred A. Riddell

Fred A. Riddell
Officer-in-Charge

Respectfully submitted;

J. Edward Deal Jr.

J. Edward Deal, Jr.
Cartographer

48. GEOGRAPHIC NAMES:

The geographic names report listed under sub-heading 13 of the 1952 field inspection report was not furnished the photogrammetric Office

All names shown on the map manuscripts were obtained from Nautical Chart No. 8248 and are shown for location purposes only.

Approved name lists:

For all sheets, titles:

Southeastern Alaska
First Judicial Division

T-9896:

Chichagof Island ✓
Ushk Bay ✓

T-9897:

• Baranof Island ✓
• Chichagof Island ✓
• Peril Strait ✓
• Poison Cove ✓
• Pogibshi Point ✓
• Goose Cove ✓ (not Pogibshi Anchorage)
• Point Marie ✓
• Dolph Rock -
• Hoggatt Reefs ✓
• Hoggatt Island ✓
• Ford Rock -
• Ushk Bay ✓
• Ushk Point ✓
• Rodgers Point ✓
Povorotni Island. ✓

T-11,292:

Peril Strait ✓
Deadman Reach ✓
Baranof Island ✓

T-9899:

• Baranof Island ✓
• Chichagof Island ✓
• Peril Strait ✓
• Nixon Shoal ✓
• Little Rose Island ✓
• Big Rose Island ✓ (omit Opasni Islands)
• Rose Channel ✓
• Rapids Point ✓
• Adams Channel ✓
• Range Creek ✓
• Yellow Point ✓
• Arthur Island ✓
• Middle Point ✓
• Baby Bear Bay ✓
• Big Island ✓
• Deep Bay ✓

Names approved
1-25-54
L. Hock

T-9900:

- Baranof Island ✓
- Chichagof Island ✓
- Peril Strait ✓
- Little Island ✓
- Grasstop Rock ✓
- Liesnoi Island ✓
- Midway Rock ✓
- Point Siroi ✓
- Mountain Head ✓
- Shoal Point ✓
- Sergius Point ✓
- Sergius Narrows ✓
- Sergius Channel ✓
- Rapids Island ✓
- Canoe Pass ✓
- Pinta Head ✓
- Launch Cove ✓ Island Point ✓
- Schulze Cove ✓
- Piper Island ✓
- Near Point ✓
- Schulze Head ✓
- Fish Point ✓
- Fish Bay ✓
- Haley Point ✓
- Haley Anchorage ✓
- Haley Rock ✓
- Range Point ✓
- Louise Cove ✓
- Channel Rocks ✓
- Kakul Narrows ✓
- Krugloi Islands ✓
- Round Island ✓
- Salmonberry Cove ✓
- Bradshaw Cove ✓
- Struya Point ✓
- Suloia Point ✓
- Suloia Bay ✓
- Point Sinbad ✓
- Suloia Island ✓

T-9901:

- Baranof Island ✓
- Peril Strait ✓
- Baby Bear Bay ✓
- Bear Bay Island ✓
- Bear Bay ✓
- Fish Bay ✓

T-9902:

- Baranof Island ✓
- Fish Bay ✓

Names approved
1-25-54. L. HICK

PHOTOGRAMMETRIC OFFICE REVIEW

T-9896 thru T-9902

1. Projection and grids ☒ 2. Title ☒ 3. Manuscript numbers ☒ 4. Manuscript size ☒

CONTROL STATIONS

5. Horizontal control stations of third-order or higher accuracy ☒ 6. Recoverable horizontal stations of less than third-order accuracy (topographic stations) ☒ 7. Photo hydro stations 7 8. Bench marks 7 9. Plotting of sextant fixes ☒ 10. Photogrammetric plot report ☒ 11. Detail points ☒

ALONGSHORE AREAS

(Nautical Chart Data)

12. Shoreline ☒ 13. Low-water line ☒ 14. Rocks, shoals, etc. ☒ 15. Bridges 7 16. Aids to navigation ☒ 17. Landmarks ☒ 18. Other alongshore physical features ☒ 19. Other along-shore cultural features ☒

PHYSICAL FEATURES

20. Water features ☒ 21. Natural ground cover 7 22. Planetable contours 7 23. Stereoscopic Instrument contours 7 24. Contours in general 7 25. Spot elevations 7 26. Other physical features ☒

CULTURAL FEATURES

27. Roads 7 28. Buildings 7 29. Railroads 7 30. Other cultural features ☒

BOUNDARIES

31. Boundary lines 7 32. Public land lines 7

MISCELLANEOUS

33. Geographic names ☒ 34. Junctions ☒ 35. Legibility of the manuscript ☒ 36. Discrepancy overlay 7 37. Descriptive Report ☒ 38. Field inspection photographs ☒ 39. Forms ☒ 40. _____

Reviewer

J. Edward Deal Jr.
Supervisor, Review Section or Unit

41. Remarks (see attached sheet) * taken from nautical chart # 8248

FIELD COMPLETION ADDITIONS AND CORRECTIONS TO THE MANUSCRIPT

42. Additions and corrections furnished by the field completion survey have been applied to the manuscript. The manuscript is now complete except as noted under item 43.

Compiler_____
Supervisor

43. Remarks:

M-2623-12

NOTES TO THE REVIEWER

Recently prints of Map Manuscripts T-8484 and T-8485, Project Ph-49(49) were furnished the Portland Photogrammetric Office on which notes of criticism by the Washington Office Review Section and comments by Mr. Bennett G. Jones had been entered.

During the compilation and review of map manuscripts covered by this report, we have endeavored to comply with the recommendations entered on above mentioned prints and to omit superfluous notes and symbols. Only annotations considered helpful for clarification of detail for the nautical chart have been made.

Where rocks, designated by field inspection, are not shown in foul areas it is because they cannot be seen on the photographs and a clarifying note is shown.

Where the type of foreshore area has not been labeled, it is because no data was furnished by field inspection and the type could not be accurately determined in the office.

Where field inspection notes have been added designating a beach or foreshore area and the limits are not shown, it is because only high-water photographs were available and the limits could not be seen.

The hachure symbol recommended on the prints for slides has been used on these map manuscripts. However, the personnel at this office are of the opinion that the symbol as shown represents a ravine and the note "slide" has been added for clarification. In the northwest, slides more often are not ravines, but convex or rounded masses of earth and stone that have broken off from the younger soft rock beneath the old hard rock surface. This material has piled up below at a different slope or gradient leaving a wide scar along the path in which it has traveled. The symbol for this feature shown on Nautical Chart No. 8248 is believed to more clearly represent a "slide" and would not require a clarifying note.

We believe, however, that much of the criticism noted by the review section was made without thorough examination of the field inspection photographs and also that they did not take into account the fact that only high water photographs were available for the compilation work.

Review Report
Shoreline Surveys
T-9896, T-9897, T-9899, T-9900, T-9901,
T-9902, T-11292
27 January 1958⁴

62. Comparison with Registered Surveys.-

T-2225 1:40,000, 1895 (with contours), Pogibshi Pt.
northward.
T-2226 1:20,000, 1895 (shoreline), Suloia Bay - Pogibshi Pt.
T-2239 1:20,000, 1895, (with contours) supersedes T-2226
T-2247 1:20,000, no date, (shoreline), Fish Bay
T-2289 1:40,000, 1896-7 (with contours) Sergius Narrows -
Old Sitha Rocks

No major discrepancies exist. The present shoreline surveys supersede the older surveys for charting purposes except for contours and bluffs.

63. Comparison with Maps of Other Agencies.- There are no authoritative maps or surveys of this area other than those listed under items 62 and 65.

64. Comparison with Contemporary Hydrographic Surveys.-

HW Line applied subsequent to review

H-7860	1:5,000	1950	Kakul Narrows
H-7861	1:10,000	1950	E. Salisbury Sd., Fish Bay, Suloia Bay
H-7930	1:5,000	1951	Sergius Narrows
H-7931	1:10,000	1951	Mountain Head to Yellow Point
	1:5,000	1951	(insert) Baby Bear Bay
H-7985	1:5,000	1952	Favorite Anchorage thru Nismeni Cove.
H-7986	1:10,000	1952	Yellow Pt. to Vie Rose Islands
	1:5,000	1952	Rose Islands to Pogibshi Pt.
H-7988	1:10,000	1952	Pogibshi Pt. to vie Broad Island
H-7989	1:10,000	1952	Ushk Bay

At the time of review only H-7985 and H-7988 had the shoreline applied: H-7985 from a planetable survey, and H-7988 from map manuscript T-9897 which was compiled after field inspection.

Rocks and ledges on the map manuscripts supplement those on the hydrographic surveys. Many rock elevations were changed during review. Tide curves were drawn for the times of rock and ledge inspection (1952) using tidal difference values established as a result of tide observations during the 1952 field season and appearing in the 1953 Tide Tables.

South of 57° 29' the curves were from Reference Station Sitka, Subordinate Station Bear Bay. North of that latitude the curves were from Reference Station JUNEAU, Subordinate Station Pogibshi Anchorage.

In Feb. 1955, the rock bearings were revised north of 57° 27½' (Rose Channel) using Pogibshi Anchorage (MHW = 140)

Between Rose Channel and Big Island a mean (12.7) of Pogibshi (140) and Bear Bay (11.5) was used.

South of Big Island the Bear Bay station was used.

These revisions occur in T-9896, T-9897, T-9899, T-9900, and T-11292. Where no changes were made, field notes had stated the MHW or MLLW relationship without reference to day, hour, or height.

65. Comparison with Nautical Charts.-

8248 1:40,000, ed. Feb. 1931, rev. Jan. 1951

The shoreline is in general agreement except that in the section of Peril Strait between Yellow Point and Pogibshi the shoreline indentations have advanced due to silting. Some rocks and ledges are not on the map manuscripts because they were not visible on the photographs and were not field inspected. Wherever the photographs suggested covered ledges, and the chart bore out the evidence, a dashed line was delineated during review. The contemporary hydrographic surveys give complete coverage of these areas.

66. Accuracy.- The radial plot was well controlled, field inspection of shoreline was thorough and delineation good. Only minor changes were made to shoreline. Rock clearing differences were discussed under Heading 64. These maps comply with project instructions and meet the National Standards of Map Accuracy.

Reviewed by:

Lena T. Stevens
Lena T. Stevens

APPROVED

Lester C. Landis
Chief, Review Branch
Div. of Photogrammetry

Will W. Swenson
Div. of Photogrammetry

May B. Kellett
Chief, Nautical Chart Branch
Division of Charts

W. B. Swell
Div. of Coastal Surveys

March 5, 1957 *mg*

FILE WITH DESCRIPTIVE REPORT OF SURVEY NO.

A basic hydrographic or topographic survey supersedes all information of like nature on the uncorrected chart.

1. **Letter** all information.
2. In "Remarks" column cross out words that do not apply.
3. Give reasons for deviations, if any, from recommendations made under "Comparison with Charts" in the Review.

FORM C&GS-0352 SUPERSEDES ALL EDITIONS OF FORM C&GS-975.